

# **5125TDRI-HK**


Project Name:	Fixture #
Project Number:	

## **Description:**

1-1/2" Schedule 40 PVC Testable Bath Drain with 3/4" Condensate Connection

#### **Features:**

- Testable Half Kit (Less Tee, Less Pipe, **Less Trim, with Test Devices)**
- **Angle Adapter**
- **Condensate Opening with** 3/4" solvent connection
- **Spin-on Tie Plate**










\*The "cCSAus Meets UPC" mark means the product conforms to the requirements of the NPC, UPC, IPC and IRC.

### **TESTING SPECIFICATIONS**



Test Plug Rating	25 PSI - Test Up To Four Floors
Flow Rate	8.25 GPM

#### Oakville Stamping and Bending Ltd.

2200 Speers Road, Unit C. Oakville, ON. Canada. L6L 2X8. T. 905.827.0320 or toll free 1.877.314.6040 F. 905.827.6375 or toll free 1.877.827.6040.