

RESOLUTION 2025-LL

**A RESOLUTION OF THE TOWN OF EATONVILLE, WASHINGTON,
AWARDING A BID FOR UPGRADES TO THE ASSOCIATED PETROLEUM
STORMDRAIN LINE TO SWICK & SONS ENTERPRISES, INC**

WHEREAS, the Town of Eatonville has a stormwater line that runs along the West side of Associated Petroleum to the Mill Village trailer court; and

WHEREAS, the existing pipe is old concrete pipe that has been damaged beyond repair by tree and plant roots causing it to drain poorly, which is causing flooding and is beginning to cause damage to adjacent properties; and

WHEREAS, the solution is to replace the concrete pipe with PVC piping that should alleviate the flooding; and

WHEREAS, the Town submitted bid requests to 3 contractors who stated they were interested and only one submitted a quote; and

WHEREAS, the Public Utilities Committee has reviewed and discussed the project and recommends moving forward; now, therefore;

**THE TOWN COUNCIL OF THE TOWN OF EATONVILLE, WASHINGTON,
HEREBY RESOLVES AS FOLLOWS:**

THAT: The Town Council approves, and the Mayor is authorized to move forward with the project as outlined in the estimate, attached hereto as Exhibit A, with Swick & Sons Enterprises, Inc in the amount of \$26,319.60.

PASSED by the Town Council of Town of Eatonville and attested by the Town Clerk in authentication of such passage this 8th day of September 2025.

David Baublits, Mayor

ATTEST:

Miranda Doll, Town Clerk

RESOLUTION 2025-LL

SWICK&SON ENTERPRISES, INC.

247 PO Box
Eatonville, WA 98328
+12533778225
swickandson@gmail.com



Estimate

ADDRESS
Town of Eatonville
Eatonville, WA 98328 US

ESTIMATE 1006
DATE 07/16/2025

JOB NAME-LOT NO
APP Stormwater Upgrade

JOB NAME AND NO
APP Stormwater Upgrade

ACTIVITY	QTY	RATE	AMOUNT
MISC CONSTRUCTION Mobilization	1	1,200.00	1,200.00T
MISC CONSTRUCTION Clear and Grub for storm install(includes haul off and disposal)	1	3,450.00	3,450.00T
catch basin Install Type 2 Catch Basin(supplied by town) On existing pipe, tie in new pipe, Mortar all pipes	1	4,680.00	4,680.00T
MISC CONSTRUCTION Remove and dispose of exisitng 120' of concrete pipe	1	4,280.00	4,280.00T
pipe Supply and install 120' sdr35 PVC storm	120	48.00	5,760.00T
5/8 MINUS Gravel supply and install for restoration	1	800.00	800.00T
MISC CONSTRUCTION Vac truck for work around fuel pumps	1	4,200.00	4,200.00T
SUBTOTAL			24,370.00
TAX			1,949.60
TOTAL			\$26,319.60

Accepted By

Accepted Date