

**PORT OF TACOMA  
TACOMA, WASHINGTON  
ON-CALL PAVEMENT REPAIRS (2026)**

**PROJECT NO. VARIOUS  
PROCUREMENT NO. 062026-1036**

**Thais Howard, PE  
Sr. Director, Engineering**

**Various  
Project Manager**

**END OF SECTION**

This page intentionally left blank

## **PROCUREMENT AND CONTRACTING REQUIREMENTS**

### DIVISION 00 -- PROCUREMENT AND CONTRACTING REQUIREMENTS

- 00 01 01 - Project Title Page
- 00 01 10 - Table of Contents
- 00 11 13 - Advertisement for Bids
- 00 21 00 - Instructions to Bidders
- 00 26 00 - Substitution Procedures
- 00 31 26 - Existing Hazardous Material Information
- 00 41 00 - Bid Form
- 00 43 13 - Bid Security Form
- 00 45 13 - Responsibility Detail Form
- 00 52 00 - Agreement Form
- 00 61 13.13 - Performance Bond
- 00 61 13.16 - Payment Bond
- 00 61 23 - Retainage Bond
- 00 61 23.13 - Retainage Escrow Agreement
- 00 72 00 - General Conditions
- 00 73 00 - Supplementary Conditions
- 00 73 16 - Insurance Requirements
- 00 73 46 - Washington State Prevailing Wage Rates
- 00 73 63 - Security Requirements

## **SPECIFICATIONS**

### DIVISION 01 -- GENERAL REQUIREMENTS

- 01 10 00 - Summary
- 01 14 00 - Work Restrictions
- 01 20 00 - Price and Payment Procedures
- 01 26 00 - Change Management Procedures
- 01 29 73 - Schedule of Values
- 01 30 00 - Administrative Requirements
- 01 31 23 - Web-Based Construction Management
- 01 33 00 - Submittal Procedures
- 01 35 29 - Health, Safety, and Emergency Response Procedures
- 01 35 43.13 - Hazardous Materials Handling Procedure
- 01 35 43.19 - Export Soil Management

- 01 35 47 - Air and Noise Control Procedures
- 01 35 91 - Historic/Cultural Treatment Resources
- 01 41 00 - Regulatory Requirements
- 01 42 19 - Reference Standards
- 01 45 00 - Quality Control
- 01 50 00 - Temporary Facilities and Controls
- 01 55 00 - Vehicular Access and Parking
- 01 57 13 - TESC and Project SWPPP
- 01 60 00 - Product Requirements
- 01 71 00 - Examination and Preparation
- 01 74 13 - Construction Cleaning
- 01 74 16 - Soil Characteristics and Waste Management
- 01 77 00 - Closeout Procedures

DIVISION 02 -- EXISTING CONDITIONS

- 02 41 00 - Site Preparation

DIVISION 03 -- CONCRETE

- 03 30 00 - Cast-in-Place Concrete

DIVISION 31 -- EARTHWORK

- 31 00 00 - Earthwork

DIVISION 32 -- EXTERIOR IMPROVEMENTS

- 32 12 16 - Asphalt Paving
- 32 17 23- Pavement Markings
- 32 31 13 - Chain Link Fences and Gates

APPENDICES

- Appendix A - Port of Tacoma Construction SWPPP Short Form

**END OF SECTION**

**ON-CALL PAVEMENT REPAIRS (2026)**

**PROJECT NO. VARIOUS | PROCUREMENT NO. 062026-1036**

- Scope of Work:** The Work required for this Project includes:  
Providing all labor, equipment, and materials necessary for paving, general civil, and fencing, alterations, additions, and repairs when requested by the Engineer on Port of Tacoma property. The Port does not guarantee a certain amount of work. The work will be assigned by Task Orders; each Task Order will address the scope of work and time of completion, and shall be performed in accordance with the Contract Documents and Task Order provisions.
- Bid Estimate:** Estimated cost range is Not to Exceed (NTE) \$1,500,000, plus Washington State Sales Tax (WSST).  
In accordance with RCW 39.04.320, fifteen (15) percent apprenticeship participation is required for certain projects estimated to cost one million (\$1,000,000) dollars or more. Bidders may contact the Department of Labor and Industries, Specialty Compliance Services Division, Apprenticeship Section, P.O. Box 44530, Olympia, WA 98504-4530, by phone (360) 902-5320, or e-mail at [Apprentice@lni.wa.gov](mailto:Apprentice@lni.wa.gov), to obtain information on available apprenticeship programs.  
In accordance with new legislation HB 1050 all port districts are required to add the requirement that **apprentices must perform** 15% or more of the total labor hours in public works contracts estimated at \$1 million or more. If the 15% apprenticeship labor hours is met the contractor will receive an incentive fee of \$1,000. If less than 15% apprenticeship labor hours is used a \$500 decrease in the total amount of the contract will be taken for not meeting the required apprenticeship labor hours. L&I will monitor apprenticeship labor hours.
- Sealed Bid Date/** Bids will be received at the Front Reception Desk, Port  
**Time/Location:** Administration Office, One Sitcum Plaza, Tacoma, Washington 98421 until **2:00 P.M. on 06/25/2026**, at which time they will be publicly opened and read aloud and the apparent low bid will be determined.
- Pre-Bid Conference**  
**and Site Tour:** No pre-bid or site visit is scheduled for this project.
- Bid Security:** Each Bid must be accompanied by a Bid security in an amount equal to five (5) percent of the Base Bid in a form allowed by the Instructions to Bidders.
- Contact**  
**Information:** Any questions to the Port may be submitted to the Procurement Department through the Procurement and Question Submission Portal (Portal link is accessible via this specific procurements website. See left side of page.). A direct link is also available here: [Procurement and Question Portal Link](#). No oral responses will be binding by the Port.

Instructions for utilizing the portal can be found here: [Procurement and Question Submission Portal Instructions](#).

Questions will not be accepted after seven (7) days prior to the Bid Date.

Bidding

Plans, Specifications, Addenda, and Plan Holders List for this

Documents:

Project are available on-line through The Port of Tacoma's Website portoftacoma.com. Click on "Contracts," "Procurement," and then the Procurement Number 062026-1036. Bidders must subscribe to the Holder's List on the right hand side of the screen in order to receive automatic email notification of future addenda and to be placed on the Holder's List.

Holder's Lists will be updated regularly and posted to the specific procurements page. Additional Instructions available in Section 00 21 00 - Instructions to Bidders.

Public Works

Effective July 1, 2019, all businesses are required to have training

Training

before bidding on public works projects and prevailing wage under

Requirements:

RCW 39.04.359 and RCW 39.12, or is on the list of exempt businesses maintained by the Department of Labor and Industries. The bidder must designate a person or persons to be trained on these requirements. The training will be provided by the Department of Labor and Industries or by a training provider whose curriculum is approved by the Department of Labor and Industries. Please refer to Labor and Industries' web site ([https://www.lni.wa.gov/TradesLicensing/PrevWage/Contractors/Training.asp?utm\\_medium=email&utm\\_source=govdelivery](https://www.lni.wa.gov/TradesLicensing/PrevWage/Contractors/Training.asp?utm_medium=email&utm_source=govdelivery)) for more information and training dates, requirements, and exemptions. Failure to attend this training could result in a determination of "not responsible" and the bidder not being awarded a public works contract.

Cooperative  
Purchasing

RCW 39.34 allows cooperative purchasing between public agencies in the State of Washington. Public agencies that file an Interlocal Joint Purchasing Agreement with the Port of Tacoma may wish to procure the public work herein offered by the selected Contractor. The selected Contractor shall extend the same cost, terms, and conditions offered to the Port of Tacoma to the Northwest Seaport Alliance under a separate agreement, contract, or purchase order(s). The Port of Tacoma is not liable in any regard for such agreement, contracts, or purchase orders. Each public agency accepts responsibility for compliance with any additional or varying laws and regulations governing public work by or on behalf of the public agency. The Port of Tacoma accepts no responsibility for the performance of the Contractor in providing public work to the Northwest Seaport Alliance, nor any responsibility for the payment price to the Contractor for the Northwest Seaport Alliance's purchases.

**END OF SECTION**

## **PART 1 - SUMMARY**

### **1.01 DEFINITIONS**

All definitions set forth in the Agreement, the General Conditions of the Contract for Construction, and in other Contract Documents are applicable to the Bidding Documents.

- A. "Addenda" are written or graphic instruments issued prior to the execution of the Contract which modify or interpret the Bidding Documents by additions, deletions, clarifications, or corrections. The contents of an Addendum are issued in no particular order and therefore should be carefully and completely reviewed.
- B. An "Additive Bid" (or "Additive") is an amount stated in the Bid to add specified features of the Work.
- C. An "Alternate Bid" (or "Alternate") is an amount stated in the Bid to be added to or deducted from the amount of the Base Bid if the corresponding change in the Work, as described in the Bidding Documents, is accepted.
- D. An "Apprentice" is a worker for whom an apprenticeship agreement has been registered and approved by the Washington State Apprenticeship and Training Council (RCW 49.04 and WAC 296-05).
- E. "Award" means the formal decision by the Port of Tacoma ("Port") notifying a Responsible Bidder with the lowest responsive Bid of the Port's acceptance of their Bid and intent to enter into a Contract with the Bidder.
- F. The "Award Requirements" include the statutory requirements as a condition precedent to Award.
- G. The "Base Bid" is the sum stated in the Bid for which the Bidder offers to perform the Work described in the Bidding Documents as the base to which Work may be added or from which Work may be deleted for sums stated in Alternate Bids.
- H. A "Bid" is a complete and properly signed proposal to do the Work, submitted in accordance with the Bidding Documents, for the sums therein stipulated and supported by any data called for by the Bidding Documents.
- I. The "Bid Date" is the day and hour specified in the Bidding Documents, as may be changed through an Addendum, by which Bidders are required to submit Bids to the Port.
- J. The "Bid Form" is the form(s) included with the Bidding Documents, with Specification Section 00 41 00, through which a Bidder submits a Bid.
- K. A "Bidder" is a person or entity who submits a Bid.
- L. The "Bidding Documents" include the Advertisement or Invitation to Bid, Instructions to Bidders, the Bid Form, any other sample bidding and contract forms, including those provided by reference, the Bid security, and the proposed Contract Documents, including any Addenda issued prior to the Bid Date.
- M. The "Contract Documents" proposed for the Work consist of the Agreement, the General Conditions of the Contract (as well as any Supplemental, Special, or other conditions included in the Project Manual), the Drawings, the Specifications, and all Addenda issued prior to, and all modifications issued after, execution of the Contract.

- N. The "Schedule of Unit Prices" is a separate schedule on the Bid Form for Unit Pricing as an all-inclusive price per unit of measurement for materials, equipment, or services as described in the Bidding Documents or in the proposed Contract Documents for the optional use of the Port. Quantities are not predictions of amounts anticipated. The Port may, but is not obligated to, accept a Schedule of Unit Price if it accepts the Base Bid. The Schedule of Unit Prices are not factored into the evaluation of determining the low bid amount and are not included as part of the bid award amount.
- O. A "Sub-Bidder" is a person or entity of any tier who submits a bid or proposal to or through the Bidder for materials, equipment or labor for a portion of the Work.

#### 1.02 BIDDER'S REPRESENTATIONS

By making its Bid, each Bidder represents that:

- A. BIDDING DOCUMENTS. The Bidder has read and understands the Bidding Documents, and its Bid is made in accordance with them.
- B. PRE-BID MEETING. The Bidder has attended pre-Bid meeting(s) required by the Bidding Documents. Attendance at a mandatory meeting or training session means that, in the sole opinion of the Port, a Project representative of a Bidder has attended all or substantially all of such meeting or session.
- C. BASIS. Its Bid is based upon the materials, systems, services, and equipment required by the Bidding Documents, and is made without exception.
- D. EXAMINATION. The Bidder has carefully examined and understands the Bidding Documents, the Contract Documents including, but not limited to, any liquidated damages, insurance provisions, and the Project site, including any existing buildings, it has familiarized itself with the local conditions under which the Work is to be performed, has correlated its observations with the requirements of the proposed Contract Documents, and it has satisfied itself as to the nature, location, character, quality, and quantity of the Work, the labor, materials, equipment, goods, supplies, work, services, and other items to be furnished, and all other requirements of the Contract Documents. The Bidder has also satisfied itself as to the conditions and other matters that may be encountered at the Project site or that may affect performance of the Work or the cost or difficulty thereof, including, but not limited to, those conditions and matters affecting transportation, access, disposal, handling and storage of materials, equipment and other items; availability and quality of labor, water, electric power, and utilities; availability and condition of roads; climatic conditions and seasons; physical conditions at the Project site and the surrounding locality; topography and ground surface conditions; and equipment and facilities needed preliminary to, and at all times during, the performance of the Work. The failure of the Bidder to fully acquaint itself with any applicable condition or matter shall not in any way relieve the Bidder from the responsibility for performing the Work in accordance with, and for the Contract Sum and within the Contract Time provided for in, the Contract Documents.
- E. PROJECT MANUAL. The Bidder has checked its copies of the Project Manual (if any) with the table of contents bound therein to ensure the Project Manual is complete.
- F. SEPARATE WORK. The Bidder has examined and coordinated all Drawings, Contract Documents, and Specifications with any other contracts to be awarded separately from, but in connection with, the Work being Bid upon, so that the Bidder is fully informed as to conditions affecting the Work under the Contract being Bid upon.

- G. LICENSE REQUIREMENTS. The Bidders and Sub-Bidders are registered and hold all licenses required by the laws of Washington, including a certificate of registration in compliance with RCW 18.27, for the performance of the Work specified in the Contract Documents.
- H. CERTIFICATION. The Bidder verifies under penalty of perjury that the Bidder has not have been determined by a final and binding citation and notice of assessment issued by the Department of Labor and Industries or through a civil judgment entered by a court of limited or general jurisdiction to have willfully violated, as defined in RCW 49.48.082, any provision of Chapters 49.46, 49.48, or 49.52 RCW within the three (3) year period immediately preceding the Bid Date.
- I. NO EXCEPTIONS. Bids must be based upon the materials, systems, and equipment described and required by the Bidding Documents, without exception.

### 1.03 BIDDING DOCUMENTS

#### A. COPIES

- 1. Bidders may obtain complete sets of the Bidding Documents from The Port of Tacoma's Website [www.portoftacoma.com](http://www.portoftacoma.com). Click on "Contracts" then "Procurement."
- 2. Complete Sets. Bidders shall use complete sets of Bidding Documents in preparing Bids and are solely responsible for obtaining updated information. The Port does not assume any responsibility for errors or misinterpretations resulting from the use of incomplete and/or superseded sets of Bidding Documents.
- 3. Conditions. The Port makes copies of the Bidding Documents available only for the purpose of obtaining Bids on the Work and does not confer a license or grant permission for any other use.
- 4. Legible Documents. To the extent any Drawings, Specifications, or other Bidding Documents are not legible, it is the Bidder's responsibility to obtain legible documents.

#### B. INTERPRETATION OR CORRECTION OF BIDDING DOCUMENTS

- 1. Format. The Contract Documents are divided into parts, divisions, and sections for convenient organization and reference. Generally, there has been no attempt to divide the Specification sections into Work performed by the various building trades, any Work by separate contractors, or any Work required for separate facilities in, or phases of the Project.
- 2. Duty to Notify. Bidders shall promptly notify the Port in writing of any ambiguity, inconsistency, or error that they may discover upon examination of the Bidding Documents or of the site and local conditions.
- 3. Products and Installation. All Bidders shall thoroughly familiarize themselves with specified products and installation procedures and submit to the Port any objections (in writing) no later than seven (7) days prior to the Bid Date. The submittal of the Bid constitutes acceptance of products and procedures specified as sufficient, adequate, and satisfactory for completion of the Contract.
- 4. Written Request. Bidders requiring clarification or interpretation of the Bidding Documents shall make a written request to the Procurement Department through the Procurement and Question Submission Portal at least seven (7) days prior to the Bid Date (Portal link is accessible via this specific procurements website. See left side of page.). A direct link is also available here: [Procurement and Question Portal Link](#). No oral responses will be binding by the Port.

Instructions for utilizing the portal can be found here: [Procurement and Question Submission Portal Instructions](#).

5. Request to Modify Responsibility Criteria. No later than seven (7) days prior to the Bid Date, a potential Bidder may request in writing that the Port modify the Responsibility Criteria. The Port will evaluate the information submitted by the potential Bidder and respond before the Bid Date. If the evaluation results in a change of the Criteria, the Port will issue an Addendum identifying the new Criteria.
6. Addenda. The Bidder shall not rely on oral information provided at any pre-Bid meetings or during site visits. Verbal statements made by representatives of the Port are for informational purposes only. Any interpretation, correction, or change of the Bidding Documents will be made solely by written Addendum. Interpretations, corrections, or changes of the Bidding Documents made in any manner other than by written Addendum, including but not limited to, oral statements will not be binding, and Bidders shall not rely upon such statements, interpretations, corrections, or changes. The Port is not responsible for explanations or interpretations of the Bidding Documents other than in a written Addendum.
7. Site Visits. Any site visits are provided as a courtesy to potential Bidders to assist them in becoming familiar with the Project site conditions. However, only the Bidding Documents, including any issued Addenda, may be relied upon by Bidders.
8. Singular References. Reference in the singular to an article, device, or piece of equipment shall include as many of such articles, devices, or pieces as are indicated in the Contract Documents or as are required to complete the installation.
9. Utilities and Runs. The Bidder should assume that the exact locations of any underground or hidden utilities, underground fuel tanks, and plumbing and electrical runs may be somewhat different from any location indicated in the surveys or Contract Documents.

#### C. SUBSTITUTIONS

1. For substitutions during bidding, refer to Section 00 26 00 – Substitution Procedures.

#### D. ADDENDA

1. Distribution. All Addenda will be written and will be made available on the Port's website or any other source specified by the Port for the Project.
2. Copies. Copies of Addenda will be made available for inspection wherever Bidding Documents are on file for that purpose.
3. Verification and Acknowledgment of Receipt. Prior to submitting a Bid, each Bidder shall ascertain that it has received all Addenda issued. Each Bidder shall acknowledge its receipt and consideration of all Addenda in its Bid.

### 1.04 BIDDING PROCEDURE

#### A. FORM AND STYLE OF BIDS

1. Form. Bids (including required attachments) shall be submitted on forms identical to the Bid Form included with the Bidding Documents. No oral, email, or telephonic responses or modifications will be considered.
2. Entries on the Bid Form. All blanks on the Bid Form shall be filled in by typewriter, printer, or manually in ink.

3. Figures. All sums shall be expressed in figures, not words. Portions of the Bid Form may require the addition or multiplication of component bids to a total or the identification of component amounts within a total. In case of discrepancy between unit prices listed and their sum(s), the unit prices listed shall govern (rather than the sum).
4. Initial Changes. Any interlineation, alteration, or erasure shall be initialed by an authorized representative of the Bidder.
5. Bid Breakdown. The Bid Form may contain, for the Port's accounting purposes only, a breakdown of some or all of the components included in the Base Bid.
  - a. For lump-sum Bids, the total Contract Sum shall be submitted.
  - b. For unit-price Bids, a price shall be submitted for each item of the Work, an extension thereof, and, if requested, the total Contract Sum.
6. Alternates. All Alternates should be Bid. The Port reserves the right, but is not obligated, to reject any Bid on which all requested Alternates are not Bid. If no change in the Base Bid is required for an Alternate, enter "Zero" or "0." If there is no entry, the Bidder will be presumed to have made no offer to perform the Alternate. If it is not otherwise clear from the Bid or the nature of the Alternate, it will be presumed that the amount listed for an Alternate is additive rather than deductive.
7. Schedule of Unit Prices. All Unit Prices under this schedule shall be bid. The Port reserves the right, but is not obligated, to reject any Bid on which all requested Schedule of Unit Prices are not Bid.
8. No Conditions. The Bidder shall make no conditions or stipulations on the Bid Form, nor qualify its Bid in any manner.
9. Identity of Bidder. The Bidder shall include in the specified location on the Bid Form, the legal name of the Bidder and, if requested, a description of the Bidder as a sole proprietor, a partnership, a joint venture, a corporation, or another described form of legal entity. The Bid shall be signed by the person or persons legally authorized to bind the Bidder to a contract. The Port verifies signature authority on the Labor and Industries website under the contractor registration business owner information. If the business owner information is not current, the Bidder shall show proof of authority to sign at the request of the Port. A Bid submitted by an agent shall have a current power of attorney attached certifying the agent's authority to bind the Bidder.
10. Bid Amounts Do Not Include Sales Tax. The Work to be performed constitutes a "retail sale" as this term is defined in RCW 82.04.050. Thus, the Base Bid amount shall include in the sum stated all taxes imposed by law, EXCEPT WASHINGTON STATE AND LOCAL SALES TAX due on the Base Bid. The engaged Contractor will pay retail sales tax on all consumables used during the performance of the Work and on all items that are not incorporated into the final Work; this tax shall be included in the Base Bid price and in any other prices set forth on the Bid Form. The Port will pay state and local retail sales tax due on each progress payment and final payment to the engaged Contractor for transmittal by the Contractor to the Washington State Department of Revenue or to the applicable local government.

**B. POTENTIAL LISTING OF SUB-BIDDERS (SUBCONTRACTORS)**

1. Procedure. On projects equal to or greater than \$1,000,000, the Bid Form includes a requirement that certain Sub-Bidders be listed, in which case the Bidder must complete the required list. In these circumstances, and regardless of the anticipated cost of the Project, the Bidder must name the Sub-Bidder or Sub-Bidders with whom the Bidder, if awarded the Contract, will subcontract directly (i.e., not lower-tier Sub-Bidders) for performance of the Work of:
  - a. HVAC (heating, ventilation, and air conditioning) Work;
  - b. Plumbing Work as described in RCW 18.106;
  - c. Electrical Work as described in RCW 19.28; and
  - d. Any other categories of Work listed on the Sub-Bidder listing form and/or Bid Form.
2. Self-Performance. If the Bidder intends to self-perform any of these categories of Work, it must name itself for each such category of Work.
3. Multiple Entries. The Bidder shall not list more than one (1) entity for a particular category of Work identified, unless a Sub-Bidder will vary based on an Alternate Bid, in which case the Bidder shall identify the Sub-Bidder to be used for the Alternate and the affected portion of the Work.
4. Failure to Submit. In accordance with RCW 39.30.060, failure of a Bidder to submit, as part of the Bid, the names of such proposed HVAC, plumbing, and electrical Sub-Bidders, or to name itself to perform such Work, or the naming of two (2) or more Sub-Bidders to perform the same Work, shall render the Bidder's Bid non-responsive and; therefore, void.
5. Requirement to Subcontract. The Bidder, if Awarded the Contract, will subcontract with the listed Sub-Bidders for performance of the portion of the Work designated on the Bid Form, subject to the provisions of the Contract for Construction and RCW 39.30.060. The Bidder shall not substitute a listed Sub-Bidder in furtherance of bid shopping or bid peddling.
6. Sub-Bidder Qualification. Listed Sub-Bidders may be required to provide evidence of their qualifications, including a statement of experience and references, prior to Award, or at any time during the Contract Time. Such information shall be provided within twenty-four (24) hours of request. This evidence shall demonstrate that the Sub-Bidder meets or exceeds all requirements for experience, qualifications, manufacturer's certifications, or any other requirements specified in any of the technical sections of the Contract Documents for which the Sub-Bidder proposes to perform Work.
7. Replacement. If a listed Sub-Bidder fails to provide adequate evidence of qualifications, is unable to comply with any bonding requirements of the Bidding Documents or with other requirements of the Contract or Bidding Documents, is not properly licensed, or fails to meet the Responsibility Criteria of the Bidding Documents, the Port may require the Bidder to replace the Sub-Bidder with another subcontractor reasonably acceptable to the Port at no change in the Contract Sum or Contract Time.
8. Sub-Bidder Standards. Sub-Bidders shall meet contractual and technical qualification standards, and provide specialized certification, licensing, and/or payment and performance bonding, if required.

9. MWBE, Veteran-owned, and small business participation encouraged. The Port's policy is to encourage the Contractor to solicit and document participation, and to provide and promote the maximum lawful, practicable opportunity for increased participation, by MWBE firms certified by the Office of Minority and Women's Business Enterprises (OMWBE), Veteran-owned businesses (defined in RCW 43.60.010, and Small, Mini and Micro business enterprises (defined in RCW 39.26.010).

C. BID SECURITY

1. Purpose and Procedure. Each Bid shall be accompanied by Bid security payable to the Port in the form required by the Bidding Documents and equal to five (5) percent of the Base Bid only (i.e., not including any Alternates or Unit Prices). The Bid security constitutes a pledge by the Bidder to the Port that the Bidder will enter into the Contract with the Port in the form provided, in a timely manner, and on the terms stated in its Bid, and will furnish in a timely manner, the payment and performance bonds, certificates of insurance, and all other documents required in the Contract Documents. Should the Bidder fail or refuse to enter into the Contract or fail to furnish such documents, the amount of the Bid security shall be forfeited to the Port as liquidated damages, not as a penalty. By submitting a Bid, each Bidder represents and agrees that the Bid security, if forfeited, is a reasonable prediction on the Bid Date of future damages to the Port. Failure of the Bidder to provide Bid Security as required shall render the bid non-responsive.
2. Form. The Bid security shall be in the form of a certified or bank cashier's check payable to the Port or a Bid bond executed by a bonding company reasonably acceptable to the Port, licensed in the State of Washington, registered with the Washington State Insurance Commissioner, possess an A.M. Best rating of "A-," Fiscal Size Category (FSC) six (6) or better, and be authorized by the U.S. Department of the Treasury. The Bid security shall be signed by the person or persons legally authorized to bind the Bidder. Bid bonds shall be submitted using the form included with the Bidding Documents.
3. Retaining Bid Security. The Port will have the right to retain the Bid security of Bidders to whom an Award is being considered until the earliest of either: (a) mutual execution of the Contract, and the Port's receipt of payment and performance bonds, (b) the specified time has elapsed so that Bids may be withdrawn, or (c) when all Bids have been rejected.
4. Return of Bid Security. Within sixty (60) days after the Bid Date, the Port will release or return Bid securities to Bidders whose Bids are not to be further considered in awarding the Contract. Bid securities of the three apparent low Bidders will be held until the Contract has been finally executed, after which all un-forfeited Bid securities will be returned. Bid security may be returned in the form provided or by separate payment.

D. SUBMISSION OF BIDS

1. Procedure. The Bid, the Bid security, and other documents required to be submitted with the Bid, shall be enclosed in a sealed envelope identified with the Project name and number and the Bidder's name and address. If the Bid is sent by mail, the sealed envelope shall be enclosed in a separate mailing envelope with the notation "SEALED BID ENCLOSED" on the face of the mailing envelope.
  - a. If a Bid is mailed, it shall be addressed to the Port of Tacoma, Contracts Department, 1 Sitcum Plaza, Tacoma, WA 98421.
  - b. If a Bid is delivered, it shall be delivered to the Front Reception Desk, Port of Tacoma, 1 Sitcum Plaza, Tacoma, WA 98421.

- c. The time stamp clock at the Front Reception Desk at 1 Sitcum Plaza is the Port's official clock.
2. Deposit. Bids shall be deposited at the designated location prior to the Bid Date indicated in the Advertisement or Invitation to Bid, or any extension thereof made by Addendum. Bids received after the Bid Date and time specified shall be returned without consideration at the discretion of the Port, or rejected at the time of receipt.
3. Delivery. The Bidder assumes full responsibility for timely delivery at the location designated for receipt of Bids.
4. Form. Oral, facsimile, telephonic, electronic, or email Bids are invalid and will not be considered.

E. MODIFICATION OR WITHDRAWAL OF BID

1. After the Bid Date. A Bid may not be modified, withdrawn, or canceled by the Bidder during a ninety (90) day period following the Bid Date, and each Bidder so agrees by virtue of submitting its Bid.
2. Before the Bid Date. Prior to the Bid Date, any Bid submitted may be modified or withdrawn only by notice to the party receiving Bids at the place designated for receipt of Bids. The notice shall be in writing, with the signature of the Bidder, and shall be worded so as not to reveal the amount of the original Bid. Email notice will not be accepted. It shall be the Bidder's sole responsibility to verify that the notice has been received by the Port in time to be withdrawn before the Bid opening.
3. Resubmittal. Withdrawn Bids may be resubmitted up to the time designated for the receipt of Bids, provided that they are then fully in conformance with these Instructions to Bidders.
4. Bid Security with Resubmission. Bid security shall be in an amount sufficient for the Bid as modified or resubmitted.

F. COMMUNICATIONS

1. Communications from a Bidder related to these Instructions to Bidders must be in writing to the Procurement Department through the Procurement and Question Submission Portal (Portal link is accessible via this specific procurements website. See left side of page.). A direct link is also available here: [Procurement and Question Portal Link](#). Communications, including but not limited to, notices and requests by Sub-Bidders shall be made through the Bidder and not directly by a Sub-Bidder to the Port. No oral responses will be binding by the Port.

Instructions for utilizing the portal can be found here: [Procurement and Question Submission Portal Instructions](#).

1.05 CONSIDERATION OF BIDS

- A. OPENING OF BIDS. Unless stated otherwise in the Advertisement or Invitation to Bid or an Addendum, the properly identified Bids received on time will be opened publicly and will be read aloud. An abstract of the Base Bids and any Alternate Bids will promptly (and generally within twenty-four (24) hours) be made available to Bidders and other interested parties.
- B. REJECTION OF BIDS. The Port shall have the right, but not the obligation, to reject any or all Bids for any reason, or for no reason, to reject a Bid not accompanied by the required Bid security, or to reject a Bid which is in any way incomplete or irregular.

- C. BIDDING MISTAKES. The Port will not be obligated to consider notice of claimed Bid mistakes received more than twenty-four (24) hours after the Bid Date. In accordance with Washington law, a low Bidder that claims error and fails to enter into the Contract is prohibited from Bidding on the Project if a subsequent call for Bids is made for the Project.
- D. ACCEPTANCE OF BID (AWARD)
1. Intent to Accept. The Port intends, but is not bound, to Award a Contract to the Responsible Bidder with the lowest responsive Bid, provided the Bid has been submitted in accordance with the requirements of the Bidding Documents and does not exceed the funds available. The Port has the right to waive any informality or irregularity in any Bid(s) received and to accept the Bid which, in its judgment, is in its own best interests.
  2. Alternates. The Port shall have the right to accept Alternates in any order or combination, unless otherwise specifically provided in the Contract or Bidding Documents, and to determine the low Bidder on the basis of the sum of the Base Bid and the Alternates (if any) accepted. Failure to submit Bids on all Alternates may be cause for rejecting the Bidder's entire Bid. The Port retains the right to accept Alternate Bid items at the price Bid within ninety (90) days after the Contract is executed.
  3. Requirements for Award. Before the Award, the lowest responsive Bidder must be deemed Responsible by the Port and must satisfy all Award Requirements.
- E. BID PROTEST PROCEDURES
1. Procedure. A Bidder protesting, for any reason, the Bidding Documents, a Bidding procedure, the Port's objection to a Bidder or a person or entity proposed by the Bidder, including but not limited to, a finding of non-Responsibility, the Award of the Contract or any other aspect arising from, or relating in any way to, the Bidding, shall cause a written protest to be filed with the Port within two (2) business days of the event giving rise to the protest. (Intermediate Saturdays, Sundays, and legal holidays are not counted as business days.) The written protest shall include the name of the protesting Bidder, the bid solicitation number and title under which the protest is submitted, a detailed description of the specific factual and legal grounds for the protest, copies of all supporting documents, evidence that the apparent low bidder has been given notice of the protest, and the specific relief requested. The written protest shall be sent by email to [procurement@portoftacoma.com](mailto:procurement@portoftacoma.com).
  2. Consideration. Upon receipt of the written protest, the Port will consider the protest. The Port may, within three (3) business days of the Port's receipt of the protest, provide any other affected Bidder(s) the opportunity to respond in writing to the protest. If the protest is not resolved by mutual agreement of the protesting Bidder and the Port, the Contracts Director of the Port, or his or her designee, will review the issues and promptly furnish a final and binding written decision to the protesting Bidder, and any other affected Bidder(s), within six (6) business days of the Port's receipt of the protest. (If more than one (1) protest is filed, the Port's decision will be provided within six (6) business days of the Port's receipt of the last protest.) If no reply is received from the Port during the six (6) business-day period, the protest will be deemed rejected.
  3. Waiver. Failure to comply with these protest procedures will render a protest waived.
  4. Condition Precedent. Timely and proper compliance with, and exhaustion of, these protest procedures shall be a condition precedent to any otherwise permissible judicial consideration of a protest.

## 1.06 POST BID INFORMATION

### A. THE LOWEST RESPONSIVE BIDDER SHALL:

1. Responsibility Detail Form. Within 24 hours of the Low Responsive Bidder Selection Notification, the apparent low Bidder shall submit to the Port the Responsibility Detail Form and other required documents (Section 00 45 13) executed by an authorized company officer. As requested from the Port, the low responsive Bidder shall provide written confirmation that the person signing the Bid on behalf of the Bidder was duly authorized at the time of bid, a detailed breakdown of the Bid in a form acceptable to the Port, and other information required by the Port.
2. The apparent low Bidder shall submit to the Port upon request:
  - a. Additional information regarding the use of the Bidder's own forces and the use of subcontractors and suppliers;
  - b. The names of the persons or entities (including a designation of the Work to be performed with the Bidder's own forces, and the names of those who are to furnish materials or equipment fabricated to a special design) proposed for each of the principal portions of the Work (i.e., either a listed Sub-Bidder or a Sub-Bidder performing Work valued at least ten (10) percent of the Base Bid), consistent with the listing required with the Bid; and
  - c. The proprietary names and the suppliers of the principal items or systems of materials and equipment proposed for the Work.
3. Failure to provide any of the above information in a timely manner will constitute an event of breach permitting forfeiture of the Bid security.
4. Bidder Responsibility. The Bidder will be required to establish, to the satisfaction of the Port, the reliability and responsibility of itself and the persons or entities proposed to furnish and perform the Work described in the Bidding Documents. If requested, the Bidder shall meet with the Port to discuss the Bid, including any pricing, the Bid components, and any assumptions made by the Bidder.
5. Sub-Bidder Responsibility. The Responsibility of the Bidder may be judged in part by the Responsibility of Sub-Bidders. Bidders must verify the Responsibility Criteria for each first-tier Sub-Bidder. A Sub-Bidder of any tier that hires other Sub-Bidders must verify Responsibility Criteria for each of its lower-tier Sub-Bidders. The verification shall include a representation that each Sub-Bidder, at the time of subcontract execution, is Responsible and possesses required licenses.
6. Objection. Prior to an Award of the Contract, the Port will notify the Bidder in writing if the Port, after due investigation, has reasonable objection to the Bidder or a person or entity proposed by the Bidder. Upon receiving such objection, the Bidder may, at Bidder's option: (a) withdraw their Bid, (b) submit an acceptable substitute person or entity with no change in the Contract Time and no adjustment in the Base Bid or any Alternate Bid, even if there is a cost to the Bidder occasioned by such substitution, or (c) file a protest in accordance with the Bidding Documents.
7. Change. Persons and entities proposed by the Bidder to whom the Port has made no reasonable objection must be used on the Work for which they were proposed and shall not be changed, except with the written consent of the Port.

8. Right to Terminate. The Bidder's representations concerning its qualifications will be construed as a covenant under the Contract. If a Bidder makes a material misrepresentation on a Qualification Statement, the Port has the right to terminate the Contract for cause and may then pursue any remedies that exist under the Contract or that are otherwise available.

B. INFORMATION FROM OTHER BIDDERS: All other Bidders designated by the Port as under consideration for Award of a Contract shall also provide a properly executed Qualification Statement, if so requested by the Port.

#### 1.07 PERFORMANCE BOND, LABOR AND MATERIAL PAYMENT BOND, AND INSURANCE

A. BOND REQUIREMENTS. Within ten (10) days after the Port's Notice of Award of the Contract, the successful Bidder shall obtain and furnish statutory bonds pursuant to RCW 39.08 covering the faithful performance of the Contract and the payment of all obligations arising thereunder in the form and amount prescribed in the Contract Documents. Bonds shall be written for one hundred (100) percent of the contract award amount, plus Washington State Sales Tax and Change Orders. The cost of such bonds shall be included in the Base Bid.

1. On contracts of one hundred fifty thousand dollars (\$150,000) or less, at the option of the Contractor or the General Contractor/Construction Manager as defined in RCW 39.10.210, the Port may, in lieu of the bond, retain ten (10) percent of the contract amount for a period of thirty days after date of final acceptance, or until receipt of all necessary releases from the department of revenue, the employment security department, and the department of labor and industries and settlement of any liens filed under RCW 60.28, whichever is later. The recovery of unpaid wages and benefits must be the first priority for any actions filed against retainage held by a state agency or authorized local government.

2. On contracts of one hundred fifty thousand dollars (\$150,000) or less, the Port may accept a full payment and performance bond from an individual surety or sureties.

B. TIME OF DELIVERY AND FORM OF BONDS. The successful Bidder shall deliver an original copy of the required bonds to the Port, 1 Sitcum Plaza, Tacoma, WA 98421, within the time specified in the Contract Documents.

C. INSURANCE. The successful Bidder shall deliver a certificate of insurance from the Bidder's insurance company that meets or exceeds all requirements of the Contract Documents.

D. GOVERNMENTAL REQUIREMENTS. Notwithstanding anything in the Bidding or Contract Documents to the contrary, the Bidder shall provide all bonding, insurance, and permit documentation as required by governmental authorities having jurisdiction for any portions of the Project.

#### 1.08 FORM OF AGREEMENT

A. FORM TO BE USED. The Contract for the Work will be written on the form(s) contained in the Bidding Documents, including any General, Supplemental, or Special Conditions, and the other Contract Documents included with the project manual.

B. CONFLICTS. In case of conflict between the provisions of these Instructions and any other Bidding Document, these Instructions shall govern. In case of conflict between the provisions of the Bidding Documents and the Contract Documents, the Contract Documents shall govern.

C. CONTRACT DELIVERY. Within ten (10) days after Notice of Award, the Bidder shall submit a signed Contract to the Port in the form tendered to the Bidder and without modification.

**PART 2 - PRODUCTS - NOT USED**

**PART 3 - EXECUTION - NOT USED**

**END OF SECTION**

## **PART 1 - GENERAL**

### 1.01 SUMMARY

- A. This Section includes administrative and procedural requirements for substitutions.

### 1.02 DEFINITIONS/CLARIFICATIONS

- A. Substitutions. Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.
- B. The Contract Documents include performance specifications for products and equipment which meet Project requirements. In those cases where a representative item or manufacturer is named in the specification, it is provided for the sole purpose of identifying a product meeting the required functional performance, and where the words "or equal" are used, a substitution request as further described, is not required.
- C. Where non-competitive or sole source products or manufacturers are explicitly specified with the words "or approved equal," or "Engineer approved equal," or "as approved by the Engineer" are used, they shall be taken to mean "or approved equal." In these cases a substitution request as further described in this Section, is required.

### 1.03 SUBMITTALS

- A. Substitution Request Form. Use copy of form located at the end of this Section.
- B. Pre-Bid Substitution Requests. Submit one (1) PDF of the Substitution Request Form along with all supporting documentation for consideration of each request. Identify product, fabrication, or installation method to be replaced. Include Drawing numbers and titles. Substitution requests prior to the Bid Date may originate directly from a prime Bidder, or from a prospective Sub-Bidder.
  - 1. Documentation. Show compliance with requirements for substitutions with the following, as applicable:
    - a. Statement indicating why specified product, fabrication, or installation cannot be provided.
    - b. Coordination information, including a list of changes or modifications needed to other parts of the Work that will be necessary to accommodate proposed substitution.
    - c. Product Data, including drawings and descriptions of products, fabrication, and installation procedures.
    - d. Samples, where applicable or requested.
    - e. Certificates and qualification data, where applicable or requested.
    - f. Research reports evidencing compliance with building code in effect for the Project.
  - 2. Engineer's Action. Engineer will review substitution requests if received through the Procurement and Question Submission Portal at least seven (7) days prior to the Bid Date (Portal link is accessible via this specific procurements website. See left side of page.) A direct link is also available here: [Procurement and Question Portal Link](#). No oral responses will be binding by the Port.
    - a. Forms of Acceptance. Substitution requests will be formally accepted via written addendum prior to the Bid Date. Bidders shall not rely upon approvals made in any other manner.

- b. Use product originally specified if Engineer does not issue a decision on use of a proposed substitution within time allocated.
- c. The Port's decision of approval or disapproval of a proposed substitution shall be final.

Instructions for utilizing the portal can be found here: [Procurement and Question Submission Portal Instructions](#).

- C. Post-Award Substitution Requests must be submitted by the Contractor and not a Subcontractor nor Supplier.
  - 1. Documentation. Show compliance with requirements for substitutions with the following, as applicable:
    - a. Statement indicating why specified product or fabrication or installation cannot be provided, if applicable.
    - b. Coordination information, including a list of changes or modifications needed to other parts of the Work that will be necessary to accommodate proposed substitution.
    - c. Detailed comparison of significant qualities of proposed substitution with those of the Work specified. Include annotated copy of applicable specification Section. Significant qualities may include, but are not limited to, attributes such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
    - d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
    - e. Samples, where applicable or requested.
    - f. Certificates and qualification data, where applicable or requested.
    - g. List of similar installations for completed projects with project names and addresses. Also provide names and addresses of the applicable architect, engineer, and owner.
    - h. Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.
    - i. Research reports evidencing compliance with building code in effect for the Project.
    - j. Comparison of the approved Baseline Project Schedule using proposed substitution with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
    - k. Cost information, including a proposal of change, if any, in the Contract Sum.
    - l. Contractor's certification that proposed substitution complies with requirements in the Contract Documents except as indicated in substitution request, is compatible with related materials, and is appropriate for applications indicated.
    - m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.

2. Engineer's Action. If necessary, Engineer will request additional information or documentation for evaluation within seven (7) calendar days of receipt of a request for substitution. Engineer will notify Contractor through Port of acceptance or rejection of proposed substitution within fifteen (15) calendar days of receipt of request, or seven (7) calendar days of receipt of additional information or documentation, whichever is later.
  - a. Forms of Acceptance. Change Order or Minor Change in Work.
  - b. Use product originally specified if Engineer does not issue a decision on use of a proposed substitution within time allocated.
3. Substitutions for Cause. Submit requests for substitution immediately upon discovery of need for change, but not later than fourteen (14) days prior to date required for preparation and review of related submittals.
  - a. Conditions. Engineer will consider Contractor's request for substitution when the following conditions are satisfied:
    - 1) Requested substitution is consistent with the Contract Documents and will produce indicated results.
    - 2) Requested substitution will not adversely affect the Baseline Project Schedule.
    - 3) Requested substitution has received necessary approvals of authorities having jurisdiction.
    - 4) Requested substitution is compatible with other portions of the Work.
    - 5) Requested substitution has been coordinated with other portions of the Work.
    - 6) Requested substitution provides specified warranty.
    - 7) If requested substitution involves more than one (1) contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.
4. Substitutions for Convenience. Engineer will consider Contractor's requests for substitution if received within fourteen (14) days after the Notice of Award.
  - a. Conditions. Engineer will consider Contractor's request for substitution when the following conditions are satisfied:
    - 1) Requested substitution offers Port a substantial advantage in cost, time, energy conservation, or other considerations, after deducting additional responsibilities Port must assume. Port's additional responsibilities may include compensation to Engineer for redesign and evaluation services, increased cost of other construction by Port, and similar considerations.
    - 2) Requested substitution does not require extensive revisions to the Contract Documents.
    - 3) Requested substitution is consistent with the Contract Documents and will produce indicated results.
    - 4) Requested substitution will not adversely affect the Baseline Project Schedule.
    - 5) Requested substitution has received necessary approvals of authorities having jurisdiction.

- 6) Requested substitution is compatible with other portions of the Work.
- 7) Requested substitution has been coordinated with other portions of the Work.
- 8) Requested substitution provides specified warranty.
- 9) If requested substitution involves more than one (1) contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

D. Substitutions will not be considered when:

1. Indicated or implied on shop drawings or product data submittals without formal request submitted in accordance with this Section.
2. Acceptance will require substantial revision of Contract Documents or other items of the Work.
3. Submittal for substitution request does not include point-by-point comparison of proposed substitution with specified product.

1.04 QUALITY ASSURANCE

- A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials.

**PART 2 - PRODUCTS - NOT USED**

**PART 3 - EXECUTION - NOT USED**

---

**PROJECT TITLE: On-Call Pavement Repairs (2026)**      **PROJECT NO.: Various**  
SUBMITTED BY: \_\_\_\_\_ CONTRACT NO.: 062026-1036  
PRIME/SUB/SUPPLIER: \_\_\_\_\_ DATE: \_\_\_\_\_

-----  
Specification Title: \_\_\_\_\_ Section No.: \_\_\_\_\_  
Description: \_\_\_\_\_ Paragraph: \_\_\_\_\_  
Page No.: \_\_\_\_\_

-----  
Proposed Substitution: \_\_\_\_\_  
Trade Name: \_\_\_\_\_ Model No.: \_\_\_\_\_  
Manufacturer: \_\_\_\_\_  
Address: \_\_\_\_\_ Phone No.: \_\_\_\_\_  
Installer: \_\_\_\_\_  
Address: \_\_\_\_\_ Phone No.: \_\_\_\_\_  
Differences between proposed substitution and specified product: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Point-by-Point comparative data attached - REQUIRED

-----  
Reason for not providing specified item: \_\_\_\_\_  
\_\_\_\_\_

Similar Installation:  
Project: \_\_\_\_\_ A/E: \_\_\_\_\_  
Address: \_\_\_\_\_  
Owner: \_\_\_\_\_ Date Installed: \_\_\_\_\_  
Proposed substitution affects other parts of Work:  No  Yes; explain \_\_\_\_\_

-----  
Supporting Data Attached:  
 Drawings  Product Data  Samples  Tests  Reports  Other: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

-----  
Applicable to Substitution Requests During Construction:  
Proposed to Port for accepting substitution: \$ \_\_\_\_\_  
Proposed substitution changes Contract Time:  No  Yes [Add] [Deduct] \_\_\_\_\_ # days.  
-----

The Undersigned certifies:  
• Proposed substitution has been fully investigated and determined to be equal or superior in all respects to specified product.

- Same warranty will be furnished for proposed substitution as for specified product.
- Same maintenance service and source of replacement parts, as applicable, is available.
- Proposed substitution will have no adverse effect on other trades and will not affect or delay Baseline Project Schedule.
- Cost data as stated above is complete. Claims for additional costs related to accepted substitution which may subsequently become apparent are to be waived.
- Proposed substitution does not affect dimensions and functional clearances.
- Payment will be made for changes to building design, including A/E design, detailing, and construction costs caused by the substitution.
- Coordination, installation, and changes in the Work as necessary for accepted substitution will be complete in all respects.

---

Submitted By: \_\_\_\_\_  
Signed By: \_\_\_\_\_ Firm: \_\_\_\_\_  
Address: \_\_\_\_\_  
Telephone: \_\_\_\_\_ Email: \_\_\_\_\_  
Attachments: \_\_\_\_\_

---

**A/E's REVIEW AND RECOMMENDATION**

- Approved Substitution
- Approved Substitution as Noted
- Reject Substitution - Use specified materials.
- Substitution Request received too late - Use specified materials.

Signed by: \_\_\_\_\_ Date: \_\_\_\_\_

---

**ENGINEER'S REVIEW AND ACTION**

- Substitution Approved - Make submittals in accordance with this Specification Section. If during construction, prepare Change Order.
- Substitution Approved as Noted - Make submittals in accordance with this Specification Section. If during construction, prepare Change Order.
- Substitution Rejected - Use specified materials.
- Substitution Request received too late - Use specified materials.

Signed by: \_\_\_\_\_ Date: \_\_\_\_\_

**END OF SECTION**

---

**PART 1 - GENERAL**

1.01 SUMMARY

- A. This Section provides the notification required for disclosure of asbestos, lead-containing or other hazardous materials.

1.02 HAZARDOUS MATERIALS NOTICE

- A. The Port is reasonably certain that asbestos and lead will not be disturbed by the project. If the Contractor encounters material suspected of containing lead or asbestos which will interfere with the execution of the work, the Contractor shall stop work and notify the Engineer.

**PART 2 - PRODUCTS - NOT USED**

**PART 3 - EXECUTION - NOT USED**

**END OF SECTION**

This page intentionally left blank

**BIDDER'S NAME:** \_\_\_\_\_

**PROJECT TITLE: ON-CALL PAVEMENT REPAIRS (2026)**

The undersigned Bidder declares that it has read the Contract Documents (including documents provided by reference), understands the conditions under which the Work will be performed, has examined the Project site, and has determined for itself all situations affecting the Work herein Bid upon. Bidder proposes and agrees, if this Bid is accepted, to provide at Bidder's own expense, all labor, machinery, tools, materials, etc., including all Work incidental to, or described or implied as incidental to such items, according to the Contract Documents, and that the Bidder will complete the Work within the time stated, and that Bidder will accept in full the lump sum or unit price(s) set forth below:

ITEM NO.		DESCRIPTION OF ITEM	UOM	QTY	UNIT PRICE	EXTENDED PRICE (QTY. x UNIT PRICE)
1	-	Mobilization & Demobilization	EA	15		
2	-	Mobilization & Demobilization (Nights & Weekends)	EA	10		
3	Less than 50	Asphalt Paving	TON	25		
4	Less than 150	Asphalt Paving	TON	100		
5	Less than 300	Asphalt Paving	TON	275		
6	300 or Greater	Asphalt Paving	TON	400		
7	Less than 50	Asphalt Paving (Nights & Weekends)	TON	40		
8	Less than 150	Asphalt Paving (Nights & Weekends)	TON	75		
9	Less than 300	Asphalt Paving (Nights & Weekends)	TON	250		
10	300 or Greater	Asphalt Paving (Nights & Weekends)	TON	450		
11	Less than 20	Concrete Repair	CY	10		
12	More than 20	Concrete Repair	CY	50		
13	-	Crushed Surfacing Base Course	TON	100		
14	-	Crushed Surfacing Top Course	TON	100		
15	-	Gravel Base	TON	15		
16	-	Gravel Borrow	TON	5		
17	-	Excavation	CY	100		
18	-	Excavation (Nights & Weekends)	CY	50		
19	-	Geotextile	SY	15		
20	-	Management of Regulated (Subtitle D)	CY	40		
21	-	Crack Sealant	LF	2500		

22	12" Thickness or Less	Concrete Saw Cutting	LF	200		
23	Greater than 12" Thickness	Concrete Saw Cutting	LF	100		
24	-	Concrete Removal	CY	75		
25	8" Thickness or less	Asphalt Saw Cutting	LF	500		
26	4" Thickness or Less	Asphalt Removal	SY	50		
27	Greater than 4" Thickness	Asphalt Removal	SY	25		
28	4" Thickness or Less	Asphalt Removal (Nights & Weekends)	SY	100		
29	Greater than 4" Thickness	Asphalt Removal (Nights & Weekends)	SY	100		
30	4" Thickness or Less	Profiling/Grinding Asphalt	SY	500		
31	Greater than 4" Thickness	Profiling/Grinding Asphalt	SY	1750		
32	4" Thickness or Less	Profiling/Grinding Asphalt (Nights & Weekends)	SY	375		
33	Greater than 4" Thickness	Profiling/Grinding Asphalt (Nights & Weekends)	SY	1500		
34	-	Asphalt Seal Coat	SY	2500		
34	-	Striping	LF	1000		
36	-	Striping (Nights & Weekends)	LF	500		
37	-	Other Striping & Painting (Speed Bumps, Disabled Parking)	SF	50		
38	-	Skid-Steer Loader with Attachment and Operator	HR	40		
39	-	Street Sweeper with Driver	HR	40		
40	-	Water Truck with Driver	HR	80		
41	-	Water Truck with Driver (Nights & Weekends)	HR	40		
42	-	Dump Truck with Driver	HR	80		
43	-	Dump Truck with Driver (Nights & Weekends)	HR	32		
44	-	Embedded Structures (Manhole Ring and Cover Adjustment)	EA	5		

45	-	Embedded Structures (Valve Box Adjustment)	EA	3		
46	-	Embedded Structures (Catch Basin Frame and Grate Adjustment)	EA	5		
47	-	Plant Opening Fees	EA	5		

10.4% WASHINGTON STATE SALES TAX (WSST) ON BASE BID SUBTOTAL	
TAX-EXEMPT BASE BID SUBTOTAL	
BID TOTAL (WITH WSST)	

Note: Show prices in figures only.

Evaluation of Bids. In accordance with the provisions of the Contract Documents, Bids will be evaluated to determine the lowest Base Bid Subtotal offered by a responsible Bidder submitting a responsive Bid.

Schedule of Unit Prices. The unit prices are proposed to apply only in the event of additions to, or deletions from, the work required and ordered. All prices shall include complete installation without Washington State Sales Tax. The bidder shall propose a price for each item; failure to propose a price for each item may render the bid non-responsive. The Port reserves the right to accept or reject the unit prices proposed.

Trench Excavation Safety Provision. If the bid amount contains work which requires trenching exceeding a depth of four (4) feet, all costs for trench safety shall be included in the Base Bid and indicated below for adequate trench safety systems in compliance with RCW 39.04 and WAC 296-155-650. Bidder shall include a lump sum amount, excluding Washington State Sales Tax. If trench excavation safety provisions do not pertain to the Work, the Bidder should enter "N.A." or "Not Applicable" in the blank below.

Trench Excavation Safety: \_\_\_\_\_ (Total in Written Figures Only)

Work to be Performed:	Name of Firm:	Subcontractor License Number:
HVAC (Heating, Ventilation, and Air Conditioning) Work		
Plumbing Work as described in RCW 18,106		
Electrical Work as described in RCW 19.28		
Structural Steel Installation		
Rebar Installation		

Non-Collusion Representation. The Bidder declares under penalty of perjury that the Bid submitted is genuine and not a sham or collusive bid, or made in the interest or on behalf of any person or firm not therein named; and further represents that the Bidder has not directly or indirectly induced or solicited any other bidder to submit a sham bid, or encouraged any other person or corporation to refrain from bidding; and that the Bidder has not in any manner sought by collusion to secure to the Bidder an advantage over any other bidder or bidders.

RCW 39.04.350 Certification. The Bidder represents and certifies, under penalty of perjury, that within the three- (3-) year period immediately preceding the Bid Date, the Bidder has not been determined by a final and binding citation and notice of assessment issued by the Department of Labor and Industries, nor through a civil judgment entered by a court of limited or general jurisdiction, to have willfully violated, as defined in RCW 49.48.082, any provision of Chapters 49.46, 49.48, nor 49.52 RCW.

Addenda. Bidder acknowledges receipt and acceptance of all Addenda through No. \_\_\_\_ (Identify Last Addenda By Number)

Bid Security. A certified check, cashier's check, or other obligation of a bank, or a bid bond in substantially the form set forth in Section 00 43 13, Bid Security Form for at least five (5) percent of the Base Bid Subtotal, shall be submitted with this Bid.

Apprenticeship Requirements. For Bids greater than one million (\$1,000,000) dollars, the apprentice labor hours required for this project are fifteen (15) percent of the total labor hours. The Bidder agrees to utilize this level of apprentice participation.

\_\_\_\_\_  
Name of Firm

\_\_\_\_\_  
Date

\_\_\_\_\_  
Signature

\_\_\_\_\_  
By Title

\_\_\_\_\_  
Mailing Address

\_\_\_\_\_  
City, State Zip Code

\_\_\_\_\_  
Telephone Number

\_\_\_\_\_  
Email Address

\_\_\_\_\_  
WA State Contractor's License No.

\_\_\_\_\_  
Employment Security Department No.

\_\_\_\_\_  
Identification of Bidder as a sole proprietor, a partnership, a joint venture, a corporation, or another described form of legal entity

**END OF SECTION**

KNOW ALL MEN BY THESE PRESENTS:

That we, \_\_\_\_\_, as Principal, and \_\_\_\_\_, as Surety, are held and firmly bound unto the PORT OF TACOMA as Obligee, in the penal sum of \_\_\_\_\_ Dollars, for the payment of which the Principal and Surety bind themselves, their heirs, executors, administrators, successors and assigned, jointly and severally, by these present.

The condition of this obligation is such that if the Obligee shall make any award to the Principal for \_\_\_\_\_, according to the terms of the proposal or bid made by the Principal therefor, and the Principal shall duly make and enter into a contract with the Obligee in accordance with the terms of said proposal or bid and award and shall give bond for the faithful performance thereof, with Surety or Sureties approved by the Obligee; or, if the principal shall, in case of failure to do so, pay and forfeit to the Obligee the penal amount of the deposit specified in the call for bids, then this obligation shall be null and void; otherwise it shall be and remain in full force and effect and the Surety shall forthwith pay and forfeit to the Obligee, as penalty and liquidated damages, the amount of this bond.

SIGNED, SEALED AND DATED THIS \_\_\_\_\_ DAY OF \_\_\_\_\_, 20\_\_

BY \_\_\_\_\_  
PRINCIPAL

BY \_\_\_\_\_  
SURETY

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

AGENT AND ADDRESS

Note: Bidder may submit Surety's bid bond form, provided it is similar in substance, made out in the name of the Port of Tacoma, and that the agent's name and address appear as specified. Bonds containing riders limiting responsibility for toxic waste or limiting the term of responsibility will be rejected.

**END OF SECTION**

This page intentionally left blank

**THIS IS NOT TO BE SUBMITTED WITH A BID.**

THE LOW RESPONSIVE BIDDER SHALL BE REQUIRED TO COMPLETE THIS RESPONSIBILITY DETAIL FORM AS SPECIFIED IN SECTION 00 21 00 - INSTRUCTIONS TO BIDDERS. **THIS COMPLETED RESPONSIBILITY DETAIL FORM SHALL BE SUBMITTED ELECTRONICALLY (PDF) VIA EMAIL TO THE CONTACT(S) IDENTIFIED IN THE LOW RESPONSIVE BIDDER SELECTION NOTIFICATION.**

**BIDDER'S COMPANY NAME:** \_\_\_\_\_

For the below Mandatory Bidder Responsibility Criteria, please mark the appropriate choice.

1.01 MANDATORY BIDDER RESPONSIBILITY CRITERIA

A. The Bidder shall meet the following mandatory responsibility criteria as described in RCW 39.04.350(1). The Bidder shall be rejected as not responsible if any answer to questions 1 through 5 is "No" or any answer to questions 6 through 8 is "Yes."

1. Does the Bidder have a Certificate of Registration in compliance with RCW 18.27?

Yes       No

2. Does the Bidder have a current Washington State Unified Business Identifier number?

Yes       No

3. Does the Bidder have Industrial Insurance Coverage for the Bidder's employees working in Washington State as required in RCW 51?

Yes       No

4. Does the Bidder have an Employment Security Department number as required in RCW 50?

*\*Attach letter dated within six (6) months of Bid Date.*

*\*Request a letter electronically by clicking on the following link <https://fortress.wa.gov/esd/twt/pwcinternet/> or by emailing a request to [publicworks@esd.wa.gov](mailto:publicworks@esd.wa.gov).*

Yes       No

5. Does the Bidder have a Washington State Excise Tax Registration number as required in RCW 82?

Yes       No

6. Has the Bidder been disqualified from bidding on any public works project under RCW 39.06.010 or 39.12.065(3)?

Yes       No

7. Has the Bidder violated RCW 39.04.370 more than one (1) time as determined by the Washington State Department of Labor and Industries?

Yes       No

- 8. Has the Bidder ever been found to be out of compliance with Apprenticeship Utilization requirements of RCW 39.04.320?  
 Yes       No
  
- 9. Has the Bidder ever been found to have willfully violated, as defined in RCW 49.48.082, any provision of Chapters 49.46, 49.48, or 49.52 RCW within the three- (3-) year period immediately preceding the date of this bid solicitation?  
 Yes       No
  
- 10. Has the Bidder completed the training required by RCW 39.04.350, or is the Bidder on the list of exempt businesses maintained by the Department of Labor and Industries?  
 Yes       No

If any answer to questions 1 through 5 is "No" or any answer to questions 6 through 8 is "Yes" - **STOP HERE** and contact the Contract Administrator. The Bidder is not responsible for this Work. Otherwise proceed to 1.02. **Provide attached to this completed form documentation to confirm responsibility criteria.**

For remaining criteria below, check or fill-out the appropriate item. Based upon the answer provided by the Bidder, the Port may request additional information or seek further explanation. As needed, provide backup documentation for any explanations listed below.

**1.02 CONTRACT AND REGULATORY HISTORY**

A. The Port will evaluate whether the Bidder's contract and regulatory history demonstrates an acceptable record of past project performance and consistent responsibility. The Bidder shall answer the following questions. The Bidder may be rejected as not responsible if any answer to questions 1 through 5 below is "Yes."

- 1. Has the Bidder had a contract terminated for cause or default in the last five (5) years?  
 Yes, **If YES, explain below.**       No  

---
  
- 2. Has the Bidder required a Surety to take over all, or a portion of, a project to cure or respond to an asserted default or material breach of contract on the part of the Bidder on any public works project in the last five (5) years?  
 Yes, **If YES, explain below.**       No  

---
  
- 3. Have the Bidder and major Sub-Bidders been in bankruptcy, reorganization, and/or receivership on any public works project in the last five (5) years?  
 Yes, **If YES, explain below.**       No  

---

4. Have the Bidder and major Sub-Bidders been disqualified by any state or local agency from being awarded and/or participating on any public works project in the last five (5) years?

- Yes, **If YES, explain below.**       No

5. Are the Bidder and major Sub-Bidders currently a party to a formal dispute resolution process with the Port (i.e., a pending mediation, arbitration, or litigation)?

- Yes, **If YES, explain below.**       No

**1.03 ACCIDENT/INJURY EXPERIENCE**

- A. The Port will evaluate the Bidder’s accident/injury Experience Modification Factor (“EMF”) from the Washington State Department of Labor and Industries to assess whether the Bidder has an acceptable safety record preventing personal injuries on projects.
- B. List the Bidder’s accident/injury EMF for the last five (5) years. An experience factor is calculated annually by the Washington State Department of Labor and Industries.

Year	Effective Year	Experience Factor
1		
2		
3		
4		
5		

If the Bidder has received an EMF of greater than 1.0 for any year, explain the cause(s) of the designation and what remedial steps were taken to correct the EMF. The Bidder may be rejected as not responsible if the Bidder’s EMF is greater than 1.0 and sufficient remedial steps have not been implemented.

**1.04 WORK PERFORMED BY BIDDER**

- A. The Bidder shall state the amount of the Work, as an equivalent to the Base Bid, excluding taxes, insurance, and bonding, the Bidder will execute with its own forces.

\_\_\_\_\_ %

**1.05 ADDITIONAL CONTRACTOR INFORMATION**

- A. As part of completing this Responsibility Detail Form, **submit the following information with the completed Responsibility Detail Form:**
  - 1. Bidder’s recent job resume, including a list of similar projects performed and contact information for the similar project owner(s), a brief description of work, start and end dates, and contract amount.
  - 2. Resumes of Bidder’s proposed project manager and job superintendent.

- B. The Bidder's failure to provide the required project information may result in a determination of the Bidder being declared non-responsible by the Port.
- C. The Bidder shall submit this completed, **SIGNED** Responsibility Detail Form electronically (PDF), with all requested backup documentation, via email to the contact(s) noted on the Low Responsive Bidder Selection Notification.
- D. The Bidder and its subcontractors to verify that its subcontractors at each tier meet the responsibility criteria as required by RCW 39.06.020 and 39.04.350.
  - 1. Bidder shall verify major subcontractors meet the responsibility criteria required. Fill out one Port of Tacoma Public Works Project Bidder Evaluation Checklist for Subcontractors for each major subcontractor and submit to the Port with this form. Backup documentation is not required to be submitted.

**PROJECT: On-Call Pavement Repairs (2026)**

**PROJECT NO.: Various**

**CONTRACT NO.: 062026-1036**

**Responsibility Certification Form**

The Low responsive Bidder shall complete the Responsibility Detail Form, attach all documentation, and submit to the Port within twenty-four (24) hours following receipt of the Low Responsive Bidder Selection Notification. All forms shall be submitted electronically (PDF) via email to the contact(s) listed on the Selection Notice. Note, the same project may be used to demonstrate experience across multiple categories if applicable.

By completing and signing this Responsibility Detail Form, the Bidder is certifying that the information contained within the Form, the backup documentation, and any additional information requested by the Port is true and complete. The Bidder's failure to disclose the required information or the submittal of false or misleading information may result in the rejection of the Bidder's Bid, revocation of award, or contract termination.

The information provided herein is true and complete.

\_\_\_\_\_  
Signature of Authorized Representative

\_\_\_\_\_  
Date

\_\_\_\_\_  
Print Name and Title

**PORT OF TACOMA PUBLIC WORKS PROJECT BIDDER EVALUATION CHECKLIST FOR  
 SUBCONTRACTORS**

**PROJECT TITLE: On-Call Pavement Repairs (2026)**

**BIDDER: \_\_\_\_\_**

**CONTRACT AND PROJECT NUMBER: 062026-1036/ Various \_\_\_\_\_**

This checklist shall be completed by the Bidder and its subcontractors to verify that its subcontractors at each tier meet the responsibility criteria as required by RCW 39.06.020 and RCW 39.04.350.

This checklist should be submitted to the Port of Tacoma Contracts Administrator within twenty-four (24) hours of request.

**Document verification information or backup data is not to be submitted to the Port, this information should remain on file with the Contractor and be presented to the Port if requested at a later date.**

Item No.	Item	Initials/ Comments
1.	At the time of Bid submittal, have a certificate of registration in compliance with RCW 18.27: Check the L&I site <a href="https://secure.lni.wa.gov/verify/">https://secure.lni.wa.gov/verify/</a>  Verify that a subcontractor has an electrical contractor license, if required by RCW 19.28, or an elevator contractor license, if required by RCW 70.87.	
2.	While reviewing registration information above, also check contractor's <b>Employer Liability Certificate</b> to verify workers' comp (industrial insurance) premium status – current account.  Complete a "Submit Contractor Tracking Request" to be notified if the contractor fails to pay workers' comp premiums or renew their contractor registration or if their electrical contractor license is suspended or revoked within one year.	
3.	State excise tax registration number (Department of Revenue). (contractor's Washington State Unified Business Identifier and tax registration number) <a href="http://dor.wa.gov/content/doingbusiness/registermybusiness/brd/">http://dor.wa.gov/content/doingbusiness/registermybusiness/brd/</a> .	
4.	Not disqualified from bidding on any public works contract under <a href="#">RCW 39.06.010</a> or <a href="#">RCW 39.12.065(3)</a> .  Check the Department of Labor and Industries <a href="https://secure.lni.wa.gov/verify/">https://secure.lni.wa.gov/verify/</a>	
5.	Verify subcontractors are registered with the Washington State Employment Security Department (ESD) and have an account number. Request a letter to be sent from the subcontractor	

<b>Item No.</b>	<b>Item</b>	<b>Initials/ Comments</b>
	<p>electronically by clicking on the following link <a href="https://esd.wa.gov/">https://esd.wa.gov/</a> or by emailing a request to <a href="mailto:publicworks@esd.wa.gov">publicworks@esd.wa.gov</a>. Include ESD#, UBI#, and business name in the email. Certificate of Coverage letter issued/dated within the last six (6) months.</p> <p>Document if subcontractor confirms in writing, under penalty of perjury, that it has no employees and this requirement does not apply.</p>	

**END OF SECTION**

THIS AGREEMENT is made and entered into by and between the PORT OF TACOMA, a State of Washington municipal corporation, hereinafter designated as the "Port," and:

The "Contractor" is: \_\_\_\_\_ (Legal Name)

\_\_\_\_\_ (Address)

\_\_\_\_\_ (Address 2)

\_\_\_\_\_ (Phone No.)

The "Project" is: On-Call Pavement Repairs (2026) (Title)

Various | 062026-1036 (Project/Contract No.)

Various (Project Address)

Various (Project Address 2)

The "Engineer" is: Thais Howard, PE (Engineer)

Sr. Director, Engineering (Title)

thoward@portoftacoma.com (Email)

(253) 888-4718 (Phone No.)

The "Contractor's Representative" is: \_\_\_\_\_ (Representative)

\_\_\_\_\_ (Title)

\_\_\_\_\_ (Email)

\_\_\_\_\_ (Phone No.)

**BACKGROUND AND REPRESENTATIONS:**

The Port publicly solicited bids on the Contract Documents. The Contractor submitted a Bid to the Port on the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_ to perform the Work.

The Contractor represents that it has the personnel, experience, qualifications, capabilities, and means to accomplish the Work in strict accordance with the Contract Documents, within the Contract Time and for the Contract Price, and that it and its Subcontractors satisfy the responsibility criteria set forth in the Contract Documents, including any supplemental responsibility criteria.

The Contractor further represents that it has carefully examined, and is fully familiar with, all provisions of the Contract Documents, including any Addenda, that it has fully satisfied itself as to the nature, location, difficulty, character, quality, and quantity of the Work required by the Contract Documents and the conditions and other matters that may be encountered at or near the Project site(s), or that may affect performance of the Work or the cost or difficulty thereof, including all applicable safety and site responsibilities, and that it understands and can satisfy all scheduling and coordination requirements and interim milestones.

**AGREEMENT:**

The Port and the Contractor agree as follows:

**1.0 CONTRACTOR TO FULLY PERFORM THE WORK**

The Contractor shall fully execute and complete the entire Work for the Project described in the Contract Documents, except to the extent specifically indicated in the Agreement, the General Conditions of the Contract (as well as any Supplemental, Special, or other conditions included in the Project Manual), the Drawings, the Specifications, and all Addenda issued prior to, and all modifications issued after, execution of the Contract.

**2.0 DATE OF COMMENCEMENT**

The date of commencement of the Work, which is the date from which the Contract Time is measured, shall be fixed as the date of execution of the Contract.

**3.0 CONTRACT TIME AND LIQUIDATED DAMAGES**

The Contractor shall achieve all interim milestones as set forth in the Executed Task Orders and Substantial Completion of the entire Work not later than March 1, 2027 , subject to adjustments of this Contract Time as provided in the Contract Documents. The Contractor shall achieve Final Completion of the entire Work within 30 calendar days of the date on which Substantial Completion is achieved.

Provisions for liquidated damages as a reasonable estimate of future loss, as of the date of this Agreement, are included in the Contract Documents. The parties agree that the stated liquidated damages are reasonable and not penalties individually nor cumulatively.

The liquidated damages for failure to achieve Substantial Completion by the required Contract end date shall be \$250 per calendar day. After the required Final Completion date, the liquidated damages for failure to achieve Final Completion shall be \$500 per calendar day.

Liquidated damages assessed by the Port will be deducted from monies due to the Contractor, or from monies that will become due to the Contractor. The liquidated damages, as specified and calculated herein, shall be levied, cumulatively if applicable, for each and every calendar day that Substantial Completion and/or Final Completion of the Work is delayed beyond the required completion dates, or the completion dates modified by the Port for extensions of the Contract Time.

4.0 CONTRACT PRICE

In accordance with the Contractor's Bid dated \_\_\_\_\_, the Port shall pay the Contractor in current funds for the Contractor's performance of the Contract, the Contract Price of \_\_\_\_\_ Dollars (\$\_\_\_\_\_), subject to additions and deductions as provided in the Contract Documents. State and local sales tax is not included in the Contract Price, but will be due and paid by the Port with each progress payment.

5.0 ALTERNATES

6.0 INSURANCE AND BONDS

The Contractor shall purchase and maintain insurance and provide bonds as set forth in the Contract Documents.

This Agreement is entered into as of the day and year first written above:

CONTRACTOR

PORT OF TACOMA

By: \_\_\_\_\_

By: \_\_\_\_\_

Title: \_\_\_\_\_

Title: \_\_\_\_\_

Date: \_\_\_\_\_

Execution \_\_\_\_\_

Date:

**END OF SECTION**

This page intentionally left blank

**PERFORMANCE BOND # \_\_\_\_\_**

**CONTRACTOR (NAME AND ADDRESS)**

**SURETY (NAME AND PRINCIPLE PLACE OF BUSINESS)**

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**OWNER (NAME AND ADDRESS)**

**AGENT OR BROKER (FOR INFORMATION ONLY)**

PORT OF TACOMA  
P.O. BOX 1837  
TACOMA, WA 98401-1837

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**KNOW ALL MEN BY THESE PRESENTS:**

That \_\_\_\_\_ as Principal, hereinafter called Contractor, and \_\_\_\_\_ as Surety, hereinafter called Surety, are held and firmly bound unto the Port of Tacoma as Obligee, hereinafter called the Port, in the amount of \_\_\_\_\_ Dollars (\$ \_\_\_\_\_) for the payment whereof Contractor and Surety bind themselves, their executors, administrators, legal representatives, successors, and assigns, jointly and severally, firmly by these presents.

**WHEREAS:**

Contractor shall execute an agreement with the Port for On-Call Pavement Repairs (2026), Project No. Various/Contract No. 062026-1036, a copy of which Contract is by reference made a part hereof (the term "Contract" as used herein to include the aforesaid agreement together with all the Contract Documents, addenda, modifications, all alterations, additions thereto, deletions therefrom, and any other document or provision incorporated into the Contract) and is hereinafter referred to as the Contract.

This bond is executed and issued pursuant to the provisions of RCW 39.08.

**NOW, THEREFORE, THE CONDITION OF THIS OBLIGATION** is such that if Contractor shall promptly and faithfully perform said Contract, then this obligation shall be null and void; otherwise, it shall remain in full force and effect.

**FURTHER:**

- A. Surety hereby waives notice of any alterations, change orders, modifications, or extensions of time made by the Port.
- B. Surety recognizes that the Contract includes provisions for additions, deletions, and modifications to the Work and/or Contract Time and the amounts payable to the Contractor. Subject to the limitations contained in (A) above, Surety agrees that no such addition, deletion, or modification, or any combination thereof, shall avoid or impair Surety's obligation hereunder.
- C. Whenever Contractor has been declared by the Port to be in default, and the Port has given Surety notice of the Port's determination of such default, Surety shall promptly (in no event more than fifteen (15) days following receipt of such notice) advise the Port of its intended action to:
  - 1. Remedy the default within fifteen (15) days following its advice to the Port as set forth above, or

- 2. Assume within fifteen (15) days, following its advice to the Port as set forth above, completion of the Contract in accordance with the Contract Documents and become entitled to payment of the balance of the Contract Sum, or
- 3. Pay the Port upon completion of the Contract, in cash, the cost of completion together with all other reasonable costs and expenses incurred by the Port as a result of the Contractor's default, including but not limited to, those reasonable costs and expenses incurred by the Port in its efforts to mitigate its losses, which may include, but are not limited to, attorney's fees and efforts to complete the Work prior to the Surety exercising the options available to it as set forth herein.
- D. If the Port shall commence suit and obtain judgment against the Surety for recovery hereunder, then the Surety, in addition to such judgment, shall pay all costs and attorney's fees incurred by the Port in enforcement of its rights hereunder. Venue for any action arising out of, or in connection with, this bond shall be in Pierce County, Washington.
- E. No right or action shall accrue on this bond to, or for the use of, any person or corporation other than the Port of Tacoma.

Signed and Sealed the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

**IMPORTANT:** Surety companies executing bonds must have an A.M. Best Rating of "A-, FSC (6)" or higher, have an underwriting limitation of not less than the Contract Sum, and be authorized to transact business in the State of Washington.

**SURETY**

**CONTRACTOR**

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Printed Name and Title

\_\_\_\_\_  
Printed Name and Title

Power of Attorney attached.

**END OF SECTION**

**LABOR AND MATERIAL PAYMENT BOND # \_\_\_\_\_**

**CONTRACTOR (NAME AND ADDRESS)**

**SURETY (NAME AND PRINCIPLE PLACE OF BUSINESS)**

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**OWNER (NAME AND ADDRESS)**

**AGENT OR BROKER (FOR INFORMATION ONLY)**

PORT OF TACOMA  
P.O. BOX 1837  
TACOMA, WA 98401-1837

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**KNOW ALL MEN BY THESE PRESENTS:**

That \_\_\_\_\_ as Principal, hereinafter called Contractor, and \_\_\_\_\_ as Surety, hereinafter called Surety, are held and firmly bound unto the Port of Tacoma as Obligee, hereinafter called the Port, and all others entitled to recovery hereunder, in the amount of \_\_\_\_\_ Dollars (\$ \_\_\_\_\_) for the payment whereof Contractor and Surety bind themselves, their executors, administrators, legal representatives, successors, and assigns, jointly and severally, firmly by these presents.

**WHEREAS:**

Contractor shall execute an agreement with the Port for On-Call Pavement Repairs (2026), Project No. Various/Contract No. 062026-1036, a copy of which Contract is by reference made a part hereof (the term "Contract" as used herein to include the aforesaid agreement together with all the Contract Documents, addenda, modifications, alterations, additions thereto, deletions therefrom, and any other document or provision incorporated into the Contract) and is hereinafter referred to as the Contract.

This bond is executed pursuant to the provisions of RCW 39.08.

**NOW, THEREFORE, THE CONDITION OF THIS OBLIGATION** is such that if Contractor shall promptly make payment to all claimants, as hereinafter defined, for all labor and material used or reasonably required for use in the performance of the Contract and shall indemnify and save the Port harmless from all cost and damage by reason of Contractor's default, then this obligation shall be null and void; otherwise, it shall remain in full force and effect, subject to the following conditions.

- A. Surety hereby waives notice of any alterations, change orders, modifications, or extensions of time made by the Port.
- B. Surety recognizes that the Contract includes provisions for additions, deletions, and modifications to the Work and/or Contract Time and the amounts payable to the Contractor. Subject to the limitations contained in (A) above, Surety agrees that no such addition, deletion, or modification, or any combination thereof, shall avoid or impair Surety's obligation hereunder.

- C. Surety hereby agrees that every person protected under the provisions of RCW 39.08.010 who has not been paid as provided under the Contract, and pursuant to RCW 39.08.010, less any amounts withheld pursuant to statute, and less retainage withheld pursuant to RCW 60.28, after the expiration of a period of thirty (30) days after the date on which the completion of the Contract in accordance with RCW 39.08, may sue on this bond, prosecute the suit to final judgment as may be due claimant, and have execution thereon including recovery of reasonable costs and attorney's fees as provided by RCW 39.08. The Port shall not be liable for the payment of any costs or expenses of any such suit.
- D. No suit or action shall be commenced hereunder by any claimant unless claimant shall have given the written notices to the Port, and where required, the Contractor, in accordance with RCW 39.08.030.
- E. The amount of this bond shall be reduced by, and to the extent of, any payment or payments made in good faith hereunder, inclusive of the payment by Surety of claims which may be properly filed in accordance with RCW 39.08 whether or not suit is commenced under and against this bond.
- F. If any Claimant shall commence suit and obtain judgment against the Surety for recovery hereunder, then the Surety, in addition to such judgment and attorney fees as provided by RCW 39.08.030, shall also pay such costs and attorney fees as may be incurred by the Port as a result of such suit. Venue for any action arising out of, or in connection with, this bond shall be in Pierce County, Washington.

Signed and Sealed the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_\_.

**IMPORTANT:** Surety companies executing bonds must have an A.M. Best Rating of "A-, FSC (6)" or higher, have an underwriting limitation of not less than the Contract Sum, and be authorized to transact business in the State of Washington.

**SURETY**

**CONTRACTOR**

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Printed Name and Title

\_\_\_\_\_  
Printed Name and Title

Power of Attorney attached.

**END OF SECTION**

BOND NO.: \_\_\_\_\_

PROJECT TITLE: On-Call Pavement Repairs (2026)

PROJECT NO.: Various \_\_\_\_\_

CONTRACT NO.: 062026-1036 \_\_\_\_\_

KNOW ALL MEN BY THESE PRESENTS: That we, \_\_\_\_\_  
\_\_\_\_\_ a corporation existing under and by virtue of the laws of the State of Washington and authorized to do business in the State of Washington, as Principal, and \_\_\_\_\_, a corporation organized and existing under the laws of the State of \_\_\_\_\_ and authorized to transact the business of surety in the State of Washington, as Surety, are jointly and severally held and bound unto the PORT OF TACOMA, hereinafter called Port, as Obligee, and are similarly held and bound unto the beneficiaries of the trust fund created by RCW 60.28 as their heirs, executors, administrators, successors, and assigns in the penal sum of \_\_\_\_\_ (\$ \_\_\_\_\_) plus five (5) percent of any increases in the Contract Price that have occurred or may occur, due to change orders, increases in the quantities, or the addition of any new item of work.

WHEREAS, on the \_\_\_\_\_ day of \_\_\_\_\_, the said Principal herein executed Contract No. 062026-1036 with the Port for On-Call Pavement Repairs (2026), Project No. Various.

WHEREAS, said Contract and RCW 60.28 require the Port to withhold from the Principal the sum of five (5) percent from monies earned by the Principal on estimates during the progress of the work, hereinafter referred to as earned retained funds.

WHEREAS, the Principal has requested that the Port accept a bond in lieu of earned retained funds as allowed under RCW 60.28.

NOW THEREFORE, this obligation is such that the Surety, its successors, and assigns are held and bound unto the Port and unto all beneficiaries of the trust fund created by RCW 60.28.011(1) in the aforesaid sum. This bond, including any proceeds therefrom, is subject to all claims and liens and in the same manner and priority as set forth for retained percentages in RCW 60.28. The condition of this obligation is also that if the Principal shall satisfy all payment obligations to persons who may lawfully claim under the trust fund created pursuant to RCW 60.28, to the Port, and indemnify and hold the Port harmless from any and all loss, costs, and damages that the Port may sustain by release of said retainage to Principal, then this obligation shall be null and void, provided the Surety is notified by the Port that the requirements of RCW 60.28.021 have been satisfied and the obligation is duly released by the Port.

IT IS HEREBY DECLARED AND AGREED that the Surety shall be liable under this obligation as Principal. The Surety will not be discharged or released from liability for any act, omission, or defenses of any kind or nature that would not also discharge the Principal.

IT IS HEREBY FURTHER DECLARED AND AGREED that this obligation shall be binding upon and inure to the benefit of the Principal, the Surety, the Port, the beneficiaries of the trust fund created by RCW 60.28 and their respective heirs, executors, administrators, successors, and assigns.

IN WITNESS WHEREOF, said Principal and said Surety have caused these presents to be duly signed and sealed this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

\_\_\_\_\_  
By: \_\_\_\_\_  
Principal

Address: \_\_\_\_\_

City/ST/Zip: \_\_\_\_\_

Phone: \_\_\_\_\_

\_\_\_\_\_  
Surety Name: \_\_\_\_\_

By: \_\_\_\_\_  
Attorney-In-Fact

Address: \_\_\_\_\_

City/ST/Zip: \_\_\_\_\_

Phone: \_\_\_\_\_

**IMPORTANT:** Surety companies executing bonds must have an A.M. Best Rating of "A-, FSC (6)" or higher, and be authorized to transact business in the State of Washington.

**END OF SECTION**

**To:** Bank Name, Address, Phone \_\_\_\_\_ Escrow Account No.: \_\_\_\_\_  
\_\_\_\_\_ Contract No.: 062026-1036  
\_\_\_\_\_ Project No.: Various  
\_\_\_\_\_ Project Title: On-Call Pavement Repairs (2026)

**Agency:** Port of Tacoma \_\_\_\_\_  
PO Box 1837 \_\_\_\_\_  
Tacoma, WA 98401-1837 \_\_\_\_\_

This Retainage Escrow Agreement (the "Agreement") is made and entered into as of \_\_\_\_\_, 20 \_\_\_\_, by and among \_\_\_\_\_ ("Contractor"), with an address of \_\_\_\_\_, the Port of Tacoma (the "Port") and \_\_\_\_\_ ("Bank").

Contractor has directed the Port to deliver to Bank its retainage warrants or checks, which shall be payable to Bank and the Contractor jointly. Such warrants or checks are to be held in a restricted deposit account as described above (the "Pledged Account") and disbursed by Bank only in accordance with this Agreement and Chapter 60.28 RCW, and upon the terms and conditions hereinafter set forth.

NOW, THEREFORE, in consideration of the mutual covenants contained herein, the parties hereto agree as follows:

1. The Port shall deliver to Bank from time to time checks or warrants payable jointly to Bank and the Contractor. Bank is hereby authorized by the Contractor to endorse in the Contractor's name any such check or warrant so that Bank may receive the proceeds thereof and invest the same and deposit such proceeds into the Pledged Account. The power of endorsement hereby granted to Bank by the Contractor shall be deemed a power coupled with an interest and shall be irrevocable during the term of this Agreement. Although Bank may be a payee named in such warrants or checks as shall be delivered to Bank, Bank's duties and responsibilities with respect to the same shall be only those duties and responsibilities that a depository bank would have pursuant to a control agreement among the Bank, the Port, and Contractor, as such agreement may exist in a form satisfactory to the Port and Article 4 of the Uniform Commercial Code of the State of Washington, as amended, for an item deposited with Bank for collection. For the purpose of each such purchase, Bank may follow the last written direction received by Bank from the Contractor, provided such direction otherwise conforms with the restrictions on investments recited herein. Below is a list of such bonds and other securities approved by the Port (the "Securities"). Other securities, except stocks, may be selected by the Contractor, subject to the express prior written approval of the Port, in its sole and absolute discretion. Purchase of such Securities shall be in a form which shall allow the Bank alone to reconvert such Securities into money if Bank is required to do so by the Administrator as provided in Paragraph 5 of this Agreement. The investments selected by the Contractor, as approved by the Port and purchased by Bank, must mature on or prior to the completion date of the contract between the Contractor and the Port, including extensions thereof (the "Contract").

2. As security for the completion of the Project and satisfaction of the Contract, Contractor hereby pledges, assigns, hypothecates, and transfers to the Port, the Pledged Assets (as defined below) and grants to the Port a security interest under the Uniform Commercial Code of the State of Washington, as amended, in and to the Pledged Assets. This Agreement creates and grants a valid, perfected first priority lien on the Pledged Assets, enforceable as such against all creditors of Contractor. Contractor covenants and agrees with the Port that it will not (a) sell, assign, transfer, exchange, or otherwise dispose of, or grant any option with respect to, the Pledged Assets, (b) create, incur, or permit to exist any lien or option in favor of, or any claim of any person with respect to, any of the Pledged Assets, or any interest therein, except for the lien provided for by this Agreement, (c) withdraw any money, securities or property from the Pledged Account, except as provided herein, or (d) attempt to modify or terminate Contractor's the agreement under which the Pledged Account was established. Contactor will defend the right, title, and security interest of the Port in and to the Pledged Assets against the claims and demands of all persons. "Pledged Assets" means the Pledged Account, now or hereafter constituted, including (i) all credit balances or other money now or hereafter credited to the Pledged Account; (ii) all money, certificated and uncertificated securities, commodities contracts, instruments, documents, general intangibles, financial assets or other investment property now or hereafter in, or distributed from, the Pledged Account; (iii) all income, products and proceeds of the sale, exchange, redemption or exercise of the foregoing, whenever occurring, whether as dividends, interest payments or other distributions of cash or property, including, without limitation, proceeds in the nature of accounts, general intangibles, and insurance proceeds; (iv) any rights incidental to the ownership of the foregoing, such as voting, conversion and registration rights and rights of recovery for securities violations; and (v) all books and records pertaining to the foregoing.
3. When an interest on the Securities accrues and is paid, Bank shall collect such interest and forward it to the Contractor at the address designated below unless otherwise directed in writing by the Contractor.
4. Bank is not authorized to deliver to the Contractor all or any part of the Securities (or any monies derived from the sale of such Securities, or the negotiation of the Port's warrants or checks) except in accordance with Chapter 60.28 RCW based on written instructions from the Senior Contract Administrator for the Port (the "Administrator"). The Administrator shall inform the Bank and keep the Bank informed in writing of the name of the person or persons with authority to give the Bank such written instructions. Compliance with such instructions shall relieve Bank of any further liability related thereto. The estimated completion date on the Contract underlying this Agreement is \_\_\_\_\_ . Upon request by Bank, the Port shall advise Bank in writing of any material change in the estimated Contract completion date. If such estimated completion date is changed, Bank is authorized to reinvest the monies held hereunder in accordance with the new estimated completion date.
5. In the event the Administrator orders Bank to do so in writing, and notwithstanding any other provisions of this Agreement, Bank shall, within ten (10) days of receipt of such order, reconvert into money the Securities and return such money together with any other monies, including accrued interest on such Securities to the Port. Consent of Contractor shall not be required for payment to the Port hereunder, and objection or other communication from Contractor shall not prevent, delay, or otherwise affect payment to the Port forthwith in accordance with the Port's order and this Agreement.

6. The Contractor agrees to pay Bank as compensation for Bank's services hereunder as follows:

Payment of all fees shall be the sole responsibility of the Contractor and shall not be deducted from any checks, moneys, Securities, or other property placed with Bank or held by Bank pursuant to this Agreement until and unless the Port directs the release thereof to the Contractor, whereupon Bank shall be granted a first lien upon such property released and shall be entitled to reimburse Bank from such property for the entire amount of Bank's fees as provided for hereinabove. In the event that Bank is made a party to any litigation with respect to the checks, moneys, Securities, or other property held by Bank hereunder, or in the event that the conditions of this escrow are not promptly fulfilled or that Bank is required to render any service not provided for in these instructions, or that there is any assignment of the interests of this escrow or any modification hereof, Bank shall be entitled to reasonable compensation for such extraordinary services from the Contractor and reimbursement from the Contractor for all costs and expenses, including reasonable attorney fees occasioned by such default, delay, controversy, or litigation.

7. Should Bank at any time and for any reason desire to be relieved of Bank's obligation as escrow holder hereunder, Bank shall give written notice to the Port and the Contractor. The Port and Contractor shall, within twenty (20) days of the receipt of such notice, jointly appoint a successor escrow holder and instruct Bank to deliver all securities and funds held hereunder to said successor. If Bank is not notified of the appointment of the successor escrow holder within twenty (20) days, Bank may return the subject matter hereof to the Port, and upon so doing, it absolves Bank from all further charges and obligations in connection with this Agreement.

8. Any one or more of the following events constitutes an Event of Default ("Event of Default") under this Agreement: (i) Contractor breaches the Contract; (ii) Contractor fails to perform any covenant or obligation under this Agreement; (iii) Contractor shall file a voluntary petition in bankruptcy or such a petition shall be filed against Contractor; and (iv) a court of competent jurisdiction shall enter an order, judgment or decree approving a petition filed against Contractor seeking any reorganization, dissolution or similar relief under any present or future federal, state or other statute, law or regulation relating to bankruptcy, insolvency or other relief for debtors.

9. Upon the occurrence of an Event of Default, the Port may exercise, in addition to all other rights and remedies granted in this Agreement, all rights and remedies of a secured party under the Uniform Commercial Code of the State of Washington, as amended. Without limiting the generality of the foregoing, the Port, without demand of performance or other demand, presentment, protest, advertisement, or notice of any kind (except any notice required by law, this Agreement) to or upon Contractor or any other person (all and each of which demands, defenses, advertisements and notices are hereby waived to the extent not prohibited by law), may, upon the occurrence of an Event of Default, collect, receive, appropriate, and realize upon the Pledged Assets, or any part thereof, and/or may forthwith withdraw from the Pledged Account, sell, assign, give option or options to purchase or otherwise dispose of and deliver the Pledged Assets or any part thereof (or contract to do any of the foregoing).

10. This Agreement shall not be binding until executed by the Contractor and the Port and accepted by Bank.

11. This instrument contains the entire agreement between Bank, the Contractor, and the Port with respect to this Agreement and Bank is not a party to nor bound by any instrument or agreement other than this; Bank shall not be required to take notice or demand nor be required to take any action whatever, except as herein expressly provided; Bank shall not be liable for any loss or damage not caused by Bank's own negligence or willful misconduct.
12. The foregoing provisions shall be binding upon the assigns, successors, personal representatives and heirs of the parties hereto.
13. This Agreement is subject to the laws of the State of Washington and is to be construed in accordance therewith.
14. Any legal action or proceeding with respect to this Agreement may be brought in the courts of the State of Washington or in the courts of the United States for the Western District of Washington, and by execution and delivery of this Agreement, Contractor consents, for itself and in respect of its property, to the nonexclusive jurisdiction of those courts. Contractor irrevocably waives any objection, including any objection to the laying of venue or based on the grounds of forum non conveniens, which it may now or hereafter have to the bringing of any action or proceeding in such jurisdiction in respect of this Agreement or any document related hereto.
15. The Contractor's Federal Income Tax Identification number is \_\_\_\_\_.

The undersigned have read and hereby approve this Agreement on the date first set forth above.

**Contractor:**

**Port of Tacoma:**

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Name/Title

\_\_\_\_\_  
Name/Port Treasurer or Deputy Treasurer

\_\_\_\_\_  
Date

\_\_\_\_\_  
Date

The above escrow instructions received and accepted this \_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

**Bank:** By: \_\_\_\_\_ Name: \_\_\_\_\_  
(Signature of Authorized Bank Officer) Title: \_\_\_\_\_

**SECURITIES AUTHORIZED BY THE PORT:**

1. FDIC insured time deposits and time deposits in commercial banks authorized by the Washington State Public Deposit Protection Commission;
2. Savings account deposits in commercial banks authorized by the Washington State Public Deposit Protection Commission;
3. Bills, certificates, notes, or bonds of the United States;
4. Other obligations of the United States or its agencies; and
5. Obligation of any corporation wholly-owned by the government of the United States.

**INSTRUCTIONS FOR RETAINAGE ESCROW AGREEMENTS:**

Whenever possible, use the Port approved Escrow Agreement. The Port, at its discretion, may or may not accept an agreement form from another source.

Please return all three (3) originals of the Agreement, with completed contractor and bank information and signatures, and the escrow account number. The Port will review and sign the Agreement and distribute copies. One (1) original will go directly to the Bank, one (1) original will be returned to the Contractor.

Fill in the following on the Escrow Agreement:

1. Page 1 – Escrow Account Number
2. Page 1 – Name, address, and phone number of the Bank
3. Page 4 – Signature, typed/printed name, date, and the title of the Contractor Signatory
4. Page 4 – Signature, typed/printed name, date, and the title of the Authorized Bank Officer signatory

Do not fill in the date in the introductory paragraph. The Port will fill in this date once the document has been fully executed by the Port.

**END OF SECTION**

This page intentionally left blank

	<b>PAGE</b>
<b>TABLE OF CONTENTS</b>	
<b>ARTICLE 1 - THE CONTRACT DOCUMENTS</b>	
1.01	GENERAL
1.02	DEFINITIONS
1.03	INTENT OF THE CONTRACT DOCUMENTS
1.04	CORRELATION OF THE CONTRACT DOCUMENTS
1.05	OWNERSHIP OF THE CONTRACT DOCUMENTS
<b>ARTICLE 2 - PORT OF TACOMA</b>	
2.01	AUTHORITY OF THE ENGINEER
2.02	ADMINISTRATION OF THE CONTRACT
2.03	INFORMATION PROVIDED BY THE PORT
2.04	CONTRACTOR REVIEW OF PROJECT INFORMATION
2.05	PORT'S RIGHT TO REJECT, STOP, AND/OR CARRY-OUT THE WORK
2.06	SEPARATE CONTRACTORS
2.07	OFFICERS AND EMPLOYEES OF THE PORT
<b>ARTICLE 3 - CONTRACTOR'S RESPONSIBILITIES</b>	
3.01	DUTY TO PERFORM THE ENTIRE WORK
3.02	OBSERVED ERRORS, INCONSISTENCIES, OMISSIONS OR VARIANCES IN THE CONTRACT DOCUMENTS
3.03	SUPERVISION AND RESPONSIBILITY FOR SUBCONTRACTORS
3.04	MATERIALS AND EQUIPMENT
3.05	CONTRACTOR WARRANTIES
3.06	REQUIRED WAGES
3.07	STATE AND LOCAL TAXES
3.08	PERMITS, LICENSES, FEES, AND ROYALTIES
3.09	SAFETY
3.10	CORRECTION OF WORK
3.11	UNCOVERING OF WORK
3.12	RELOCATION OF UTILITIES
3.13	LABOR
3.14	INDEMNIFICATION
3.15	WAIVER OF CONSEQUENTIAL DAMAGES
<b>ARTICLE 4 - SUBCONTRACTORS AND SUPPLIERS</b>	
4.01	RESPONSIBILITY FOR ACTIONS OF SUBCONTRACTORS AND SUPPLIERS
4.02	AWARD OF CONTRACTS TO SUBCONTRACTORS AND SUPPLIERS
4.03	SUBCONTRACTOR AND SUPPLIER RELATIONS
<b>ARTICLE 5 - WORKFORCE AND NON-DISCRIMINATION REQUIREMENTS</b>	
5.01	COMPLIANCE WITH NON-DISCRIMINATION LAWS
5.02	MWBE, VETERAN-OWNED, AND SMALL BUSINESS ENTERPRISE PARTICIPATION
5.03	APPRENTICESHIP PARTICIPATION
<b>ARTICLE 6 - CONTRACT TIME AND COMPLETION</b>	
6.01	CONTRACT TIME
6.02	PROGRESS AND COMPLETION
6.03	SUBSTANTIAL COMPLETION

- 6.04 COMPLETION OF PUNCH LIST
- 6.05 FINAL COMPLETION
- 6.06 FINAL ACCEPTANCE
- 6.07 PORT'S RIGHT TO USE THE PREMISES

**ARTICLE 7 - PAYMENT**

- 7.01 ALL PAYMENTS SUBJECT TO APPLICABLE LAWS AND SCHEDULE OF VALUES
- 7.02 APPLICATIONS FOR PAYMENT
- 7.03 PROGRESS PAYMENTS
- 7.04 PAYMENT BY CONTRACTOR TO SUBCONTRACTORS
- 7.05 FINAL PAYMENT
- 7.06 RETAINAGE
- 7.07 DISPUTED AMOUNTS
- 7.08 EFFECT OF PAYMENT
- 7.09 LIENS

**ARTICLE 8 - CHANGES IN THE WORK**

- 8.01 CHANGES IN THE WORK
- 8.02 CHANGES IN THE CONTRACT SUM
- 8.03 CHANGES IN THE CONTRACT TIME
- 8.04 RESERVATION OF RIGHTS
- 8.05 UNIT PRICES

**ARTICLE 9 - SUSPENSION AND TERMINATION OF CONTRACT**

- 9.01 PORT'S RIGHT TO SUSPEND WORK
- 9.02 TERMINATION OF CONTRACT FOR CAUSE BY THE PORT
- 9.03 TERMINATION OF CONTRACT FOR CONVENIENCE BY THE PORT
- 9.04 TERMINATION OF CONTRACT BY THE CONTRACTOR
- 9.05 SUBCONTRACT ASSIGNMENT UPON TERMINATION

**ARTICLE 10 - BONDS**

- 10.01 CONTRACTOR PERFORMANCE AND PAYMENT BONDS

**ARTICLE 11 - DISPUTE RESOLUTION**

- 11.01 NOTICE OF PROTEST AND CLAIM
- 11.02 MEDIATION
- 11.03 LITIGATION

**ARTICLE 12 - MISCELLANEOUS**

- 12.01 GENERAL
- 12.02 WAIVER
- 12.03 GOVERNING LAW
- 12.04 COMPLIANCE WITH LAW
- 12.05 ASSIGNMENT
- 12.06 TIME LIMIT ON CAUSES OF ACTION
- 12.07 SERVICE OF NOTICE
- 12.08 RECORDS
- 12.09 STATUTES

## ARTICLE 1 - THE CONTRACT DOCUMENTS

### 1.01 GENERAL

- A. Contract Documents form the Contract. The Contract Documents are enumerated in the Agreement between the Port and Contractor ("Agreement"). Together, the Contract Documents form the Contract. The Contract represents the entire integrated agreement between the parties and supersedes all prior negotiations, representations, or agreements, either written or oral. The Contract may be amended or modified only in writing and only as set forth in the Contract Documents.
- B. Headings only for convenience. The titles or headings of the sections, divisions, parts, articles, paragraphs, and subparagraphs of the Contract Documents are intended only for convenience.

### 1.02 DEFINITIONS

- A. "Contract Documents" proposed for the Work consist of the Agreement, the General Conditions of the Contract (as well as any Supplemental, Special, or other conditions included in the Project Manual), the Drawings, the Specifications, and all Addenda issued prior to, and all modifications issued after, execution of the Contract.
- B. "Contractor" means the person or entity contracting to perform the Work under these Contract Documents. The term Contractor includes the Contractor's authorized representative for purposes of identifying obligations and responsibilities under the Contract Documents, including the ability to receive notice and direction from the Port.
- C. "Day" means a calendar day unless otherwise specifically designated.
- D. "Drawings" are the graphic and pictorial portions of the Contract Documents showing the design, location, and dimensions of the Work, including plans, elevations, sections, details, and diagrams.
- E. "Engineer" is the Port employee generally tasked with administering the Project on the Port's behalf and the person with overall responsibility for managing, for the Port, the Project scope, budget, and schedule. To the extent empowered, the Engineer may delegate to others at the Port (such as a Project Manager or Inspector) the responsibility for performing delegated responsibilities of the Engineer's under this Contract.
- F. "Port" means the Port of Tacoma. The Port will designate in writing a representative (usually the Engineer) who shall have the authority to act on the Port's behalf related to the Project. The "Port" does not include staff, maintenance, or safety workers, or other Port employees or consultants that may contact the Contractor or be present at the Project site.
- G. "Project" is identified in the Agreement and is the total construction to be performed by or through the Port, of which the Work performed under the Contract Documents may be only a part.
- H. "Specifications" are those portions of the Contract Documents that specify the written requirements for materials, equipment, systems, standards, and workmanship for the Work and for the performance of related services.
- I. "Subcontractor" means a person or entity that contracts directly with the Contractor to perform any Work under the Contract Documents. "Subcontractor of any tier" includes Subcontractors as well as any other person or entity, including suppliers, that contracts with a Subcontractor or a lower-tier Subcontractor (also referred to as "Sub-subcontractors") to perform any of the Work.

- J. "Work" means the construction and services required by the Contract Documents, whether completed or partially completed, and includes all labor, tools, equipment, materials, services, and incidentals necessary to complete all obligations under the Contract Documents. The Work may constitute only a part of the Project, and may interface and need to be coordinated with the work of others.

#### 1.03 INTENT OF THE CONTRACT DOCUMENTS

- A. Intent of Contract Documents. The intent of the Contract Documents is to describe the complete Work and to include all items and information necessary for the proper execution and completion of the Work by the Contractor.
- B. Contract Documents are complementary. The Contract Documents are complementary, and what is required by one shall be as binding as if required by all; performance by the Contractor is required to the extent consistent with the Contract Documents and reasonably inferable from them as being necessary to produce the indicated results.
- C. No third party contract rights. The Contract Documents shall not create a contractual relationship of any kind (1) between the Port and a Subcontractor of any tier (although the Port does not waive any third-party beneficiary rights it may otherwise have as to Subcontractors of any tier), (2) between the Contractor and the Engineer or other Port employees or consultants, or (3) between any persons or entities other than the Port and Contractor.

#### 1.04 CORRELATION OF THE CONTRACT DOCUMENTS

- A. Precedence. In the event of a conflict or discrepancy between or among the Contract Documents, the conflict or discrepancy will be resolved by the following order of precedence: with an addendum or Change Order having precedence over an earlier document, and computed dimensions having precedence over scaled dimensions, and large scale drawings take precedence over small scale drawings:
  - 1. The signed Agreement
    - a. Supplemental Conditions
    - b. Division 00 General Conditions
    - c. Division 01 General Requirements of Specifications
    - d. All other Specifications, including all remaining divisions, material and system schedules and attachments, and Drawings
    - e. All other sections in Division 00 not specifically identified herein by Section
- B. Inconsistency between or among Contract Documents. If there is any inconsistency between the Drawings, schedules, or Specifications, or any attachments, the Contractor will make an inquiry to the Engineer to determine how to proceed, and, unless otherwise directed, the Contractor will provide the better quality or greater quantity of any work or materials, as reasonably interpreted by the Port, at no change in the Contract Sum or Contract Time. Thus, if Work is shown on Drawings, but not contained in Specifications or schedules, or contained in Specifications or schedules, but not shown on the Drawings, the Work as shown or contained will be provided at no change in the Contract Sum or Contract Time, according to Specifications or Drawings to be issued by the Port.

- C. Inconsistency with law. In the event of a conflict between the Contract Documents and applicable laws, codes, ordinances, regulations, or orders of governmental authorities having jurisdiction over the Work, or in the event of any conflict between such laws, the most stringent requirements govern.
- D. Organization of Contract Documents. The organization of the Specifications and Drawings shall not control the Contractor in dividing the Work among Subcontractors or in establishing the extent of the Work to be performed. The Port assumes no responsibility for the division and proper coordination of Work between particular Subcontractors.
- E. Bid quantities are estimates only. Any "bid quantities" set forth in the Contract Documents are estimates only. The Port does not warrant that the actual amount of Work will correspond to any estimates. The basis of payment will be the actual quantities performed in accordance with the Contract Documents.

#### 1.05 OWNERSHIP OF THE CONTRACT DOCUMENTS

- A. Port owns all Contract Documents. All Drawings, Specifications, and other Contract Documents furnished to the Contractor are Port property, and the Port retains all intellectual property rights, including copyrights. The Contract Documents are to be used only with respect to the Project.

### **ARTICLE 2 - PORT OF TACOMA**

#### 2.01 AUTHORITY OF THE ENGINEER

- A. Engineer will be Port's representative. The Engineer or the Engineer's designee will be the Port's representative during the Project and will administer the Project on the Port's behalf.
- B. Engineer may enforce all obligations. The Engineer has the authority to enforce all requirements imposed on the Contractor by the Contract Documents.
- C. Only Engineer is agent of Port. Other than the Engineer, no other Port employee or consultant is an agent of the Port, and none are authorized to agree on behalf of the Port to changes in the Contract Sum or Contract Time, nor to waive provisions of the Contract Documents, nor to direct the Contractor to take actions that change the Contract Sum or Contract Time, nor to accept notice of protests or claims on behalf of the Port.

#### 2.02 ADMINISTRATION OF THE CONTRACT

- A. Port will administer Contract. The Port will provide administration of the Contract through the Engineer or the Engineer's designee. All communications with the Port or its consultants related to the Contract will be through the designated representative.
- B. Port not responsible for means and methods. The Port is not responsible for, and will have no control or charge of, the means, methods, techniques, sequences, or procedures of construction, or for safety precautions or programs incidental thereto, because these are the sole responsibility of the Contractor. If the Port makes any suggestion of means, methods, techniques, sequences, or procedures, the Contractor will exercise its independent judgment in deciding whether to adopt the suggestion, except as otherwise provided in the Contract Documents.
- C. Port not responsible for acts or omissions of Contractor or Subcontractors. The Port is not responsible for, and will have no control or charge of, the acts or omissions of the Contractor, Subcontractors of any tier, suppliers, or any of their agents or employees, or any other persons performing a portion of the Work.

- D. Port not responsible for the Work. The Port is not responsible for the Contractor's failure to carry out the Work in accordance with the Contract Documents. The presence of the Engineer or others at the Project site at any time does not relieve the Contractor from its responsibility for non-conforming Work.
- E. Port will have access to the Work. The Port and its representatives will at all times have access to the Work in progress, and the Contractor will provide proper facilities for such access and for inspection.

#### 2.03 INFORMATION PROVIDED BY THE PORT

- A. Port to furnish information with reasonable promptness. The Port shall furnish information and services required of the Port by the Contract Documents with reasonable promptness.
- B. Subsurface investigation. The Port may have undertaken a limited investigation of the soil and other subsurface conditions at the Project site for design purposes only. The results of these investigations will be available for the convenience of the Contractor, but they are not Contract Documents. There is no warranty or guarantee, express or implied, that the conditions indicated are representative of those existing at the site or that unforeseen developments may not occur. The Contractor is solely responsible for interpreting the information.

#### 2.04 CONTRACTOR REVIEW OF PROJECT INFORMATION

- A. Contractor to familiarize itself with site and conditions of Work. Prior to executing the Contract, the Contractor shall visit the site, become generally familiar with local conditions under which the Work is to be performed, and correlate personal observations with the requirements of the Contract Documents and all information provided with the Bid Documents. By signing the Contract, the Contractor confirms that the Contract Sum is reasonable compensation for the Work; that the Contract Time is adequate; that it has carefully examined the Contract Documents and the Project site; and that it has satisfied itself as to the nature, location, and character of the Work, the labor, materials, equipment, and other items required and all other requirements of the Contract Documents. The Contractor's failure fully to acquaint itself with any such condition does not relieve the Contractor from the responsibility for performing the Work in accordance with the Contract Documents, within the Contract Time, and for the Contract Sum.
- B. Contractor to review Contract Documents. Because the Contract Documents are complementary, the Contractor will, before starting each portion of the Work, carefully study and compare the various Drawings, Specifications, and other Contract Documents, as well as all information furnished by the Port.
- C. Contractor to confirm field conditions. Before starting each portion of the Work, the Contractor shall take field measurements of and verify any existing conditions, including all Work in place, and all general reference points; shall observe any conditions at the site affecting the Contractor; and shall carefully compare field measurements, conditions and other information known to the Contractor with the Contract Documents.

#### 2.05 PORT'S RIGHT TO REJECT, STOP, AND/OR CARRY-OUT THE WORK

- A. Port may reject Work. The Port has the authority, but not the obligation, to reject work, materials, and equipment that is defective or that otherwise does not conform to the Contract Documents, and to decide questions concerning the Contract Documents. However, the failure to so reject, or the presence of the Port at the site, shall not be construed as assurance that the Work is acceptable or being completed in compliance with the Contract Documents.

- B. Port may stop Work. If the Contractor fails to correct Work that does not comply with the requirements of the Contract Documents, or repeatedly or materially fails to properly carry out the Work, the Port may issue an order to stop all or a portion of the Work until the cause for the order has been eliminated. The Port's right to stop the Work shall not impose a duty on the Port to exercise this right for the benefit of the Contractor or any third party.
- C. Port may carry-out Work. If the Contractor fails to perform the Work properly, fails to perform any provision of this Contract, or fails to maintain the Baseline Project Schedule, or if the Port reasonably concludes that the Work will not be completed in the specified manner or within the Contract Time, then the Port may, after three (3) days' written notice to the Contractor and without prejudice to any other remedy the Port may have, perform itself or have performed any or all of the Work and may deduct the cost thereof from any payment then or later due the Contractor.

## 2.06 SEPARATE CONTRACTORS

- A. Port may engage separate contractors or perform work with its own forces. The Port may contract with other contractors ("Separate Contractor") in connection with the Project or perform work with its own forces. The Contractor shall coordinate and cooperate with any Port forces or Separate Contractors, as applicable. The Contractor shall provide reasonable opportunity for the introduction and storage of materials and the execution of work by others.
- B. Contractor to inspect work of others. If any part of the Contractor's Work depends on the work of the Port or any Separate Contractor, the Contractor shall inspect and promptly report to the Port, in writing, any defects that impact the Contractor. Failure of the Contractor to so inspect and report defects in writing shall constitute an acceptance by Contractor of the work of the Port or Separate Contractor.
- C. Contractor to resolve claims of others. Should the Contractor, or any of its Subcontractors of any tier, cause damage of any kind, including but not limited to delay, to any Separate Contractor, the Contractor shall promptly, and using its best efforts, settle or otherwise resolve the dispute with the Separate Contractor. The Contractor shall also promptly remedy damage caused to completed or partially completed construction.

## 2.07 OFFICERS AND EMPLOYEES OF THE PORT

- A. No personal liability. Officers, employees, and representatives of the Port, including the Commissioners, acting within the scope of their employment, shall not be personally liable to Contractor for any acts or omissions arising out of the Project.

## ARTICLE 3 - CONTRACTOR'S RESPONSIBILITIES

### 3.01 DUTY TO PERFORM THE ENTIRE WORK

- A. Contractor must perform entire Work in accordance with Contract Documents. The Contractor shall perform the entire Work required by the Contract in accordance with the Contract Documents. Unless otherwise specifically provided, the Contractor shall provide and pay for all labor, tools, equipment, materials, electricity, power, water, other utilities, transportation, and other facilities necessary for the execution and completion of the Work.
- B. Contractor shall be independent contractor. The Contractor shall be, and operate as, an independent contractor in the performance of the Work. The Contractor is not authorized to enter into any agreements or undertakings for, or on behalf of, the Port and is not an agent or employee of the Port.

### 3.02 OBSERVED ERRORS, INCONSISTENCIES, OMISSIONS, OR VARIANCES IN THE CONTRACT DOCUMENTS

- A. Contractor to notify Port of any discrepancy. The Contractor's obligations to review and carefully study the Contract Documents and field conditions are for the purpose of facilitating coordination and construction. If the Contractor at any time observes that the Contract Documents, including Drawings and Specifications, vary from the conditions of the Project site, are in error, or omit any necessary detail, the Contractor shall promptly notify the Engineer in writing through a Request for Information. Any Work done after such observation, until authorized by the Engineer, shall be at Contractor's risk. The Contractor shall also promptly report to the Engineer any observed error, inconsistency, omission, or variance with applicable laws through a Request for Information. If the Contractor fails either to carefully study and compare the Contract Documents, or to promptly report any observed error, inconsistency, omission, or variance, the Contractor shall assume full responsibility and shall bear all costs, liabilities, and damages attributable to the error, inconsistency, omission, or variance.
- B. Requests for Information. The Contractor shall submit Requests for Information concerning the Contract Documents by following the procedure and using such form as the Port may require. The Contractor shall minimize Requests for Information by thoroughly studying the Contract Documents and reviewing all Subcontractor requests. The Contractor shall allow adequate time in its planning and scheduling for a response from the Port to a Request for Information.
- C. Port may provide information to supplement Drawings and Specifications. Minor items of work or detail that are omitted from the Drawings and Specifications, but inferable from the information presented and normally provided by accepted good practice, shall be provided and/or performed by the Contractor as part of the Contract Sum and within the Contract Time. Similarly, the Engineer may furnish to the Contractor additional Drawings and clarifications, consistent with the Contract Documents, as necessary to detail and illustrate the Work. The Contractor shall conform its Work to such additional Drawings and clarifications at no increase in the Contract Sum or Contract Time.

### 3.03 SUPERVISION AND RESPONSIBILITY FOR SUBCONTRACTORS

- A. Contractor responsible for Work and workers. The Contractor shall have complete control of the means, methods, techniques, sequences, or procedures related to the Work, and for all safety precautions or programs. The Contractor shall have complete control over, and responsibility for, all personnel performing the Work. The Contractor is also responsible for the acts and omissions of the Contractor's principals, employees, and other persons or entities performing portions of the Work for, or on behalf of, the Contractor or any of its Subcontractors of any tier.
- B. Contractor to supervise the Work. The Contractor shall continuously supervise and direct the Work using competent and skilled personnel and the Contractor's best skill and attention.
- C. Contractor to enforce discipline and good order. The Contractor shall enforce strict discipline and good order among all workers on the Project, and shall not employ any unfit person or anyone not skilled in the work to which they are assigned. Incompetent, careless, or negligent workers shall immediately be removed from the Work. The Port may, but is not obligated to, require the Contractor to remove from the Work, at no change in the Contract Sum or Contract Time, anyone whom the Port considers objectionable.

### 3.04 MATERIALS AND EQUIPMENT

- A. Material and equipment to be new. All materials and equipment to be incorporated into the Work shall be new, unless specifically provided otherwise in the Contract Documents. The Contractor shall, if required in writing by the Port, furnish satisfactory evidence regarding the kind and quality of any materials, identify the source, and warrant compliance with the Contract Documents. The Contractor shall ensure that all materials and equipment are protected, kept dry, and stored under cover in a manner to protect such materials and equipment.
- B. Material and equipment shall conform to manufacturer instructions. All materials and equipment shall conform, and shall be applied, installed, used, maintained, and conditioned in accordance with the instructions of the applicable manufacturer, fabricator, or processor, unless otherwise specifically provided by the Engineer.

### 3.05 CONTRACTOR WARRANTIES

- A. Work will be of good quality and performed in workmanlike manner. In addition to any specific warranties set forth in the Contract Documents, the Contractor warrants that the Work, including all materials and equipment furnished under the Contract, will be of good quality and new, will be performed in a skillful and workmanlike manner, and will conform to the requirements of the Contract Documents. Any Work not conforming to this warranty, including unapproved or unauthorized substitutions, shall be considered defective.
- B. Work will be free from defects. The Contractor warrants that the Work will be free from defects for a period of one (1) year from the date of Substantial Completion of the Project.
- C. Contractor to collect and deliver warranties to Port. The Contractor shall collect and deliver to the Port any written warranties required by the Contract Documents. These warranties shall be obtained and enforced by the Contractor for the benefit of the Port without the necessity of separate assignment. These warranties shall extend to the Port all rights, claims, benefits, and interests that the Contractor may have under express or implied warranties or guarantees against a Subcontractor of any tier, supplier, or manufacturer for defective or non-conforming Work. Warranty provisions that purport to limit or alter the Port's rights under the Contract Documents, or the laws of the State of Washington, are null and void.
- D. General requirements. The Contractor is not relieved of its general warranty obligations by the specification of a particular product or procedure in the Contract Documents. Warranties in the Contract Documents shall survive completion, acceptance, and final payment.

### 3.06 REQUIRED WAGES

- A. Contractor will pay required wages. The Contractor shall pay (and shall ensure that all Subcontractors of any tier pay) all prevailing wages and other wages (such as Davis-Bacon Act wages) applicable to the Project. See Specification Section 00 73 46.
- B. The Contractor shall defend (at Contractor's sole cost, with legal counsel approved by Port), indemnify, and hold the Port harmless from all liabilities, obligations, claims, demands, damages, disbursements, lawsuits, losses, fines, penalties, costs, and expenses, whether direct or indirect, and including, but not limited to, attorneys' fees and consultants' fees and other costs and expenses of litigation, from any violation or alleged violation by the Contractor or any Subcontractor of any tier of RCW 39.12 ("Prevailing Wages on Public Works") or Chapter 51 RCW ("Industrial Insurance").

### 3.07 STATE AND LOCAL TAXES

- A. Contractor will pay taxes on consumables. The Contractor will pay the retail sales tax on all consumables used during performance of the Work and on all items that are not incorporated into the final Work; this tax shall be included in the Contract Sum.

- B. Port will pay taxes on the Contract Sum. The Port will pay state and local retail sales tax on the Contract Sum with each progress payment, and on final payment, for transmittal by the Contractor to the Washington State Department of Revenue or to the applicable local taxing authority. Rule 170: WAC 458-20-170.
- C. Direct all tax questions to the Department of Revenue. The Contractor should direct all questions concerning taxes on any portion of the Work to the State of Washington Department of Revenue or to the local taxing authority.
- D. State Sales Tax - Rule 171: WAC 458-20-171. For work performed related to building, repairing, or improving streets, roads, etc., which are owned by a municipal corporation, or political subdivision of the state, or by the United States, and which are used, primarily, for foot or vehicular traffic, the Contractor shall include Washington State Retail Sales Taxes in the various schedule prices, or other contract amounts, including those that the Contractor pays on the purchase of materials, equipment, or supplies used or consumed in doing the Work.
  - 1. The bid form will indicate which bid items are subject to Rule 171. Any such identification by the Port is not binding upon the Department of Revenue.

### 3.08 PERMITS, LICENSES, FEES, AND ROYALTIES

- A. Contractor to provide and pay for permits unless otherwise specified. Unless otherwise specified, the Contractor shall procure and pay for all permits, licenses, and governmental inspection fees necessary or incidental to the performance of the Work. All costs related to these permits, licenses, and inspections shall be included in the Contract Sum. Any action taken by the Port to assist the Contractor in obtaining permits or licenses shall not relieve the Contractor of its sole responsibility to obtain and pay for permits, licenses, and inspections as part of the Contract Sum.
- B. Contractor's obligations when permit must be in Port's name. When applicable law or agency requires a permit to be issued to a public agency, the Port will support the Contractor's request for the permit and accept the permit in the Port's name, if:
  - 1. The Contractor takes all necessary steps required for the permit to be issued;
  - 2. The permit applies to Work performed in connection with the Project; and
  - 3. The Contractor agrees in writing to abide by all requirements of the permit and to defend and hold harmless the Port from any liability in connection with the permit.
- C. Contractor to pay royalties. The Contractor shall pay all royalties and license fees required for the Work unless otherwise specified in the Contract Documents.

### 3.09 SAFETY

- A. Contractor solely responsible for safety. The Contractor shall be solely responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the Work and the performance of the Contract.
- B. Port not responsible for safety. The Port may identify safety concerns to the Contractor; however, no action or inaction of the Port or any third party relating to safety will: (1) relieve the Contractor of its sole and complete responsibility for safety and sole liability for any consequences, (2) impose any obligation on the Port or a third party to inspect or review the Contractor's safety program or precautions, (3) impose any continuing obligation on the Port or a third party to ensure the Contractor performs the Work safely, or (4) affect the Contractor's responsibility for the protection of property, workers, and the general public.

- C. Contractor to maintain a safe Work site. The Project site may be occupied during performance of the Work. The safety of these site occupants is of paramount importance to the Port. The Contractor shall maintain the Work site and perform the Work in a safe manner and in accordance with the Washington Industrial Safety and Health Act (WISHA) and all other applicable safety laws, rules, and regulations. This requirement shall apply continuously and not be limited to working hours.
- D. Contractor to protect Work site and adjacent property until Final Completion. The Contractor shall continuously protect the Work and adjacent property from damage. At all times until Final Completion, the Contractor shall be responsible for, and protect from damage, weather, deterioration, theft, and vandalism, the Work and all materials, equipment, tools, and other items incorporated or to be incorporated in the Work, and shall repair any damage, injury, or loss.

### 3.10 CORRECTION OF WORK

- A. Contractor to correct defective Work. The Contractor shall, at no cost to the Port, promptly correct Work that is defective or that otherwise fails to conform to the requirements of the Contract Documents. Such Work shall be corrected, whether before or after Substantial Completion, and even if it was previously inspected or observed by the Port.
- B. One-year correction period. The Contractor shall correct all defects in the Work appearing within one (1) year of Substantial Completion or within any longer period prescribed by law or by the Contract Documents. The Contractor shall initiate remedial action within fourteen (14) days of receipt of notice from the Port and shall complete remedial work within a reasonable time. Work corrected by the Contractor shall be subject to the provisions of this Section 3.10 for an additional one-year period following the Port's acceptance of the corrected Work.
- C. Contractor responsible for defects and failures to correct. The Contractor shall be responsible for any expenses incurred by the Port resulting from defects in the Work. If the Contractor refuses or neglects to correct the defects, or does not timely accomplish corrections, the Port may correct the Work and charge the Contractor the cost of the corrections. If damage or loss of service may result from a delay in correction, the corrections may be made by the Port and reimbursed by the Contractor.
- D. Port may accept defective work. The Port may, at its sole option, elect to retain defective or nonconforming Work. In such a case, the Port shall reduce the Contract Sum by a reasonable amount to account for the defect or non-conformance.
- E. No period of limitation established. Nothing contained in this Section 3.10 establishes a period of limitation with respect to any obligations under the Contract Documents or law. The establishment of the one (1) year correction period relates only to the specific obligation of the Contractor to correct defective or non-conforming Work.

### 3.11 UNCOVERING OF WORK

- A. Contractor to uncover work covered prior to inspection. If any portion of the Work is covered prior to inspection and approval, the Contractor shall, at its expense, uncover or remove the Work for inspection by the Port or others, and replace the Work to the standard required by the Contract Documents.

- B. Contractor to uncover work at Port's request. After initial inspection and observation, the Port may order a reexamination of Work, and the Work must be uncovered by the Contractor. If the uncovered Work complies with the Contract Documents, the Port shall pay the cost of reexamination and replacement. If the Work is found not to comply with the Contract Documents, the Contractor shall pay the cost of replacement, unless the Contractor demonstrates that it did not cause the defect in the Work.

### 3.12 RELOCATION OF UTILITIES

- A. Contractor should assume underground utilities are in approximate locations. The Contractor should assume that the locations of any underground or hidden utilities, underground tanks, and plumbing or electrical runs indicated in surveys or the Contract Documents are shown in approximate locations. The accuracy of this information is not guaranteed by the Port and shall be verified by the Contractor. The Contractor shall comply with RCW 19.122.030 and utilize a utility locator service to locate utilities on Port property. The Contractor shall bear the risk of loss if any of its Work directly or indirectly damages or interrupts any utility service or causes or contributes to damages of any nature.
- B. Utility relocation or removal. Where relocation or removal of utilities is necessary or required, it shall be performed at the Contractor's sole expense, unless the Contract Documents specify otherwise. If a utility owner is identified as being responsible for relocating or removing utilities, the work will be accomplished at the utility owner's convenience, either during, or in advance of, construction. Unless otherwise specified, it shall be the Contractor's sole responsibility to coordinate, schedule, and pay for work performed by a utility owner.
- C. Contractor to notify Port of unknown utilities. If the Contractor discovers the presence of any unknown utilities, it shall immediately notify the Engineer in writing.

### 3.13 LABOR

- A. Contractor responsible for labor peace. The Contractor is responsible for labor peace relating to the Work and shall cooperate in maintaining Project-wide labor harmony. The Contractor shall use its best efforts as an experienced contractor to adopt and implement policies and practices designed to avoid work stoppages, slowdowns, disputes, or strikes.
- B. Contractor to minimize impact of labor disputes. The Contractor will take all necessary steps to prevent labor disputes from disrupting or otherwise interfering with access to Port property. If a labor dispute disrupts the progress of the Work or interferes with access, the Contractor shall promptly and expeditiously take all necessary action to eliminate or minimize the disruption or interference.

### 3.14 INDEMNIFICATION

- A. Duty to defend, indemnify, and hold harmless. To the fullest extent permitted by law and subject to this Section 3.14, the Contractor shall defend (at the Contractor's sole cost, with legal counsel approved by Port), indemnify, and hold harmless the Port and the Northwest Seaport Alliance, including their respective Commissions, officers, managers, and employees, the Engineer, any consultants, and the agents and employees, successors and assigns of any of them (the "Indemnified Parties") from and against claims, damages, lawsuits, losses (including loss of use), disbursements, liabilities, obligations, fines, penalties, costs, and expenses, whether direct and indirect or consequential, including but not limited to, consultants' fees, and attorneys' fees incurred on such claims and in proving the right to indemnification ("Claims"), arising out of, or resulting from, the acts or omissions of the Contractor, a Subcontractor of any tier, their agents, and anyone directly or indirectly employed by any of them or anyone for whose acts they may be liable (individually and collectively, the "Indemnitor").

- B. Duty to defend, indemnify, and hold harmless for sole negligence. The Contractor will fully defend, indemnify, and hold harmless the Indemnified Parties for the sole negligence or willful misconduct of the Indemnitor.
- C. Duty to defend, indemnify, and hold harmless for concurrent negligence. Where Claims arise from the concurrent negligence of (1) the Port; and (2) the Indemnitor, the Contractor's obligations to indemnify and defend the Indemnified Parties under this Section 3.14 shall be effective only to the extent of the Indemnitor's negligence.
- D. Duty to indemnify not limited by workers' compensation or similar employee benefit acts. In claims against any of the Indemnified Parties by an employee of the Contractor, a Subcontractor of any tier, anyone directly or indirectly employed by them, or anyone for whose acts they may be liable, the indemnification obligation under this Section 3.14 shall not be limited by a limitation on amount or type of damages, compensation, or benefits payable under workers' compensation acts, disability benefit acts, or other employee benefit acts. After mutual negotiation of the parties, the Contractor waives immunity as to the Indemnified Parties under Title 51 RCW, "Industrial Insurance."
- E. Intellectual property indemnification. The Contractor will be liable for and shall defend (at the Contractor's sole cost, with legal counsel approved by Port), indemnify, and hold the Indemnified Parties harmless for Claims for infringement by the Contractor of copyrights or patent rights arising out of, or relating to, the Project.
- F. Labor peace indemnification. If the Contractor fails to satisfy its labor peace obligations under the Contract, the Contractor will be liable for and shall defend (at the Contractor's sole cost, with legal counsel approved by Port), indemnify, and hold harmless the Indemnified Parties for Claims brought against the Port by third parties (including but not limited to lessees, tenants, contractors, customers, licensees, and invitees of the Port) for injunctive relief or monetary loss.
- G. Cyber risk indemnification. Contractor shall defend, indemnify, and hold harmless the Indemnified Parties from and against any liability, expense, fines, penalties, cost, demand, or other obligation, resulting from or out of any cyber-related risk that includes theft, loss or misuse of data, release of private information as result of a network breach, penetration, compromise, or loss of IT systems control.
- H. Joinder. The Contractor agrees to being added by the Port as a party to any arbitration or litigation with third parties in which the Port alleges indemnification or seeks contribution from the Indemnitor. The Contractor shall cause each of its Subcontractors of any tier to similarly stipulate in their subcontracts; in the event any does not, the Contractor shall be liable in place of such Subcontractor(s) of any tier.
- I. Other. To the extent that any portion of this Section 3.14 is stricken by a court or arbitrator for any reason, all remaining provisions shall retain their vitality and effect. The obligations of the Contractor under this Section 3.14 shall not be construed to negate, abridge, or otherwise reduce any other right or obligations of indemnity which would otherwise exist. To the extent the wording of this Section 3.14 would reduce or eliminate an available insurance coverage, it shall be considered modified to the extent necessary so that the insurance coverage is not affected. This Section 3.14 shall survive completion, acceptance, final payment, and termination of the Contract.

### 3.15 WAIVER OF CONSEQUENTIAL DAMAGES

- A. Mutual waiver of consequential damages. The Contractor and Port waive claims against each other for consequential damages arising out of, or relating to, this Contract. This mutual waiver includes, but is not limited to: (1) damages incurred by the Port for rental expenses, financing, business and reputation, and for loss of management or employee productivity or of the services of such persons, and (2) damages incurred by the Contractor for principal and home office overhead and expenses including, but not limited to, the compensation of personnel stationed there, for losses of financing, business, and reputation, for losses on other projects, for loss of profit, and for interest or financing costs. This mutual waiver includes, but is not limited to, all consequential damages due to either party's termination.
- B. Limitation. Nothing contained in this Section 3.15; however, shall be deemed to preclude an award of liquidated damages, when applicable, in accordance with the requirements of the Contract Documents, to preclude damages specified in the Agreement, or to affect the Contractor's obligation to indemnify the Port for direct, indirect, or consequential damages alleged by a third party.

#### **ARTICLE 4 - SUBCONTRACTORS AND SUPPLIERS**

##### **4.01 RESPONSIBILITY FOR ACTIONS OF SUBCONTRACTORS AND SUPPLIERS.**

- A. Contractor responsible for Subcontractors. The Contractor is fully responsible to the Port for the acts and omissions of its Subcontractors of any tier and all persons either directly or indirectly employed by the Contractor or its Subcontractors.

##### **4.02 AWARD OF CONTRACTS TO SUBCONTRACTORS AND SUPPLIERS**

- A. Contractor to provide proposed Subcontractor information. The Contractor, within ten (10) days after the Port's notice of award of the Contract, shall provide the Engineer with the names of the persons or entities proposed to perform each of the principal portions of the Work (i.e., either a Subcontractor listed in a bid or proposal or a Subcontractor performing Work valued at least ten percent (10%) of the Contract Sum) and the proprietary names, and the suppliers of, the principal items or systems of materials and equipment proposed for the Work. No progress payment will become due until after this information has been furnished.
- B. Port to respond promptly with objections. The Port may respond promptly to the Contractor in writing stating: (1) whether the Port has reasonable objection to any proposed person or entity, or (2) whether the Port requires additional time for review. If the Port makes a reasonable objection, the Contractor shall replace the Subcontractor with no increase to the Contract Sum or Contract Time. Such a replacement shall not relieve the Contractor of its responsibility for the performance of the Work and compliance with all of the requirements of the Contract within the Contract Sum and Contract Time.
- C. Reasonable objection defined. "Reasonable objection" as used in this Section 4.02 includes, but is not limited to: (1) a proposed Subcontractor of any tier different from the entity listed with the bid, (2) lack of "responsibility" of the proposed Subcontractor, as defined by Washington law and the Bidding Documents, or lack of qualification or responsibility of the proposed Subcontractor based on the Contract or Bidding Documents, or (3) failure of the Subcontractor to perform satisfactorily in the Port's opinion (such as causing a material delay or submitting a claim that the Port considers inappropriate) on one or more projects for the Port within five (5) years of the bid date.
- D. No substitution allowed without permission. The Contractor shall not substitute a Subcontractor, person, or organization without the Engineer's written consent.

##### **4.03 SUBCONTRACTOR AND SUPPLIER RELATIONS**

---

- A. Contractor to schedule, supervise, and coordinate Subcontractors. The Contractor shall schedule, supervise, and coordinate the operations of all Subcontractors of any tier, including suppliers. The Contractor shall ensure that appropriate Subcontractors coordinate the Work of lower-tier Subcontractors.
- B. Subcontractors to be bound to Contract Documents. By appropriate agreement, the Contractor shall require each Subcontractor and supplier to be bound to the terms of the Contract Documents and to assume toward the Contractor, to the extent of their Work, all of the obligations that the Contractor assumes toward the Port under the Contract Documents. Each subcontract shall preserve and protect the rights of the Port and shall allow to the Subcontractor, unless specifically provided in the subcontract, the benefit of all rights, remedies, and redress against the Contractor that the Contractor, by the Contract Documents, has against the Port. Where appropriate, the Contractor shall require each Subcontractor to enter into similar agreements with lower-tier Subcontractors.
- C. Contractor to correct deficiencies in Subcontractor performance. When a portion of the Work subcontracted by the Contractor is not being prosecuted in accordance with the Contract Documents, or if such subcontracted Work is otherwise being performed in an unsatisfactory manner in the Port's opinion, the Contractor shall, on its own initiative or upon the written request of the Port, take immediate steps to correct the deficiency or remove the non-performing party from the Project. The Contractor shall replace inadequately performing Subcontractors upon request of the Port at no change in the Contract Sum or Contract Time.
- D. Contractor to provide subcontracts. Upon request, the Contractor will provide the Port copies of written agreements between the Contractor and any Subcontractor.

## **ARTICLE 5 - WORKFORCE AND NON-DISCRIMINATION REQUIREMENTS**

### **5.01 COMPLIANCE WITH NON-DISCRIMINATION LAWS**

- A. Contractor to comply with non-discrimination laws. The Contractor shall fully comply with all applicable laws, regulations, and ordinances pertaining to non-discrimination.
- B. Nondiscrimination Provision
  - 1. Nondiscrimination Requirement. During the term of this Contract, Contractor, including any subcontractor, shall not discriminate on the bases enumerated at RCW 49.60.530(3). In addition, Contractor, including any subcontractor, shall give written notice of this nondiscrimination requirement to any labor organizations with which Contractor, or subcontractor, has a collective bargaining or other agreement.
  - 2. Obligation to Cooperate. Contractor, including any subcontractor, shall cooperate and comply with any Washington state agency investigation regarding any allegation that Contractor, including any subcontractor, has engaged in discrimination prohibited by this Contract pursuant to RCW 49.60.530(3).

3. Default. Notwithstanding any provision to the contrary, POT may suspend Contractor, including any subcontractor, upon notice of a failure to participate and cooperate with any state agency investigation into alleged discrimination prohibited by this Contract, pursuant to RCW 49.60.530(3). Any such suspension will remain in place until POT receives notification that Contractor, including any subcontractor, is cooperating with the investigating state agency. In the event Contractor, or subcontractor, is determined to have engaged in discrimination identified at RCW 49.60.530(3), POT may terminate this Contract in whole or in part, and Contractor, subcontractor, or both, may be referred for debarment as provided in RCW 39.26.200. Contractor or subcontractor may be given a reasonable time in which to cure this noncompliance, including implementing conditions consistent with any court-ordered injunctive relief or settlement agreement.
4. Remedies for Breach. Notwithstanding any provision to the contrary, in the event of Contract termination or suspension for engaging in discrimination, Contractor, subcontractor, or both, shall be liable for contract damages as authorized by law including, but not limited to, any cost difference between the original contract and the replacement or cover contract and all administrative costs directly related to the replacement contract, which damages are distinct from any penalties imposed under Chapter 49.60, RCW. POT shall have the right to deduct from any monies due to Contractor or subcontractor, or that thereafter become due, an amount for damages Contractor or subcontractor will owe POT for default under this provision.

#### 5.02 MWBE, VETERAN-OWNED, AND SMALL BUSINESS ENTERPRISE PARTICIPATION.

- A. In accordance with the legislative findings and policies set forth in RCW 39.19, the Port encourages participation in all of its contracts by MWBE firms certified by the Office of Minority and Women's Business Enterprises (OMWBE). Participation may be either on a direct basis in response to this invitation or as a subcontractor to a Bidder. However, unless required by federal statutes, regulations, grants, or contract terms referenced in the Contract Documents, no preference will be included in the evaluation of Bids, no minimum level of MWBE participation shall be required as a condition for receiving an award, and Bids will not be rejected or considered non-responsive on that basis. Any affirmative action requirements set forth in federal regulations or statutes included or referenced in the Contract Documents will apply.

The Port encourages participation in all of its contracts by Veteran-owned businesses (defined in RCW 43.60.010) and located at <http://www.dva.wa.gov/program/certified-veteran--and-servicemember-owned-businesses> and Small, Mini, and Micro businesses (defined in RCW 39.26.010)

#### 5.03 APPRENTICESHIP PARTICIPATION

- A. In accordance with RCW 39.04.320, fifteen (15) percent Apprenticeship Participation is required for all projects estimated to cost one million (\$1,000,000) dollars or more.
- B. Apprentice participation, under this contract, may be counted towards the required percentage (%) only if the apprentices are from an apprenticeship program registered and approved by the Washington State Apprenticeship and Training Council (RCW 49.04 and WAC 296-05).
- C. Bidders may contact the Department of Labor and Industries, Specialty Compliance Services Division, Apprenticeship Section, P.O. Box 44530, Olympia, WA 98504-4530 by phone at (360) 902-5320, or e-mail at [Apprentice@lni.wa.gov](mailto:Apprentice@lni.wa.gov), to obtain information on available apprenticeship programs.

- D. For each project that has apprentice requirements, the contractor shall submit a "Statement of Apprentice and Journeyman Participation" on forms provided by the Port of Tacoma, with every request for project payment. The Contractor shall submit consolidated and cumulative data collected by the Contractor and collected from all subcontractors by the Contractor. The data to be collected and submitted includes the following:
1. Contractor name and address
  2. Contract number
  3. Project name
  4. Contract value
  5. Reporting period "Beginning Date" through "End Date"
  6. Name and registration number of each apprentice by contractor
  7. Total number of apprentices and labor hours worked by them, categorized by trade or craft.
  8. Total number of journeymen and labor hours worked by them, categorized by trade or craft
  9. Cumulative combined total of apprentice and journeymen labor hours
  10. Total percentage of apprentice hours worked
- E. No changes to the required percentage (%) of apprentice participation shall be allowed without written approval of the Port. In any request for the change, the Contractor shall clearly demonstrate a good faith effort to comply with the requirements for apprentice participation.
- F. Labor hours used in the 15% labor hour calculation will include all employees working on the project who are subject to prevailing wage laws. The definition of Labor Hours is further clarified to include working supervisor and foreman hours if they are covered under prevailing wage laws based on the time spent performing laborious activities. Simply adding supervisor or foreman to the employee's title does not exempt their hours from the calculation.
- G. During the life of the project, Apprentice Utilization is actively monitored through LNIs Prevailing Wage Intents and Affidavits (PWIA) system using the certified payroll calculated percentage. In addition, the affidavit calculated percentage shown in PWIA must be at least 15.0% to be compliant. All affidavits must be filed before determining if the Apprentice Utilization Requirement was met. Failure to achieve at least 15.0% apprentice Utilization as shown in PWIA for certified payrolls and affidavits will cause a penalty of \$500.00

## **ARTICLE 6 - CONTRACT TIME AND COMPLETION**

### **6.01 CONTRACT TIME**

- A. Contract Time is measured from Contract execution. Unless otherwise provided in the Agreement, the Contract Time is the period of time, including authorized adjustments, specified in the Contract Documents from the date the Contract is executed to the date Substantial Completion of the Work is achieved.

- B. Commencement of the Work. The Contractor shall begin Work in accordance with the notice of award and the notice to proceed and shall complete all Work within the Contract Time. When the Contractor's signed Agreement, required insurance certificate with endorsements, bonds, and other submittals required by the notice of award have been accepted by the Port, the Port will execute the Contract and, following receipt of other required pre-work submittals, will issue a notice to proceed to allow the Contractor to mobilize and commence physical Work at the Project site, as further described in these contract documents. No Work at the Project site may commence until the Port issues a notice to proceed.
- C. Contractor shall achieve specified completion dates. The Contractor shall achieve Substantial Completion within the Contract Time and shall achieve Final Completion within the time period thereafter stated in the Contract Documents.
- D. Time is of the essence. Time limits stated in the Contract Documents, including any interim milestones, are of the essence of the Contract. By executing the Agreement, the Contractor confirms that the Contract Time is a reasonable period for performing the Work.

#### 6.02 PROGRESS AND COMPLETION

- A. Contractor to maintain schedule. The Contractor's sequence and method of operations, application of effort, and work force shall at all times be created and implemented to ensure the orderly, expeditious, and timely completion of the Work and performance of the Contract. The Contractor shall furnish sufficient forces and shall work such hours, including extra shifts, overtime operations, and weekend and holiday work as may be necessary to ensure completion of the Work within the Contract Time and the approved Baseline Project Schedule.
- B. Contractor to take necessary steps to meet schedule. If the Contractor fails substantially to perform in a timely manner in accordance with the Contract Documents and, through the fault of the Contractor or Subcontractor(s) of any tier, fails to meet the Baseline Project Schedule, the Contractor shall take such steps as may be necessary to immediately improve its progress by increasing the number of workers, shifts, overtime operations, or days of work, or by other means and methods, all without additional cost to the Port. If the Contractor believes that any action or inaction of the Port constitutes acceleration, the Contractor shall immediately notify the Port in writing and shall not accelerate the Work until the Port either directs the acceleration in writing or denies the constructive acceleration.
- C. Liquidated damages not exclusive. Any provisions in the Contract Documents for liquidated damages shall not preclude other damages due to breaches of Contract of the Contractor.

#### 6.03 SUBSTANTIAL COMPLETION

- A. Substantial Completion defined. Substantial Completion is the stage in the progress of the Work, or portion or phase thereof, when the Work or designated portion is sufficiently complete in accordance with the Contract Documents so that the Port can fully occupy or utilize the Work, or the designated portion thereof, for its intended use, all requirements in the Contract Documents for Substantial Completion have been achieved, and all required documentation has been properly submitted to the Port in accordance with the Contract Documents. All Work, other than incidental corrective or punch list Work and final cleaning, must be completed. The fact that the Port may occupy the Work or a designated portion thereof does not indicate that Substantial Completion has occurred or that the Work is acceptable in whole or in part.
- B. Work not Substantially Complete unless Final Completion attainable. The Work is not Substantially Complete unless the Port reasonably judges that the Work can achieve Final Completion within the period of time specified in the Contract Documents.

- C. Notice of Substantial Completion. When the Work or designated portion has achieved Substantial Completion, the Port will provide a notice to establish the date of Substantial Completion. The notice shall establish responsibilities of the Port and Contractor for security, maintenance, heat, utilities, damage to the Work, and insurance, and shall fix the time within which the Contractor shall finish all remaining Work. If the notice of Substantial Completion does not so state, all responsibility for the foregoing items shall remain with the Contractor until Final Completion.

#### 6.04 COMPLETION OF PUNCH LIST

- A. Contractor shall complete punch list items prior to Final Completion. The Contractor shall cause punch list items to be completed prior to Final Completion. If, after Substantial Completion, the Contractor does not expeditiously proceed to correct punch list items or if the Port considers that the punch list items, are unlikely to be completed prior to the date established for Final Completion (or such other period of time as is specified in the Contract Documents), the Port may, upon seven (7) days' written notice to the Contractor, take over and perform some or all of the punch list items. The Port may also take over and complete any portion of the Work at any time following Substantial Completion and deduct the actual cost of performing the Work (including direct and indirect costs) from the Contract Sum. The Port's rights under this Section 6.04 are not obligations and shall not relieve the Contractor of its responsibilities under any other provisions of the Contract Documents.

#### 6.05 FINAL COMPLETION

- A. Final Completion. Upon receipt of written notice from the Contractor that all punch list items and other Contract requirements are completed, the Contractor will notify the Port, and the Port will perform a final inspection. If the Port determines that some or all of the punch list items have not been addressed, the Contractor shall be responsible to the Port for all costs, including re-inspection fees, for any subsequent reviews to determine completion of the punch list. When the Port determines that all punch list items have been satisfactorily addressed, that the Work is acceptable under the Contract Documents, and that the Work has fully been performed, the Port will promptly notify the Contractor of Final Completion.
- B. Contractor responsible for costs if Final Completion is not timely achieved. In addition to any liquidated damages, the Contractor is liable for, and the Port may deduct from any amounts due the Contractor, all costs incurred by the Port for services performed after the contractual date of Final Completion, whether or not those services would have been performed prior to that date had Final Completion been timely achieved.
- C. Final Completion submittals. The Port is not obligated to accept the Project as complete until the Contractor has submitted all required submittals to the Port.
- D. Contractor responsible for the Work until Final Completion. The Contractor shall assume the sole risk of loss and responsibility for all Work under the Contract, and all materials to be incorporated in the Work, whether in storage or at the Project site, until Final Completion. Damage from any cause to either permanent or temporary Work, utilities, materials, equipment, existing structures, the site, or other property owned by the Port or others, shall be repaired by the Contractor to the reasonable satisfaction of the Port at no change in the Contract Sum.

#### 6.06 FINAL ACCEPTANCE

- A. Final Acceptance. Final Acceptance is the formal action of the Port accepting the Project as complete.

- B. Final Acceptance not an acceptance of defective Work. Final Acceptance shall not constitute acceptance by the Port of unauthorized or defective Work, and the Port shall not be prevented from requiring the Contractor to remove, replace, repair, or dispose of unauthorized or defective Work or recovering damages due to the same.
- C. Completion of Work under RCW 60.28. Pursuant to RCW 60.28, "Lien for Labor, Materials, Taxes on Public Works," completion of the Contract Work shall occur upon Final Acceptance.

#### 6.07 PORT'S RIGHT TO USE THE PREMISES

- A. Port has right to use and occupy Work. The Port reserves the right to occupy or use any part of the Work before or after Substantial Completion of some or all of the Work without relieving the Contractor of any of its obligations under the Contract. Such occupancy or use shall not constitute acceptance by the Port of any of the Work, and shall not cause any insurance to be canceled or lapse.
- B. No compensation due if Port elects to use and occupy Work. No additional compensation shall be due to the Contractor as a result of the Port's use or occupancy of the Work or a designated portion.

### ARTICLE 7 - PAYMENT

#### 7.01 ALL PAYMENTS SUBJECT TO APPLICABLE LAWS AND SCHEDULE OF VALUES

- A. Payment of the Contract Sum. The Contract Sum is stated in the Agreement and, including authorized adjustments, is the total amount payable by the Port to the Contractor for performance of the Work under the Contract Documents. Payments made to the Contractor are subject to all laws applicable to the Port and the Contractor. Payment of the Contract Sum constitutes full compensation to the Contractor for performance of the Work, including all risk, loss, damages, or expense of whatever character arising out of the nature or prosecution of the Work. The Port is not obligated to pay for extra work or materials furnished without prior written approval of the Port.
- B. Schedule of Values. All payments will be based upon an approved Schedule of Values. Prior to submitting its first Application for Payment, the Contractor shall submit a Schedule of Values to the Port allocating the entire Contract Sum to the various portions of the Work. The Schedule of Values shall be prepared in such form, and supported by such data to substantiate its accuracy, as the Port may require. This schedule, unless objected to by the Port, shall be used as a basis for reviewing the Contractor's applications for payment.

#### 7.02 APPLICATIONS FOR PAYMENT

- A. Applications for Payment. Progress payments will be made monthly for Work duly certified, approved by the Engineer, and performed (based on the Schedule of Values and actual quantities of Work performed) during the calendar month preceding the Application for Payment. These amounts are paid in trust to the Contractor for distribution to Subcontractors to the extent, and in accordance with, the approved Application for Payment.

#### 7.03 PROGRESS PAYMENTS

- A. Progress payments. Following receipt of a complete Application for Payment, the Engineer will either authorize payment or indicate in writing to the Contractor the specific reasons why the payment request is being denied, in whole or in part, and the remedial action the Contractor must take to receive the withheld amount. After a complete Application for Payment has been received and approved by the Port, payment will be made within thirty (30) days. Any payments made by, or through, or following receipt of, payment from third parties will be made in accordance with the third party's policies and procedures.
- B. Port may withhold payment. The Port may withhold payment in whole or in part as provided in the Contract Documents or to the extent reasonably necessary to protect the Port from loss or potential loss for which the Contractor is responsible, including loss resulting from the Contractor's acts and omissions.

#### 7.04 PAYMENT BY CONTRACTOR TO SUBCONTRACTORS

- A. Payment to Subcontractors. With each Application for Payment, the Contractor shall provide a list of Subcontractors to be paid by the Contractor. No payment request shall include amounts the Contractor does not intend to pay to a Subcontractor because of a dispute or other reason. If, however, after submitting an Application for Payment, but before paying a Subcontractor, the Contractor discovers that part or all of a payment otherwise due to the Subcontractor is subject to withholding from the Subcontractor under the subcontract (such as for unsatisfactory performance or non-payment of lower-tier Subcontractors), the Contractor may withhold the amount as allowed under the subcontract, but it shall give the Subcontractor and the Port written notice of the remedial actions that must be taken and pay the Subcontractor within eight (8) working days after the Subcontractor satisfactorily completes the remedial action identified in the notice.
- B. Payment certification to be provided upon request. The Contractor shall provide, with each Application for Payment, a certification signed by Contractor attesting that all payments by the Contractor to Subcontractors from the last Application for Payment were made within ten (10) days of the Contractor's receipt of payment. The certification will also attest that the Contractor will make payment to Subcontractors for the current Application for Payment within ten (10) days of receipt of payment from the Port.

#### 7.05 FINAL PAYMENT

- A. Final payment. Final applications for payment are due within seven (7) days following Final Completion. Final payment of the unpaid balance of the Contract Sum, except retainage, will be made following Final Completion and within thirty (30) days of the Contractor's submission of an approved final Application for Payment.
- B. Releases required for final payment. The final payment shall not become due until the Contractor delivers to the Port a complete release of all liens arising out of the Contract, as well as an affidavit stating that, to the best of Contractor's knowledge, its release includes all labor and materials for which a lien could be filed. If a Subcontractor of any tier refuses to furnish a release or waiver required by the Port, the Port may (a) retain in the fund, account, or escrow funds in such amount as to defray the cost of foreclosing the liens of such claims and to pay attorneys' fees, the total of which shall be no less than 150% of the claimed amount, or (b) accept a bond from the Contractor, satisfactory to the Port, to indemnify the Port against the lien. If any such lien remains unsatisfied after all payments from the retainage are made, the Contractor shall refund to the Port all moneys that the Port may be compelled to pay in discharging such lien, including all costs and reasonable attorneys' fees.

- C. Contractor to hold Port harmless from liens. The Contractor shall defend (at the Contractor's sole cost, with legal counsel approved by Port), indemnify, and hold harmless the Port from any liens, claims, demands, lawsuits, losses, damages, disbursements, liabilities, obligations, fines, penalties, costs, and expenses, whether direct or indirect, including but not limited to, attorneys' fees and consultants' fees and other costs and expenses, except to the extent a lien has been filed because of the failure of the Port to make a contractually required payment.

#### 7.06 RETAINAGE

- A. Retainage to be withheld. In accordance with RCW 60.28, a sum equal to five percent (5%) of each approved Application for Payment shall be retained. Prior to submitting its first Application for Payment, the Contractor shall exercise one of the options listed below:
  - 1. Retained percentages will be retained by the Port in a fund; or
  - 2. Deposited by the Port in an interest-bearing account or escrow account in a bank, mutual savings bank, or savings and loan association designated by the Contractor, not subject to withdrawal until after the final acceptance of said improvement or work as completed, or until agreed to by both parties; provided that interest on such account shall be paid to the Contractor. Contractor to complete and submit Port provided Retainage Escrow Agreement (Section 00 61 23.13); or
  - 3. If the Contractor provides a bond in place of retainage, it shall be in an amount equal to 5% of the Contract Sum plus Change Orders. The retainage bond shall be based on the form furnished in Section 00 61 23 or otherwise acceptable to the Port and duly completed and signed by a licensed surety or sureties registered with the Washington State Insurance Commissioner and on the currently authorized insurance list published by the Washington State Insurance Commissioner. The surety or sureties must be rated at least "A-, FSC(6)" or higher by A.M. Best Rating Guide and be authorized by the Federal Department of the Treasury. Attorneys-in-fact who sign the retainage bond must file with each bond a certified and effective Power of Attorney statement.
- B. Contractor may withhold retainage from Subcontractors. The Contractor or a Subcontractor may withhold not more than five percent (5%) retainage from the monies earned by any Subcontractor or lower-tier Subcontractor, provided that the Contractor pays interest to the Subcontractor at the same interest rate it receives from its reserved funds. If requested by the Port, the Contractor shall specify the amount of retainage and interest due a Subcontractor.
- C. Release of retainage. Retainage will be withheld and applied by the Port in a manner required by RCW 60.28 and released in accordance with the Contract Documents and statutory requirements. Release of the retainage will be processed in the ordinary course of business within sixty (60) days following Final Acceptance of the Work by the Port provided that no notice of lien has been given as provided in RCW 60.28, that no claims have been brought to the attention of the Port, that the Port has no claims under this Contract, and that release of retention has been duly authorized by the State. The following items must also be obtained prior to release of retainage: pursuant to RCW 60.28, a certificate from the Department of Revenue; pursuant to RCW 50.24, a certificate from the Department of Employment Security; and appropriate information from the Department of Labor and Industries including approved affidavits of wages paid for the Contractor and each subcontractor.

#### 7.07 DISPUTED AMOUNTS

- A. Disputed amounts. If the Contractor believes it is entitled to payment for Work performed during the prior calendar month in addition to the agreed-upon amount, the Contractor may submit to the Port, along with the approved Application for Payment, a separate written payment request specifying the exact additional amount claimed to be due, the category in the Schedule of Values to which the payment would apply, the specific Work for which additional payment is sought, and an explanation of why the Contractor believes additional payment is due.

#### 7.08 EFFECT OF PAYMENT

- A. Payment does not relieve Contractor of obligations. Payment to the Contractor of progress payments or final payment does not relieve the Contractor from its responsibility for the Work or its responsibility to repair, replace, or otherwise make good defective Work, materials, or equipment. Likewise, the making of a payment does not constitute a waiver of the Port's right to reject defective or non-conforming Work, materials, or equipment (even though they are covered by the payment), nor is it a waiver of any other rights of the Port.
- B. Acceptance of final payment waives claims. Acceptance of final payment by the Contractor, a Subcontractor of any tier, or a supplier shall constitute a waiver of claims except those previously made in writing and identified as unsettled in Contractor's final Application for Payment.
- C. Execution of Change Order waives claims. The execution of a Change Order shall constitute a waiver of claims by the Contractor arising out of the Work to be performed or deleted pursuant to the Change Order, except as specifically described in the Change Order.

#### 7.09 LIENS

- A. Contractor to discharge liens. The Contractor shall promptly pay (and secure the discharge of any liens asserted by) all persons properly furnishing labor, equipment, materials, or other items in connection with the performance of the Work including, but not limited to, any Subcontractors of any tier.

### **ARTICLE 8 - CHANGES IN THE WORK**

#### 8.01 CHANGES IN THE WORK

- A. Changes in the Work authorized. Without invalidating the Contract and without notice to the Contractor's surety, the Port may authorize changes in the Work after execution of the Contract, including changes in the Contract Sum or Contract Time. Changes shall occur solely by Change Order, Unilateral Change Directive, or Minor Change in Work. All changes in the Work are effective immediately, and the Contractor shall proceed promptly to perform the change, unless otherwise provided in the Change Order or Directive.
- B. Changes in the Work Defined.
  - 1. A Change Order is a written instrument signed by the Port and Contractor stating their agreement to a change in the Work and the adjustment, if any, in the Contract Sum and/or Contract Time.
  - 2. A Unilateral Change Directive is a written instrument issued by the Port to transmit new or revised Drawings, issue additions or modifications to the Contract, furnish other direction and documents adjustment, if any, to the Contract Sum and/or Contract Time. A Unilateral Change Directive is signed only by the Port, without requiring the consent or signature of the Contractor.
  - 3. A Minor Change in the Work is a written order from the Port directing a change that does not involve an adjustment to the Contract Sum or the Contract Time.

- C. Request for Proposal: At any time, the Port may issue a Proposal Request directing the Contractor to propose a change to the Contract Sum and/or Contract Time, if any, based on a proposed change in the Work. The Contractor shall submit a responsive Change Order proposal as soon as possible, and no later than fourteen (14) days after receipt, in which the Contractor specifies in good faith the extent to which the Contract Sum and/or Contract Time would change. All cost components shall be limited to the manner described in Section 8.02(B). If the Contractor fails to timely respond to a Proposal Request, the Port may issue the change as a Unilateral Change Directive.
1. Fixed price method is default for Contractor Change Order proposal. When the Port has requested that the Contractor submit a Change Order proposal, the Port may specify the basis on which the Contract Sum will be adjusted by the Contractor. The Engineer's preference, unless otherwise indicated, is for changes in the Work to be priced using Lump Sums or Unit Prices or on a time and material (Force Account) basis if unit pricing or lump sums cannot be negotiated or determined. In all instances, however, proposed changes shall include a not-to-exceed price for the change and shall be itemized for evaluation purposes in accordance with Section 8.02(B), as requested by the Engineer.
  2. The Port may accept or reject the Contractor's Change Order proposal, request further documentation, or negotiate acceptable terms with the Contractor. If The Port and Contractor reach agreement on the terms of any change in the Work, including any adjustment in the Contract Sum or Contract Time, such agreement shall be incorporated in a Change Order.
  3. The Change Order shall constitute full payment and final settlement of all claims for time and for direct, indirect, and consequential costs, including costs of delays, inconvenience, disruption of schedule, or loss of efficiency or productivity, related to any Work either covered or affected by the Change Order, or related to the events giving rise to the request for equitable adjustment. The Port may reject a proposal, in which case the Port may either not effectuate the change or issue a Unilateral Change Directive. The Port will not make payment to the Contractor for any work until that work has been incorporated into an executed Change Order.
- D. Unforeseen Conditions: If the Contractor encounters conditions at the site that are: (1) subsurface or otherwise concealed physical conditions that differ materially from those indicated in the Contract Documents or any soils reports made available by the Port to the Contractor, or (2) unknown physical conditions of an unusual nature that differ materially from those ordinarily found to exist and generally recognized as inherent in construction activities of the character provided for in the Contract Documents, the Contractor shall immediately provide oral notice to the Engineer before conditions are disturbed, followed within 24 hours by an initial written notice. The Contractor shall submit a detailed proposal no later than seven (7) days following discovery of differing site conditions. The Engineer will promptly investigate these conditions and, if the Engineer determines that they differ materially and cause an increase or decrease in the Contractor's cost or time required for performance of any part of the Work, will establish a change in the Contract Sum or Contract Time, or both, consistent with the requirements of the Contract Documents. If the Contractor disputes the Engineer's determination, the Contractor may proceed as provided in the dispute resolution procedure (Article 11). No increase to the Contract Sum or the Contract Time shall be allowed if the Contractor does not comply with the contractual requirements or if the Contractor knew, or reasonably should have known, of the concealed conditions prior to executing the Contract.

- E. Proceed Immediately: Pending agreement on the terms of the Change Order or upon determination of a differing site condition as defined in 8.01(D), the Engineer may direct Contractor to proceed immediately with the change in the Work. Contractor shall not proceed with any change in the Work until it has obtained the Engineer's written approval and documentation of the following:
1. The scope of work
  2. An agreed upon maximum not-to-exceed amount
  3. The method of final cost determination
  4. Estimated time to complete the changed work
  5. As a change in the Work is performed, unless the parties have signed a written Change Order to establish the cost of the change, the Contractor shall maintain an itemized accounting of all costs related to the change based on the categories in Section 8.02(B) and provide such data to the Port upon request. This includes, without limitation, invoices, including freight and express bills, and other support for all material, equipment, Subcontractor, and other charges related to the change and, for material furnished from the Contractor's own inventory, a sworn affidavit certifying the actual cost of such material. Failure to provide data to the Port within seven (7) days of a request constitutes a waiver of any claim. The Port may furnish any material or equipment to the Contractor that it deems advisable, and the Contractor shall have no claim for any costs or fee on such material or equipment.
- F. Procedure for Unilateral Change Directive. Whether or not the Port has rejected a Contractor's proposal, the Port may issue a Unilateral Change Directive and the Contractor shall promptly proceed with the specified Work. If the Contractor disagrees with a Unilateral Change Directive, the Contractor shall advise the Port in writing through a Change Order proposal within seven (7) days of receipt. The Contractor's Change Order proposal shall reasonably specify the reasons for any disagreement and the adjustment it proposes. Without this timely Change Order proposal, the Contractor shall conclusively be deemed to have accepted the Port's proposal.
- G. Payment pending final determination of Force Account work. Pending final determination of the total cost of Force Account Work, and provided that the Work to be performed under Force Account is complete and any reservations of rights have been signed by the Port, the Contractor may request payment for amounts not in dispute in the next Application for Payment accompanied by documentation indicating the parties' agreement. Work done on a Force Account basis must be approved in writing on a daily basis by the Engineer or the Engineer's designee and invoices shall be submitted with an Application for Payment within sixty (60) days of performance of the Work.

## 8.02 CHANGES IN THE CONTRACT SUM

- A. Port to Decide How Changes are Measured. The Port may elect, in its sole discretion, how changes in the Work will be measured for payment. Change in the Work may be priced on a lump sum basis, through Unit Prices, as Force Account, or by another method documented in the executed Change Order, Unilateral Change Directive, or Minor Change in the Work.
- B. Determination of Cost of Change. The total cost of any change in the Work, including a claim under Article 11, shall not exceed the prevailing cost for the Work in the locality of the Project. In all circumstances, the change in the Work shall be limited to the reasonable, actual cost of the following components:

1. Direct labor costs: These are the actual labor costs determined by the number of additional craft hours at their normal hourly rate necessary to perform a change in the Work. The hourly cost of labor will be based upon the following:
  - a. Basic wages and fringe benefits: The hourly wage (without markup or labor burden) and fringe benefits paid by the Contractor as established by the Washington Department of Labor and Industries or contributed to labor trust funds as itemized fringe benefits, whichever is applicable, not to exceed that specified in the applicable "Intent to Pay Prevailing Wage," for the laborers, apprentices, journeymen, and foremen performing or directly supervising the change in the Work on site. These wages do not include the cost of Contractor's project manager or superintendent or above, and the premium portion of overtime wages is not included unless pre-approved in writing by the Port. Costs paid or incurred by the Contractor for vacations, per diem, subsistence, housing, travel, bonuses, stock options, or discretionary payments to employees are not separately reimbursable. The Contractor shall provide to the Port copies of payroll records, including certified payroll statements for itself and Subcontractors of any tier, upon the Port's request.
  - b. Workers' insurance: Direct contributions to the State of Washington as industrial insurance; medical aid; and supplemental pension by class and rates established by the Washington Department of Labor and Industries.
  - c. Federal insurance: Direct contributions required by the Federal Insurance Compensation Act (FICA); Federal Unemployment Tax Act (FUTA); and State Unemployment Compensation Act (SUCA).
2. Direct material costs: This is an itemization, including material invoices, of the quantity and actual cost of additional materials necessary to perform the change in the Work. The cost will be the net cost after all discounts or rebates, freight costs, express charges, or special delivery costs, when applicable. No lump sum costs will be allowed unless approved in advance by the Port.
3. Construction equipment usage costs: This is an itemization of the actual length of time that construction equipment necessary and appropriate for the Work is used solely on the changed Work times the applicable rental cost as established by the lower of the local prevailing rates published in [www.equipmentwatch.com](http://www.equipmentwatch.com), as modified by the AGC/WSDOT agreement, or the actual rate paid to an unrelated third party. If more than one rate is applicable, the lowest available rate will be utilized. Rates and quantities of equipment rented that exceed the local fair market rental costs shall be subject to the Port's prior written approval. Total rental charges for equipment or tools shall not exceed 75% of the fair market purchase value of the equipment or the tool. Actual, reasonable mobilization costs are permitted if the equipment is brought to the site solely for the change in the Work. Mobilization and standby costs shall not be charged for equipment already present on the site.

The rates in effect at the time of the performance of the changed Work are the maximum rates allowable for equipment of modern design, and in good working condition, and include full compensation for furnishing all fuel, oil, lubrication, repairs, maintenance, and insurance. No gas surcharges are payable. Equipment not of modern design and/or not in good working condition will have lower rates. Hourly, weekly, and/or monthly rates, as appropriate, will be applied to yield the lowest total cost.

4. Subcontractor costs: These are payments the Contractor makes to Subcontractors for changed Work performed by Subcontractors. The Subcontractors' cost of changed Work shall be determined in the same manner as prescribed in this Section 8.02 and, among other things, shall not include consultant costs, attorneys' fees, or claim preparation expenses.
5. Service provider costs: These are payments the Contractor makes to service providers for changed Work performed by service providers. The service providers' cost of changed Work shall be determined in the same manner as prescribed in this Section 8.02.
6. Markup: This is the maximum total amount for overhead, profit, and other costs, including office, home office and site overhead (including purchasing, project manager, superintendent, project engineer, estimator, and their vehicles and clerical assistants), taxes (except for sales tax on the Contract Sum), warranty, safety costs, printing and copying, layout and control, quality control/assurance, small or hand tools (a tool that costs \$500 or less and is normally furnished by the performing contractor), preparation of as-built drawings, impact on unchanged Work, Change Order and/or claim preparation, and delay and impact costs of any kind (cumulative, ripple, or otherwise), added to the total cost to the Port of any Change Order work. No markup shall be due, however, for direct settlements of Subcontractor claims by the Port after Substantial Completion. The markup shall be limited in all cases to the following schedule:
  - a. Direct labor costs -- 20% markup on the direct cost of labor for the party (Contractor or Subcontractor) providing labor related to the change in the Work;
  - b. Direct material costs -- 20% markup on the direct cost of material for the party (Contractor or Subcontractor) providing material related to the change in the Work;
  - c. Construction equipment usage costs -- 10% markup on the direct cost of equipment for the party (Contractor or Subcontractor) providing equipment related to the change in the Work;
  - d. Contractor markup on Subcontractor costs -- 10% markup for the Contractor on the direct cost (excluding markup) of a change in the Work performed by Subcontractors (and for Subcontractors, for a change in the Work performed by lower-tier Subcontractors); and
  - e. Service provider costs -- 5% markup for the Contractor on the direct cost (excluding markup) of a change in the Work performed by service providers.

The total summed markup of the Contractor and all Subcontractors of any tier shall not exceed 30% of the direct costs of the change in the Work. If the markup would otherwise exceed 30%, the Contractor shall proportionately reduce the markup for the Contractor and all Subcontractors of any tier.
7. Cost of change in insurance or bond premium. This is defined as:
  - a. Contractor's liability insurance: The actual cost (expressed as a percentage submitted with the certificate of insurance provided under the Contract Documents and subject to audit) of the Contractor's liability insurance arising directly from the changed Work; and
  - b. Public works bond: The actual cost (expressed as a percentage submitted under the Contract Documents and subject to audit) of the Contractor's performance and payment bond arising directly from the changed Work.

Upon request, the Contractor shall provide the Port with supporting documentation from its insurer or surety of any associated cost incurred. The cost of the insurance or bond premium together shall not exceed 2.0% of the cost of the changed Work.

8. Unit Prices. If Unit Prices are specified in the Contract Documents or established by agreement of the parties for certain Work, the Port may apply them to the changed Work. Unit Prices shall include pre-agreed rates for material quantities and shall include reimbursement for all direct and indirect costs of the Work, including overhead, profit, bond, and insurance costs arising out of, or related to, the Unit Priced item. Quantities must be supported by field measurement statements signed by the Port, and the Port shall have access as necessary for quantity measurement. The Port shall not be responsible for not-to-exceed limit(s) without its prior written approval.

### 8.03 CHANGES IN THE CONTRACT TIME

- A. Extension of the Contract Time. If the Contractor is delayed at any time in the commencement or progress of the Work by events for which the Port is responsible, by unanticipated abnormal weather (subject to Section 8.03(E) below), or by other causes not the fault or responsibility of the Contractor that the Port determines may justify a delay in the Contract Time, then the Contract Time shall be extended by Change Order for such reasonable time as the Port may determine. In no event, however, shall the Contractor be entitled to any extension of time absent proof of: (1) delay to an activity on the critical path of the Project, or (2) delay transforming an activity to the critical path, so as to actually delay the anticipated date of Substantial Completion.
- B. Allocation of responsibility for delay not caused by Port or Contractor. If a delay was not caused by the Port, the Contractor, or anyone acting on behalf of any of them, the Contractor is entitled only to an increase in the Contract Time but not an increase in the Contract Sum.
- C. Allocation of responsibility for delay caused by Port. If a delay was caused by the Port or someone acting on behalf of the Port and affected the critical path, the Contractor shall be entitled to a change in the Contract Time and Contract Sum in accordance with Section 8.02. The Contractor shall not recover damages, an equitable adjustment, or an increase in the Contract Sum or Contract Time from the Port; however, where the Contractor could reasonably have avoided the delay. The Port is not obligated directly or indirectly for damages for any delay suffered by a Subcontractor of any tier that does not increase the Contract Time.
- D. Allocation of responsibility for delay caused by Contractor. If a delay was caused by the Contractor, a Subcontractor of any tier, or anyone acting on behalf of any of them, the Contractor is not entitled to an increase in the Contract Time or in the Contract Sum.
- E. Adverse weather. If adverse weather is identified as the basis for a claim for additional time, the claim shall be documented by data substantiating that weather conditions were abnormal for the period of time, could not reasonably have been anticipated and had an adverse effect on the critical path of construction, and that the Work was on schedule (or not behind schedule through the fault of the Contractor) at the time the adverse weather conditions occurred. Neither the Contract Time nor the Contract Sum will be adjusted for normal inclement weather. For a claim based on adverse weather, the Contractor shall be eligible only for a change in the Contract Time (but not a change in the Contract Sum) if the Contractor can substantiate that there was significantly greater than normal inclement weather considering the full term of the Contract Time.

- F. Damages for delay. In the event the Contractor (including any Subcontractors of any tier) is held to be entitled to damages from the Port for delay beyond the amount permitted in Section 8.02(B), the total combined damages to the Contractor and any Subcontractors of any tier for each day of delay shall be limited to the reasonable, actual costs of the delay for which the Port is wholly responsible. The limitation on damages set forth in this Section does not apply to any damages arising exclusively from delay to which the Contractor is entitled to recover under Section 8.03(F).
- G. Limitation on damages. The Contractor shall not be entitled to damages arising out of loss of efficiency; morale, fatigue, attitude, or labor rhythm; constructive acceleration; home office overhead; expectant under run; trade stacking; reassignment of workers; rescheduling of Work, concurrent operations; dilution of supervision; learning curve; beneficial or joint occupancy; logistics; ripple; season change; extended or increased overhead or general conditions; profit upon damages for delay; impact damages including cumulative impacts; or similar damages. Any effect that such alleged costs may have upon the Contractor or its Subcontractors of any tier is fully compensated through the markup on Change Orders paid through Section 8.02(B).

#### 8.04 RESERVATION OF RIGHTS

- A. Reservations of rights void unless signed by Port. Reservations of rights will be deemed waived and are void unless any reserved rights are described in detail and are signed by the Contractor and the Port.
- B. Procedure for unsigned reservations of rights. If the Contractor adds a reservation of rights not signed by the Port to any Change Order, Unilateral Change Directive, Change Order proposal, Application for Payment, or any other document, all amounts and all Work therein shall be considered disputed and not payable until costs are re-negotiated or the reservation is withdrawn or changed in a manner satisfactory to, and signed by, the Port. If the Port makes payment based on a document that contains a reservation of rights not signed by the Port, and if the Contractor cashes such payment, then the reservation of rights shall be deemed waived, withdrawn, and of no effect.

#### 8.05 UNIT PRICES

- A. Adjustment to Unit Prices. If Unit Prices are stated in the Contract Documents or subsequently agreed upon, and if quantities originally contemplated are materially changed (less than eighty percent (80%) or more than one hundred and twenty percent (120%) of the quantity estimated) so that application of a Unit Price would be substantially unfair, the applicable Unit Price but not the Contract Time, shall be adjusted if the Port prospectively approves a Change Order revising the Unit Price.
- B. Procedure to change Unit Prices. The Contractor or Port may request a Change Order revising a Unit Price by submitting information to support the change. A proposed change to a Unit Price will be evaluated by the Port based on the change in cost resulting solely from the change in quantity, any change in production rate or method as compared to the original plan, and the share, if any, of fixed expenses properly chargeable to the item. If the Port and Contractor agree on the change, a Change Order will be executed. If the parties cannot agree, the Contractor shall comply with the dispute resolution procedures (Article 11).

### **ARTICLE 9 - SUSPENSION AND TERMINATION OF CONTRACT**

#### 9.01 PORT'S RIGHT TO SUSPEND WORK

- A. Port may suspend the Work. The Port may at any time suspend the Work, or any part thereof, by giving notice to the Contractor. The Work shall be resumed by the Contractor as soon as possible, but no later than fourteen (14) days after the date fixed in a notice to resume the Work. The Port shall reimburse the Contractor for appropriate and reasonable expenses consistent with Section 8.02 incurred by the Contractor as a result of the suspension, except where a suspension is the result of the Contractor repeatedly or materially failing to carry out or correct the Work in accordance with the Contract Documents, and the Contractor shall take all necessary steps to minimize expenses.
- B. Contractor obligations. During any suspension of Work, the Contractor shall take every precaution to prevent damage to, or deterioration of, the Work. The Contractor shall be responsible for all damage or deterioration to the Work during the period of suspension and shall, at its sole expense, correct or restore the Work to a condition acceptable to the Port prior to resuming Work.

#### 9.02 TERMINATION OF CONTRACT FOR CAUSE BY THE PORT

- A. Port may terminate for cause. If the Contractor is adjudged bankrupt or makes a general assignment for the benefit of the Contractor's creditors, if a receiver is appointed due to the Contractor's insolvency, or if the Contractor, in the opinion of the Port, persistently or materially refuses or fails to supply enough properly skilled workmen or materials for proper completion of the Contract, fails to make prompt payment to Subcontractors or suppliers for material or labor, disregards laws, ordinances, or the instructions of the Port, fails to prosecute the Work continuously with promptness and diligence, or otherwise materially violates any provision of the Contract, then the Port, without prejudice to any other right or remedy, may terminate the Contractor after giving the Contractor seven (7) days' written notice (during which period the Contractor shall have the right to cure).
- B. Procedure following termination for cause. Following a termination for cause, the Port may take possession of the Project site and all materials and equipment, and utilize such materials and equipment to finish the Work. The Port may also exclude the Contractor from the Project site(s). If the Port elects to complete all or a portion of the Work, it may do so as it sees fit. The Port shall not be required to accept the lowest bid for completion of the Work and may choose to complete all or a portion of the Work using its own work force. If the Port elects to complete all or a portion of the Work, the Contractor shall not be entitled to any further payment until the Work is finished. If the expense of finishing the Work, including compensation for additional managerial and administrative services of the Port, exceeds the unpaid balance of the Contract Sum, the excess shall be paid by the Contractor.
- C. Port's remedies following termination for cause. The Port may exercise any rights, claims, or demands that the Contractor may have against third persons in connection with the Contract, and for this purpose the Contractor assigns and transfers to the Port all such rights, claims, and demands.
- D. Inadequate termination for cause converted to termination for convenience. If, after the Contractor has been terminated for cause, it is determined that inadequate "cause" for such termination exists, then the termination shall be considered a termination for convenience pursuant to Section 9.03.

#### 9.03 TERMINATION OF CONTRACT FOR CONVENIENCE BY THE PORT

- A. Port may terminate for convenience. The Port may, at any time (without prejudice to any right or remedy of the Port), terminate all, or any portion of, the Contract for the Port's convenience and without cause. The Contractor shall be entitled to receive payment consistent with the Contract Documents only for Work properly executed through the date of termination, and costs necessarily incurred by reason of the termination (such as the cost of settling and paying claims arising out of the termination under subcontracts or orders), along with a fee of one percent (1%) of the Contract Sum not yet earned on the whole or part of the Work. The total amount to be paid to the Contractor shall not exceed the Contract Sum as reduced by the amount of payments otherwise made. The Port shall have title to all Work performed through the date of termination.

#### 9.04 TERMINATION OF CONTRACT BY THE CONTRACTOR

- A. Contractor may terminate for cause. The Contractor may terminate the Contract if the Work is stopped for a period of sixty (60) consecutive days through no act or fault of the Contractor or a Subcontractor of any tier, for either of the following reasons:
  - 1. Issuance of an order of a court or other public authority having jurisdiction that requires all Work to be stopped; or
  - 2. An act of government, such as a declaration of national emergency, that requires all Work to be stopped.
- B. Procedure for Contractor termination. If one of the reasons described in Section 9.04A exists, the Contractor may, upon seven (7) days' written notice to the Port (during which period the Port has the opportunity to cure), terminate the Contract and recover from the Port payment for Work executed through the date of termination in accordance with the Contract Documents and for proven loss with respect to materials, equipment, tools, and construction equipment and machinery, including reasonable overhead and profit on Work executed and direct costs incurred by reason of such termination. The total recovery of the Contractor shall not exceed the unpaid balance of the Contract Sum.
- C. Contractor may stop the Work for failure of Port to pay undisputed amounts. The Contractor may stop Work under the Contract if the Port does not pay undisputed amounts due and owing to the Contractor within fifteen (15) days of the date established in the Contract Documents. If the Port fails to pay undisputed amounts, the Contractor may, upon fifteen (15) additional days' written notice to the Port, during which the Port can cure, stop the Work until payment of the amount owing has been received. The Contract Time shall be extended appropriately, and the Contract Sum shall be increased by the amount of the Contractor's reasonable costs of shut-down, delay, and start-up.

#### 9.05 SUBCONTRACT ASSIGNMENT UPON TERMINATION

- A. Subcontracts assigned upon termination. Each subcontract is hereby assigned by the Contractor to the Port provided that:
  - 1. The Port requests that the subcontract be assigned.
  - 2. The assignment is effective only after termination by the Port and only for those subcontracts that the Port accepts in writing.
  - 3. The assignment is subject to the prior rights of the surety, if any, under any bond issued in accordance with the Contract Documents.

When the Port accepts the assignment of a subcontract, the Port assumes the Contractor's rights and obligations under the subcontract, but only for events and payment obligations that arise after the date of the assignment.

## **ARTICLE 10 - BONDS**

### **10.01 CONTRACTOR PERFORMANCE AND PAYMENT BONDS**

- A. Contractor to furnish performance and payment bonds. Within ten (10) days following its receipt of a notice of award, and as part of the Contract Sum, the Contractor shall secure and furnish duly executed performance and payment bonds using the forms furnished by the Port. The bonds shall be executed by a surety (or sureties) reasonably acceptable to the Port, admitted and licensed in the State of Washington, registered with the Washington State Insurance Commissioner, and possessing an A.M. Best rating of "A-, FSC (6)" or better and be authorized by the U.S. Department of the Treasury. Pursuant to RCW 39.08, the bonds shall be in an amount equal to the Contract Sum, and shall be conditioned only upon the faithful performance of the Contract by the Contractor within the Contract Time and upon the payment by the Contractor of all taxes, fees, and penalties to the State of Washington and all laborers, Subcontractors, and suppliers, and others who supply provisions, equipment, or supplies for the performance of the Work covered by this Contract. The bonds shall be signed by the person or persons legally authorized to bind the Contractor.
- B. On contracts of one hundred fifty thousand dollars or less, at the option of the contractor as defined in RCW 39.10.210, the Port may, in lieu of the bond, retain ten percent of the contract amount for a period of thirty days after date of final acceptance, or until receipt of all necessary releases from the department of revenue, the Employment Security Department, and the Department of Labor and Industries and settlement of any liens filed under chapter 60.28 RCW, whichever is later. The recovery of unpaid wages and benefits must be the first priority for any actions filed against retainage held by a state agency or authorized local government.  
  
For contracts of one hundred fifty thousand dollars or less, the Port may accept a full payment and performance bond from an individual surety or sureties.
- C. Port may notify surety. If the Port makes or receives a claim against the Contractor, the Port may, but is not obligated to, notify the Contractor's surety of the nature and amount of the claim. If the claim relates to a possibility of a Contractor's default, the Port may, but is not obligated to, notify the surety and request the surety's assistance in resolving the controversy.

## **ARTICLE 11 - DISPUTE RESOLUTION**

### **11.01 NOTICE OF PROTEST AND CLAIM**

- A. Dispute resolution procedure mandatory. All claims, direct or indirect, arising out of, or relating to, the Contract Documents or the breach thereof, shall be decided exclusively by the following alternative dispute resolution procedure, unless the parties mutually agree otherwise. If the Port and Contractor agree to a partnering process to assist in the resolution of disputes, the partnering process shall occur prior to, and not be in place of, the mandatory dispute resolution procedures set forth below.

- B. Notice of protest defined. Except for claims requiring notice before proceeding with the affected Work as otherwise described in the Contract Documents, the Contractor shall provide immediate oral notice of protest to the Engineer prior to performing any disputed Work and shall submit a written notice of protest to the Port within seven (7) days of the occurrence of the event giving rise to the protest that includes a clear description of the event(s). The protest shall identify any point of disagreement, those portions of the Contract Documents believed to be applicable, and an estimate of quantities and costs involved. When a protest relates to cost, the Contractor shall keep full and complete records and shall permit the Port to have access to those records at any time as requested by the Port.
- C. Claim defined. A claim is a demand by one of the parties seeking adjustment or interpretation of the Contract terms, payment of money, extension of time, or other relief with respect to the terms of the Contract Documents. The term "claim" also includes all disputes and matters in question between the Port and Contractor arising out of, or relating to, the Contract Documents. Claims must be initiated in writing and include a detailed factual statement and clear description of the claim providing all necessary dates, locations, and items of Work, the date or dates on which the events occurred that give rise to the claim, the names of employees or representatives knowledgeable about the claim, the specific provisions of the Contract Documents that support the claim, any documents or oral communications that support the claim, any proposed change in the Contract Sum (showing all components and calculations) and/or Contract Time (showing cause and analysis of the resultant delay in the critical path), and all other data supporting the claim. Claims shall also be submitted with a statement certifying, under penalty of perjury, that the claim as submitted is made in good faith, that the supporting cost and pricing data are true and accurate to the best of Contractor's knowledge and belief, that the claim is fully supported, and that the amount requested accurately reflects the adjustment in the Contract Sum or Contract Time for which Contractor believes the Port is liable. A claim shall be deemed to include all changes, direct and indirect, in cost and in time to which the Contractor and Subcontractors of any tier are entitled and may not contain reservations of rights without the Port's written approval; any unapproved reservations of rights shall be without effect.
- D. Claim procedure. The Contractor shall submit a written claim within thirty (30) days of providing written notice of protest. The Contractor may delay submitting supporting data by an additional thirty (30) days if it notifies the Port in its claim that substantial data must be assembled. Any claim of a Subcontractor of any tier may be brought only through, and after review by and concurrence of, the Contractor.
- E. Failure to comply with notice of protest and claim requirements waives claims. Any notice of protest by the Contractor and any claim of the Contractor, whether under the Contract or otherwise, must be made pursuant to, and in strict accordance with, the applicable provisions of the Contract. Failure to properly and timely submit a notice of protest or to timely submit a claim shall waive the claim. No act, omission, or knowledge, actual or constructive, of the Port shall waive the requirement for timely written notice of protest and a timely written claim, unless the Port and the Contractor sign an explicit, unequivocal written waiver approved by the Port. The Contractor expressly acknowledges and agrees that the Contractor's failure to timely submit required notices of protest and/or timely submit claims has a substantial impact upon, and prejudices, the Port. For the purpose of calculating time periods, an "event giving rise to a claim," among other things, is not a Request for Information, but rather is a response that the Contractor believes would change the Contract Sum and/or Contract Time.

- F. False claims. The Contractor shall not make any fraudulent misrepresentations, concealments, errors, omissions, or inducements to the Port in the formation or performance of the Contract. If the Contractor or a Subcontractor of any tier submits a false or frivolous claim to the Port, which for purposes of this Section 11.01(F) is defined as a claim based in whole or in part on a materially incorrect fact, statement, representation, assertion, or record, the Port shall be entitled to collect from the Contractor by offset or otherwise (without prejudice to any right or remedy of the Port) any and all costs and expenses, including investigation and consultant costs, incurred by the Port in investigating, responding to, and defending against the false or frivolous claim.
- G. Compliance with lien and retainage statutes required. If a claim relates to, or is the subject of, a lien or retainage claim, the party asserting the claim may proceed in accordance with applicable law to comply with the notice and filing deadlines prior to resolution of the claim by mediation or by litigation.
- H. Performance required pending claim resolution. Pending final resolution of a claim, the Contractor shall continue to perform the Contract and maintain the Baseline Project Schedule, and the Port shall continue to make payments of undisputed amounts due in accordance with the Contract Documents.

#### 11.02 MEDIATION

- A. Claims must be subject to mediation. At any time following the Port's receipt of a written claim, the Port may require that an officer of the Contractor and the Port's designee (all with authority to settle) meet, confer, and attempt to resolve a claim. If the claim is not resolved during this meeting, the claim shall be subject to mandatory mediation as a condition precedent to the initiation of litigation. This requirement can be waived only by an explicit, written waiver signed by the Port and the Contractor.
- B. Mediation procedure. A request for mediation shall be filed in writing with the other party to the Contract, and the parties shall promptly attempt to agree upon a mediator. If the parties have not reached agreement within thirty (30) days of the request, either party may file the request with the American Arbitration Association, or such other alternative dispute resolution service to which the parties mutually agree, with a copy to the other party, and the mediation shall be administered by the American Arbitration Association (or other agreed service). The parties to the mediation shall share the mediator's fee and any filing fees equally. The mediation shall be held in Pierce County, Washington, unless another location is mutually agreed upon. Agreements reached in mediation shall be enforceable as settlement agreements in any court having jurisdiction thereof. Unless the Port and the Contractor mutually agree in writing otherwise, all claims shall be considered at a mediation session that shall occur prior to Final Completion.

#### 11.03 LITIGATION

- A. Claims not resolved by mediation are subject to litigation. Claims not resolved through mediation shall be resolved by litigation, unless the parties mutually agree otherwise. The venue for any litigation shall be Pierce County, Washington. The Contractor may bring no litigation on claims, unless such claims have been properly raised and considered in the procedures of this Article 11. The Contractor must demonstrate in any litigation that it complied with all requirements of this Article.

- B. Litigation must be commenced promptly. All unresolved claims of the Contractor shall be waived and released, unless the Contractor has complied with the requirements of the Contract Documents, and litigation is served and filed within 180 days of the date of Substantial Completion approved in writing by the Port or termination of the Contract. The pendency of mediation (the time period between receipt by the non-requesting party of a written mediation request and the date of mediation) shall toll these deadlines until the earlier of the mediator providing written notice to the parties of impasse, or thirty (30) days after the date of the mediation session.
- C. Port not responsible for attorneys' fees. Neither the Contractor nor a Subcontractor of any tier, whether claiming under a bond or lien statute or otherwise, shall be entitled to attorneys' fees directly or indirectly from the Port (but may recover attorneys' fees from the bond or statutory retainage fund itself to the extent allowable under law).
- D. Port may join Contractor in dispute. The Port may join the Contractor as a party to any litigation or arbitration involving the alleged fault, responsibility, or breach of contract of the Contractor or Subcontractor of any tier.

## **ARTICLE 12 - MISCELLANEOUS**

### 12.01 GENERAL

- A. Rights and remedies are cumulative. The rights and remedies of the Port set forth in the Contract Documents are cumulative, and in addition to and not in limitation of, any rights and remedies otherwise available to the Port. The pursuit of any remedy by the Port shall not be construed to bar the Port from the pursuit of any other remedy in the event of similar, different, or subsequent breaches of this Contract. All such rights of the Port shall survive completion of the Project or termination of the Contractor.
- B. Reserved rights do not give rise to duty. The rights reserved or possessed by the Port to take any action shall not give rise to a duty for the Port to exercise any such right.

### 12.02 WAIVER

- A. Waiver must be in writing and authorized by Port. Waiver of any provisions of the Contract Documents must be in writing and authorized by the Port. No other waiver is valid on behalf of the Port.
- B. Inaction or delay not a waiver. No action, delay in acting, or failure to act by the Port shall constitute a waiver of any right or remedy of the Port, or constitute an approval or acquiescence of any breach or defect in the Work, nor shall any delay or failure of the Port to act waive or otherwise prejudice the right of the Port to enforce a right or remedy at any subsequent time.
- C. Claim negotiation not a waiver. The fact that the Port and the Contractor may consider, discuss, or negotiate a claim that has or may have been defective or untimely under the Contract, shall not constitute a waiver of the provisions of the Contract Documents, unless the Port and the Contractor sign an explicit, unequivocal waiver.

### 12.03 GOVERNING LAW

- A. Washington law governs. This Contract and the rights and duties of the parties hereunder shall be governed by the internal laws of the State of Washington, without regard to its conflict of law principles.

### 12.04 COMPLIANCE WITH LAW

- A. Contractor to comply with applicable laws. The Contractor shall at all times comply with all applicable Federal, State and local laws, ordinances, and regulations. This compliance shall include, but is not limited to, the payment of all applicable taxes, royalties, license fees, penalties, and duties.
- B. Contractor to provide required notices. The Contractor shall give notices required by all applicable Federal, State and local laws, ordinances, and regulations bearing on the Work.
- C. Contractor to confine operations at site to permitted areas. The Contractor shall confine operations at the Project site to areas permitted by applicable laws, ordinances, permits, rules and regulations, and lawful orders of public authorities and the Contract Documents.

#### 12.05 ASSIGNMENT

- A. Assignment. The Port and Contractor respectively bind themselves, their partners, successors, assigns, and legal representatives to the other party and to the partners, successors, assigns, and legal representatives of such other party. The Contractor may not assign, transfer, or novate all or any portion of the Contract, including but not limited to, any claim or right to the Contract Sum, without the Port's prior written consent. If the Contractor attempts to make an assignment, transfer, or novation without the Port's consent, the assignment shall be of no effect, and Contractor shall nevertheless remain legally responsible for all obligations under the Contract. The Contractor also shall not assign or transfer, to any third party, any claims it may have against the Port arising under the Contract or otherwise related to the Project.

#### 12.06 TIME LIMIT ON CAUSES OF ACTION

- A. Time limit on causes of action. The Port and Contractor shall commence all causes of action, whether in contract, tort, breach of warranty, or otherwise, against the other arising out of, or related to, the Contract in accordance with the requirements of the dispute resolution procedure set forth in Article 11 of these General Conditions, within the time period specified by applicable law, and within the time limits identified in the Contract Documents. The Contractor waives all claims and causes of action not commenced in accordance with this Section 12.06.

#### 12.07 SERVICE OF NOTICE

- A. Notice. Written notice under the Contract Documents by either the Contractor or Port may be served on the other party by personal service, electronic or facsimile transmission, or delivery service to the last address provided in writing to the other party. For the purpose of measuring time, notice shall be deemed to be received by the other party on the next business day following the sender's electronic or facsimile transmittal or delivery by delivery service.

#### 12.08 RECORDS

- A. Contractor and Subcontractors to maintain records and cooperate with Port audit. The Contractor and Subcontractors of any tier shall maintain books, ledgers, records, documents, estimates, bids, correspondence, logs, schedules, emails, and other tangible and electronic data and evidence relating or pertaining to costs and/or performance of the Contract ("records") to such extent, and in such detail, as will properly reflect and fully support compliance with the Contract Documents and with all costs, charges, and other amounts of whatever nature. The Contractor shall preserve these records for a period of six (6) years following the date of Final Acceptance under the Contract. Within seven (7) days of the Port's request, both during the Project and for six (6) years following Final Acceptance, the Contractor and Subcontractors of any tier shall make available, at their office during normal business hours, all records for inspection, audit, and reproduction (including electronic reproduction) by the Port or its representatives; failure to fully comply with this requirement shall constitute a material breach of contract and a waiver of all claims by the Contractor and Subcontractors of any tier.
- B. Rights under RCW 42.56. The Contractor agrees, on behalf of itself and Subcontractors of any tier, that any rights under Chapter 42.56 RCW will commence at Final Acceptance, and that the invocation of such rights at any time by the Contractor or a Subcontractor of any tier, or their respective representatives, shall initiate an equivalent right to disclosures from the Contractor and Subcontractors of any tier for the benefit of the Port.

#### 12.09 STATUTES

- A. Contractor to comply with Washington statutes. The Contractor shall abide by the provisions of all applicable statutes, regulations, and other laws. Although a number of statutes are referenced in the Contract Documents, these references are not meant to be, and are not, a complete list.
  - 1. Pursuant to RCW 39.06, "Registration, Licensing of Contractors," the Contractor shall be registered and licensed as required by the laws of the State of Washington, including but not limited to RCW 18.27, "Registration of Contractors," and shall satisfy all State of Washington bonding and insurance requirements. The Contractor shall also have a current state Unified Business Identifier number; have industrial insurance coverage for the Contractor's employees working in Washington as required by Title 51 RCW; have an Employment Security Department number as required by Title 50 RCW; have a state excise tax registration number as required in Title 82 RCW; and not be disqualified from bidding on any public works contract under RCW 39.06.010 (unregistered or unlicensed contractors) or RCW 39.12.065(3) (prevailing wage violations).
  - 2. The Contractor shall comply with all applicable provisions of RCW 49.28, "Hours of Labor."
  - 3. The Contractor shall comply with pertinent statutory provisions relating to public works of RCW 49.60, "Discrimination."
  - 4. The Contractor shall comply with pertinent statutory provisions relating to public works of RCW 70.92, "Provisions in Buildings for Aged and Handicapped Persons," and the Americans with Disabilities Act.
  - 5. Pursuant to RCW 50.24, "Contributions by Employers," in general, and RCW 50.24.130 in particular, the Contractor shall pay contributions for wages for personal services performed under this Contract or arrange for an acceptable bond.
  - 6. The Contractor shall comply with pertinent provisions of RCW 49.17, "Washington Industrial Safety and Health Act," and Chapter 296-155 WAC, "Safety Standards for Construction Work."

7. Pursuant to RCW 49.70, "Worker and Community Right to Know Act," and WAC 296-62-054 et seq., the Contractor shall provide to the Port, and have copies available at the Project site, a workplace survey or material safety data sheets for all "hazardous" chemicals under the control or use of Contractor or any Subcontractor of any tier.
8. All products and materials incorporated into the Project as part of the Work shall be certified as "asbestos-free" and "lead-free" by United States standards, and shall also be free of all hazardous materials or substances. At the completion of the Project, the Contractor shall submit certifications of asbestos-free and of lead-free materials certifying that all materials and products incorporated into the Work meet the requirements of this Section, and shall also certify that materials and products incorporated into the Work are free of hazardous materials and substances.

**END OF SECTION**

## **PART 1 - GENERAL**

### **1.01 DEFINITIONS**

- A. The Work for the Project is defined as the scope of work set forth in each Task Order. The general term Work includes the overall scope of the on-call contract for On-Call Pavement Repairs (2026) and miscellaneous associated tasks.
- B. Project Submittals are submittals due with each Task Order. General Submittals are for the overall on-call contract for On-Call Pavement Repairs (2026). General Submittals includes all pre-award submittals and additionally (but not limited to) the following:
  - 1. Weighted Wage Rates
  - 2. Contractors Equipment Rates and List
  - 3. Emergency Contacts
- C. The Project Manager is the individual identified by the Port as having delegated authority under the Contract for the specific Task Order.
- D. The definitions of "night" and "weekend" work are used for scheduling and coordination purposes only; they do not imply entitlement to overtime compensation. Contractors are solely responsible for complying with all applicable labor laws.

### **1.02 NIGHT AND WEEKEND WORK REQUIREMENTS**

- A. Due to operational constraints, tenant activities, and Port of Tacoma scheduling requirements, paving work is frequently required to occur during non-standard hours, including nights and weekends; contractor will be required to perform work on nights and weekends.
- B. For the purposed of this contract, "Nights and Weekends" shall be defined as work performed outside of standard business hours, subject to the following conditions:
  - 1. Standard Workday:
    - a. A Standard Workday shall be defined as work performed between 6:00 AM and 6:00 PM, Monday through Friday.
  - 2. Night Hours:
    - a. Night Hours shall be defined as work performed between 6:01 PM and 5:59 AM, Monday through Friday.
  - 3. Weekend Hours:
    - a. All work performed between 6:00 PM Friday and 6:00 AM Monday shall be considered "Weekend Hours".
- C. Contractors shall include in their bid all costs associated with performing work during Night and Weekend Hours. This includes labor availability and premiums, equipment and material availability, lighting, traffic control, and all other costs necessary to complete the work in accordance with the Contract Documents.

### **1.03 NIGHT AND WEEKEND COMPENSATION ELIGIBILITY**

- A. The contractor shall not be eligible for any premium rates above the unit amounts established by the Contract Documents.

#### 1.04 CONTRACTOR'S COST ESTIMATE

- A. Prior to any Work being performed by the Contractor, the Port's Project Manager identified for a Task Order will forward the Contractor a proposed scope of work and may additionally request a site visit with the Contractor. The Contractor shall review the proposed scope of work and become familiar with all site conditions, constraints, Night and Weekends, work requirements, and review the Contract Documents for specific requirements for the scope of work.
1. Contractor shall review with the assigned Project Manager the Work restraints, submittals, requirements for security and access to the site, and all other coordination and Task Order requirements that may be required and submit all costs associated with the Task Order with their Task Order proposal.
  2. Contractors shall include in their estimate all costs associated with performing work, including where applicable, Nights and Weekends; this includes, labor and material premiums, equipment availability, lighting, traffic control, and any other costs necessary to complete the work in accordance with Port standards and Contract Documents. No additional compensation above the established unit prices allowed, unless explicitly authorized in writing by the Port.
- B. The Contractor shall provide the Project Manager with a detailed cost estimate for the proposed scope of work, utilizing the units established by the contract documents, on the template provided by the Port. The Contractor's cost estimate shall identify the estimated unit quantities for the Work and, as needed, further labor, material, and equipment costs for the Work if no unit price exists for the type of Work being estimated.
1. For task order Work not included in the bid Schedule of Unit Prices, the additional Work will be paid as negotiated unit price(s), or lump sum(s), or on a time and material basis if unit pricing or lump sums cannot be negotiated at the time of Task Order negotiation. The Contractor shall provide backup information for its pricing of items not included on the Schedule of Unit Prices when requested by the Project Manager, including as needed Work proposed to be performed by a Subcontractor.
  2. The Contractor's cost estimate shall include only those mark-ups allowed by the Contract. Markups for Task Order pricing on time and material work and shall be as defined in Section 00 72 00 – General Conditions, paragraph 8.02 B. The estimate shall include a final Project estimate which will be the basis for the Task Order amount.
  3. The Contractor shall submit its cost estimate within five (5) calendar days of receipt of the proposed scope of work.
  4. Estimates shall also include an estimated start date and an estimated duration, in calendar days, to complete the proposed scope of work.
- C. EXECUTED TASK ORDERS
1. If the Port accepts the Contractor's cost estimate, the Port's Contracting Department will issue the Contractor an executed Task Order for the Work set forth therein. The Contractor shall do no Work without a fully executed Task Order from the Port. Work shall be coordinated through the Port's Project Manager.
- D. PROCEEDING WITH THE WORK

1. The Task Order will serve as notice to the Contractor to proceed. The Contractor shall begin work within fourteen (14) calendar days of receipt of the executed Task Order unless otherwise noted and agreed upon with the Port's Project Manager. No mobilization on site shall occur until all required pre-Work submittals are submitted and accepted by the Project Manager.

E. REVISION OF THE AMOUNT AUTHORIZED

1. The Contractor shall immediately notify the Port's Project Manager immediately if it ever determines that the Work cannot be completed within the Contract Time. The Contractor shall provide the Port's Project Manager with a revised estimate and schedule within two (2) calendar days of providing such notice. The Contractor shall not proceed with any Work that would result in exceeding the authorized not-to-exceed amount identified in the Task Order without confirmation from the Port's Project Manager. If a revised Task Order total is negotiated, the Port will issue an amendment to the Task Order.

F. PAYMENT FOR ON-CALL WORK

1. Upon satisfactory completion and acceptance of the Work, the Contractor shall submit to the Port an invoice for such Work. The Contractor shall attach a copy of the Task Order with the invoice.
2. The Port will not make payment on any Task Order invoice until all required Intents have been filed with the Department of Labor & Industries (L&I).
3. Contractor shall pay prevailing wages for all work that would otherwise be subject to the requirements of chapter 39.12 RCW. Prevailing wages for all work performed pursuant to each Task Order must be the prevailing wage rates in effect at the beginning date for each contract year. On-Call contracts shall have prevailing wage rates updated annually.
4. Intents and affidavits for prevailing wages paid shall be submitted annually for all work completed within the previous twelve- (12-) month period of the On-Call contract.
5. Payment will be based on the Schedule of Unit Prices. The Contractor shall include (or attach) the following items pertaining to the Project as part of each invoice:
  - a. Port assigned Contract number, and if applicable, Project ID number and Task ID number.
  - b. Quantity and type of Work as described in the Schedule of Unit Prices.
  - c. Copy of signed Contractor Work Authorization.
  - d. Contractor's Partial Release and Waiver of Lien (Form available on Port Website)
  - e. Amounts paid to Subcontractors and Suppliers (Form available on Port Website)
  - f. Copies of Intents to Pay Prevailing Wages for any new sub-tier contractor doing Work for the Task Order.
6. The invoice shall provide an itemized accounting of the labor, material, and equipment costs for the Work, all Subcontractor Work where applicable, and all approved mark-ups. Each invoice shall have backup documentation that supports the invoice including daily reports, material invoices and equipment rental invoices per the Schedule of Unit Prices.
7. Failure to provide completed invoice information and back-up documentation will delay the payment process and the invoice will be returned to the Contractor for completion.

8. When more than one invoice is submitted for an individual Task Order, the invoice shall clearly be marked Partial or Final invoice.

#### 1.05 COMPLETION

- A. Substantial Completion will be issued at the completion of each Task Order once all Work is complete and all Project submittals have been accepted by the Port and following any revision to the Task Order, as may be needed, is executed.
  1. The Project Manager will issue the Notice of Substantial Completion. Final Task Order Invoices should be submitted within thirty (30) days of such notice.
- B. Final Completion of the Contract will be determined once Substantial Completion has been determined and additional required submittals have been received by the Port.
- C. Final Acceptance will be issued once all additional required submittals have been accepted by the Port per the Contract Documents.

**PART 2 - PRODUCTS – NOT USED**

**PART 3 - EXECUTION – NOT USED**

**END OF SECTION**

## PART 1 - GENERAL

### 1.01 SUMMARY

- A. This Section includes requirements for the Contractor's insurance.

### 1.02 SUBMITTAL REQUIREMENTS

- A. Evidence of the required insurance within ten (10) days of the issued Notice of Award to the Contractor.
- B. Updated evidence of insurance as required until final completion.

### 1.03 COMMERCIAL GENERAL LIABILITY (CGL) INSURANCE

- A. The Contractor shall secure and maintain until Final Completion, at its sole cost and expense, the following insurance in carriers reasonably acceptable to the Port, licensed in the State of Washington, registered with the Washington State Insurance Commissioner, and possessing an A.M. Best rating of "A-, FSC six (6)" or better.
- B. The Port of Tacoma (Port) will be included as additional insureds for both ongoing and completed operations by endorsement to the policy using ISO Form CG 20 10 11 85 or forms CG 20 10 04 13 and CG 20 37 04 13 (or equivalent coverage endorsements). The inclusion of the Port as additional insureds shall not create premium liability for the Port.

Also, by endorsement to the policy, there shall be:

- 1. An express waiver of subrogation in favor of the Port;
  - 2. A cross liabilities clause; and
  - 3. An endorsement stating that the Contractor's policy is primary and not contributory with any insurance carried by the Port.
- C. If the Contractor, Supplier, or Subcontractors will perform any work requiring the use of a licensed professional, per RCW 18, the Contractor shall provide evidence to the Port of professional liability insurance in amounts not less than \$1,000,000.
  - D. This insurance shall cover all of the Contractor's operations, of whatever nature, connected in any way with the Contract, including any operations performed by the Contractor's Subcontractors of any tier. **It is the obligation of the Contractor to ensure that all Subcontractors (at whatever level) carry a similar program that provides the identified types of coverage, limits of liability, inclusion of the Port as additional insured(s), waiver of subrogation and cross liabilities clause.** The Port reserves the right to reject any insurance policy as to company, form, or substance. Contractor's failure to provide, or the Port's acceptance of, the Contractor's certificate of insurance does not waive the Contractor's obligation to comply with the insurance requirements of the Contract as specifically described below:
    - 1. Marine General Liability Insurance on an Occurrence Form Basis including, but not limited to:
      - a. Bodily Injury Liability;
      - b. Property Damage Liability;
      - c. Contractual Liability;
      - d. Products - Completed Operations Liability;

- e. Personal Injury Liability;
- f. By endorsement to the policy, not exclude work within fifty feet of any railroad track;
- g. Marine coverages as appropriate for the scope of work.

Alternatively, a Commercial General Liability (CGL) policy is acceptable if all of the above coverages are incorporated in the policy and there are no marine exclusions that will remove coverage for either vessels or work done by or above or around the water.

2. Marine Protection and Indemnity/Vessel Pollution Liability: Contractor shall obtain, at Contractor's expense and keep in effect during the term of the Contract, Marine Protection and Indemnity insurance which shall include Collision Liability and Jones Act coverages, including coverage for all masters, crew, and passengers. The limit of liability shall not be less than \$5,000,000. If Collision Liability is part of the Hull and Machinery coverage for the vessel, evidence of Hull and Machinery coverage in amounts not less than the actual cash value of the vessel shall also be provided.
  - a. Vessel Pollution Liability: Contractor shall obtain, at Contractor's expense and keep in effect during the term of the Contract, Vessel Pollution Liability on all vessels used under this Contract. Vessel Pollution Liability limits shall be the same as the Protection and Indemnity (P&I) limits called for in Section 2.
3. Comprehensive Automobile Liability including, but not limited to:
  - a. Bodily Injury Liability;
  - b. Property Damage Liability;
  - c. Personal Injury Liability;
  - d. Owned and Non-Owned Automobile Liability; and
  - e. Hired and Borrowed Automobile Liability.
4. Railroad protective liability insurance naming the Port and Tacoma Rail as Insureds with coverage of at least \$2,000,000 per occurrence and \$6,000,000 in the aggregate. The policy must be issued on a standard ISO form CG 00 35 10 93 and include the following:
  - a. Endorsed to include the Pollution Exclusion Amendment (ISO form CG 28 31 10 93);
  - b. Endorsed to include the Limited Seepage and Pollution Endorsement;
  - c. Endorsed to include Evacuation Expense Coverage Endorsement;
  - d. No other endorsements restricting coverage may be added; and
  - e. The original policy must be provided to the Port prior to execution of the Contract; within ten (10) days of Notice of Award.
5. Contractor's Pollution Liability (CPL) covering claims for bodily injury, property damage and cleanup costs, and environmental damages from pollution conditions arising from the performance of covered operations.
  - a. If the Work involves remediation or abatement of regulated waste to include, but not limited to asbestos containing materials, lead containing products, mercury, PCB, underground storage tanks, or other hazardous materials or substances, the CPL policy shall not exclude such coverage, or a specific policy covering such exposure shall be required from the Contractor and all Subcontractors performing such Work.

- b. If the Work involves transporting regulated materials or substances or waste, a separate policy or endorsement to the CPL policy specifically providing coverage for liability and cleanup arising from an upset or collision during transportation of hazardous materials or substances shall be required from the Contractor and all Subcontractors performing such Work.
  - c. It is preferred that CPL insurance shall be on a true occurrence form without a sunset clause. However, if CPL insurance is provided on a Claims Made basis, the policy shall have a retroactive date prior to the start of this project, and this insurance shall be kept in force for at least three years after the final completion of this project. Alternatively, the contractor, at its option, may provide evidence of extended reporting period of not less than three (3) years in its place. The Contractor shall be responsible for providing the Port with certificates of insurance each year evidencing this coverage.
  - d. The Port shall be named as an additional insured(s) on the CPL policy.
6. Technology Professional Liability Errors and Omissions Insurance appropriate to the Consultant's profession and work hereunder, with limits not less than \$2,000,000 per occurrence. Coverage shall be sufficiently broad to respond to the duties and obligations as is undertaken by the Vendor in this agreement and shall include, but not be limited to, claims involving infringement of intellectual property, copyright, trademark, invasion of privacy violations, information theft, release of private information, extortion and network security. The policy shall provide coverage for breach response costs as well as regulatory fines and penalties as well as credit monitoring expenses with limits sufficient to respond to these obligations.

The policy shall include, or be endorsed to include, **property damage liability coverage** for damage to, alteration of, loss of, or destruction of electronic data and/or information "property" of the Agency in the care, custody, or control of the Vendor.

- E. Except where indicated above, the limits of all insurance required to be provided by the Contractor shall be not less than \$2,000,000 for each occurrence. If the coverage is aggregated, the coverage shall be no less than two times the per occurrence or per claim limit. However, coverage in the amounts of these minimum limits shall not be construed as to relieve the Contractor from liability in excess of such limits. Any additional insured endorsement shall NOT be limited to the amounts specified by this Contract, unless expressly waived in writing by the Port.
- F. Contractor shall certify that its operations are covered by the Washington State Worker's Compensation Fund. The Contractor shall provide its Account Number or, if self-insured, its Certificate of Qualification Number. The Contractor shall also provide evidence of Stop-Gap Employers' Liability Insurance.

United States Longshoremen's and Harbor Worker's Act (USL&H) and Jones Act may be required for this project. The Contractor shall be solely responsible for determining the applicability of USL&H and Jones Act coverage. The failure of the Contractor to procure either USL&H or Jones Act coverage shall at no time create liability on the part of the Port. The Contractor shall bear all responsibility and shall indemnify and hold harmless the Port for any and all liability, cost, and/or damages.

- G. The Contractor shall furnish, within ten (10) days following issuance of the Notice of Award, a certificate of insurance satisfactory to the Port evidencing that insurance in the types and minimum amounts required by the Contract Documents has been secured. The Certificate of Insurance shall be signed by an authorized representative of the insurer together with a copy of the endorsement, which shows that the Port are named as additional insured(s).
- H. Contractor shall provide at least forty-five (45) days prior written notice to the Port of any termination or material change, or ten (10) day's-notice in the case of non-payment of premium(s).
- I. If the Contractor is required to make corrections to the Work after Final Completion, the Contractor shall obtain at its own expense, prior to the commencement of any corrective work, insurance coverage as required by the Contract Documents, which coverage shall be maintained until the corrections to the Work have been completed and accepted by the Port.

#### 1.04 BUILDER'S RISK INSURANCE

- A. Until Final Completion of the Work, the construction Work is at the risk of the Contractor and no partial payment shall constitute acceptance of the Work or relieve the Contractor of responsibility of completing the Work under the Contract.
- B. To the extent the Work provided under this Contract does not include the construction, rehabilitation or repair of any dam, road or bridge, and whenever the estimated cost of the Work is less than \$5,000,000, the Port and Contractor acknowledge that the Port will purchase, or has purchased, from a company or companies lawfully authorized and admitted to do business in Washington, property insurance written on a Builder's Risk "all-risk" (including Earthquake and Flood with applicable sub-limits) or equivalent policy form to cover the course of construction in the amount of the full insurable value thereof. This property insurance shall be maintained, unless otherwise provided in the Contract Documents or otherwise agreed in writing by all persons and entities who are beneficiaries of such insurance, until final payment has been made or until no person or entity other than the Port has an insurable interest in the property, whichever is later. Without further endorsement, the coverage afforded by this insurance includes the interests of the Port, the Contractor, and Subcontractors of any tier on the Project. Coverage for materials intended to be installed in the facility will be covered by the Builder's Risk policy. Losses up to the deductible amount, and payment of any deductible amount, shall be the responsibility of the Contractor. All tools and equipment not intended as part of the construction or installation (including but not limited to Contractor's equipment and tools) will NOT be covered by the policy.

- C. To the extent the Work provided under this Contract involves any dam, roadway or bridge, the value of which exceeds \$250,000, or whenever the estimated cost of the Work is equal to or greater than \$5,000,000, Contractor will purchase from a company or companies lawfully authorized and admitted to do business in Washington, property insurance written on a Builder's Risk "all-risk" (excluding Earthquake and Flood with applicable sub-limits) or equivalent policy form to cover the course of construction in the amount of the full insurable value thereof. This Builder's Risk insurance shall be maintained, unless otherwise provided in the Contract Documents or otherwise agreed in writing by all persons and entities who are beneficiaries of such insurance, until final payment has been made or until no person or entity other than the Port has an insurable interest in the property, whichever is later. Contractor shall provide evidence satisfactory to the Port confirming the coverage afforded by this insurance shall include the interests of the Port, the Contractor, and Subcontractors of any tier on the Project. Coverage for materials intended to be installed in the facility will be covered by the Builder's Risk policy purchased by the Contractor. Losses up to the deductible amount, and payment of any deductible amount, shall be the responsibility of the Contractor.
- D. In all instances, the Contractor shall obtain property insurance for all Contractor-owned equipment and tools and, in the event of loss, payment of any deductible amount shall be the responsibility of the Contractor.

**PART 2 - PRODUCTS - NOT USED**

**PART 3 - PRODUCTS - NOT USED**

**END OF SECTION**

This page intentionally left blank

## **PART 1 - GENERAL**

### **1.01 PREVAILING AND OTHER REQUIRED WAGES**

- A. The Contractor shall pay (and shall ensure that all Subcontractors of any tier pay) all prevailing wages and other wages (such as Davis-Bacon Act wages) applicable to the Project.
- B. Pursuant to RCW 39.12, "Prevailing Wages on Public Works," no worker, laborer, or mechanic employed in the performance of any part of the Work shall be paid less than the "prevailing rate of wage" in effect as of the date that bids are due.
  - 1. Based on the Bid Date, the applicable effective date for prevailing wages for this Contract is 05/26/2026.
- C. The State of Washington prevailing wage rates applicable for this public works Project, which is located in Pierce County, may be found at the following website address of the Department of Labor and Industries:  
  
<https://www.lni.wa.gov/licensing-permits/public-works-projects/prevailing-wage-rates/>
- D. The schedule of the prevailing wage rates is made a part of the Contract Documents by reference as though fully set forth herein, and a printed copy of the applicable prevailing wage rates are also available for viewing at the Port Administration Building, located at 1 Sitcum Plaza, Tacoma, WA 98421 (253-383-5841). Upon request to the Procurement Department at [procurement@portoftacoma.com](mailto:procurement@portoftacoma.com), the Port will email or mail a hard copy of the applicable Journey Level prevailing wages for this Project.
- E. Questions relating to prevailing wage data should be addressed to the Industrial Statistician.
  - Mailing Address: Washington State Department of Labor and Industries  
Prevailing Wage Office  
P.O. Box 44540  
Olympia, WA 98504
  - Telephone: (360) 902-5335
  - Facsimile: (360) 902-5300
  - 1. If there is any discrepancy between the provided schedule of prevailing wage rates and the published rates applicable under WAC 296-127-011, the applicable published rates shall apply with no increase in the Contract Sum. It is the Contractor's responsibility to ensure that the correct prevailing wage rates are paid.
- F. Statement to Pay Prevailing Wages
  - 1. Prior to any payment being made by the Port under this Contract, the Contractor, and each Subcontractor of any tier, shall file a Statement of Intent to Pay Prevailing Wages with the Department of Labor and Industries for approval.
  - 2. The statement shall include the hourly wage rate to be paid to each classification of workers entitled to prevailing wages, which shall not be less than the prevailing rate of wage, and the estimated number of workers in each classification employed on the Project by the Contractor or a Subcontractor of any tier, as well as the Contractor's contractor registration number and other information required by the Department of Labor and Industries.

3. The statement, and any supplemental statements, shall be filed in accordance with the requirements of the Department of Labor and Industries. No progress payment shall be made until the Port receives such certified statement.
- G. The Contractor shall post, in a location readily visible to workers, at the Project site: (i) a copy of the Statement of Intent to Pay Prevailing Wages approved by the Industrial Statistician of the Department of Labor and Industries and (ii) the address and telephone number of the Industrial Statistician of the Department of Labor and Industries to whom a complaint or inquiry concerning prevailing wages may be directed.
- H. If a State of Washington prevailing wage rate conflicts with another applicable wage rate (such as Davis-Bacon Act wage rate) for the same labor classification, the higher of the two shall govern.
- I. Pursuant to RCW 39.12.060, if any dispute arises concerning the appropriate prevailing wage rate for work of a similar nature, and the dispute cannot be adjusted by the parties in interest, including labor and management representatives, the matter shall be referred for arbitration to the Director of the Department of Labor and Industries, and his or her decision shall be final and conclusive and binding on all parties involved in the dispute.
- J. Immediately following the end of all Work completed under this Contract, the Contractor and each Subcontractor of any tier, shall file an approved Affidavit of Wages Paid with the Department of Labor and Industries.
- K. The Contractor shall defend (at the Contractor's sole cost, with legal counsel approved by Port), indemnify, and hold the Port harmless from all liabilities, obligations, claims, demands, damages, disbursements, lawsuits, losses, fines, penalties, costs, and expenses, whether direct, indirect, including, but not limited to, attorneys' fees and consultants' fees and other costs and expenses, from any violation or alleged violation by the Contractor or any Subcontractor of any tier of RCW 39.12 ("Prevailing Wages on Public Works") or RCW Title 51 ("Industrial Insurance"), including, but not limited to, RCW 51.12.050.

**PART 2 - PRODUCTS - NOT USED**

**PART 3 - EXECUTION - NOT USED**

**END OF SECTION**

## **PART 1 - GENERAL**

### **1.01 REQUIREMENTS APPLICABLE PORT-WIDE**

- A. The Contractor shall submit, prior to the start of Work, a list of emergency contact numbers for itself and its Subcontractors, Suppliers, and manufacturer representatives. Each person on the Project site shall have a valid identification card that is tamper proof with laminated photo identification, such as one (1) of the following:
  - 1. State-issued Driver's license (also required if driving a vehicle)
  - 2. Card issued by a governmental agency
  - 3. Passport
  - 4. Pacific Maritime Association card
  - 5. Labor organization identification card
- B. Identification cards shall be visible while on the Project site or easily displayed when requested.

### **1.02 TRANSPORTATION WORKER IDENTIFICATION CARD (TWIC) SUMMARY**

- A. TWIC is required for all personnel needing unescorted access to secure and restricted areas of Port facilities subject to 33 CFR 105, including truckers, surveyors, construction personnel, and delivery personnel. Secure areas are those areas with security measures for access control in accordance with a Coast Guard approved security plan. Restricted areas are those areas within a secure area that require increased limited access and a higher degree of security protection. New terminals under construction prior to terminal operations may not be designated secure areas. Construction on existing maritime transportation facilities and punchlist or other type of work requirements on facilities that have been certified under 33 CFR will require a TWIC.
- B. Contractors should allow for application and enrollment for the security threat assessment and issuance of TWIC when submitting a bid.

### **1.03 ESCORTING**

- A. To access restricted Port facilities, all un-credentialed individuals must be accompanied by a person who has been issued a TWIC and trained as an escort at that specific facility.
- B. Each restricted facility has their own guidelines for escorting. Having escort training at one facility does not qualify you to escort at other facilities. Prior to conducting escort services for non-TWIC personnel, the escorts are required to contact the Facility Security Officer at the gate for verification they are on the escort list and to document who is being escorted.
- C. For required documentation, upon completion of escorting, the escort is to inform the Security officer that the escort is complete. It is the Contractor's responsibility to schedule escort training with the Facility Security Officer.
- D. For more information, refer to the Port Security website at:  
<http://www.portoftacoma.com/shipping/security>

### **1.04 ELIGIBILITY FOR TWIC**

- A. Refer to the Transportation Worker Identification Credential website at: <https://www.tsa.gov/for-industry/twic> for information on eligibility and applying for TWIC.

1.05 TWIC USE AND DISPLAY

- A. Each worker granted unescorted access to secure areas of a facility or vessel must present their cards to authorized personnel, who will compare the holder to his or her photo, inspect security features on the TWIC, and evaluate the card for signs of tampering. The Coast Guard will verify TWIC's when conducting vessel and facility inspections and during spot checks using hand-held scanners, ensuring credentials are valid.

**PART 2 - PRODUCTS - NOT USED**

**PART 3 - EXECUTION - NOT USED**

**END OF SECTION**

**PART 1 - GENERAL**

1.01 SCOPE

- A. The Port desires to have available, competitively bid labor, equipment and materials for small asphalt paving projects, on reasonably short notice.
- B. The Work under this contract is to provide, furnish and install all labor, materials and equipment required to complete the work, installed, tested, and ready for use, and as described in these documents.
- C. Due to operational constraints, tenant activities, and vessel schedules, paving work is frequently required to occur during non-standard hours, including Nights and Weekends.

1.02 LOCATION

- A. The work is located Port-wide in the Tacoma Tideflats

1.03 WORK PERFORMED UNDER SEPARATE CONTRACTS

- A. Before work begins and by way of the Engineer, Contractor shall be informed of other contracts which may be in progress in the same or immediate area. The Contractor shall coordinate the progress of its work with the established schedules for completion and phasing.
- B. All present schedules are subject to change due to weather, equipment failure, Port operations, vessel schedules, etc.

1.04 WORK BY OTHERS ON THIS PROJECT

- A. Work by others will be determined at the time of developing the proposal for each Task order.

1.05 PRE-ORDERED MATERIALS

- A. Port of Tacoma procured items will be determined at the time of the proposal for each Task Order.

1.06 EXISTING MATERIALS

- A. Existing Materials to be furnished to the contractor by Port of Tacoma will be determined at the time of the proposal for the task order.

1.07 ENGINEERING AND INSPECTION

- A. The Engineer will perform the necessary inspection work except as otherwise specified in the Contract Documents. Refer to Section 01 45 00, Quality Control, for general requirements.

1.08 COORDINATION

- A. Port Activities: The Contractor shall coordinate its activity with the Project Manager or Port Inspector, so interference with Port activities and vessel operations will be minimized. In addition, the Contractor shall carry out work in a manner that minimizes interference and does not delay Port operations.
- B. Specific task order work may include additional work constraints which will be identified by the Engineer at the time of the Task Order proposal and execution.

**PART 2 - PRODUCTS - NOT USED**

**PART 3 - EXECUTION - NOT USED**

**END OF SECTION**

---

This page intentionally left blank

## **PART 1 - GENERAL**

### **1.01 SUMMARY**

- A. This Section specifies work sequence and constraints.
- B. The purpose of the milestones, sequence and limitations of construction are to ensure that the Contractor understands the requirements and limitations on its work by the specific characteristics of the Contract, schedules and conducts work in a manner consistent with achieving these purposes, and complies with the construction schedule, the specific sequence, constraints, milestones and limitations of work specified.
- C. Sequence of construction. Plan the sequence of construction to accommodate all the requirements of the specifications. The Contract Price shall include all specified requirements as described in this Section.

### **1.02 CONTRACTOR ACCESS AND USE OF PREMISES**

- A. Activity Regulations
  - 1. Ensure Contractor personnel deployed to the project become familiar with and follow all regulations or restrictions established by the Engineer.
- B. Working Facility
  - 1. The Facility will remain in operation for the duration of construction. The Contractor shall conduct all items of the Work in such a manner as to prevent interference with the normal operations of the Facility.
  - 2. TWIC Requirements:
    - a. TWIC is required for all personnel needing unescorted access to secure and restricted areas of Port facilities subject to 33 CFR 105, including truckers, surveyors, construction personnel, and delivery personnel.
    - b. To access restricted Port facilities, all un-credentialed individuals must be accompanied by a person who has been issued a TWIC and trained as an escort at that specific facility. Each restricted facility has their own guidelines for escorting. Having escort training at one facility does not qualify you to escort at other facilities.
    - c. For more information, refer to Section 00 73 63 - Security Requirements
- C. Work Site Regulations
  - 1. Keep within the limits of work and assigned avenues of ingress and egress. Do not enter any areas outside the designated work location unless previously approved by the Engineer. The Contractor must comply with the following conditions:
    - a. Restore all common areas to a clean and useable condition that permits the resumption of Tenant operations after the Contractor ceases daily work.
    - b. Be responsible for control and security of Contractor-owned equipment and materials at the work site. Report to Port Security (phone (253) 383-9472) any missing/lost/stolen property.
    - c. Ensure all materials, tools and equipment will be removed from the site or secured within the designated laydown area at the end of each shift.

**PART 2 - PRODUCTS**  
**PART 3 - EXECUTION**

**END OF SECTION**

## **PART 1 - GENERAL**

### **1.01 PAYMENT PROCEDURES**

- A. The Contractor shall bill the Port for each individual project, correlating to the individual Task Order requests as completed, to provide the Port with sufficient information to properly distribute the charges.
- B. Prior to submitting pay estimates to the Port, the Contractor and the Engineer shall review the work accomplished to determine the actual quantities including labor, materials and equipment charges to be billed. All quantity backup documentation shall be submitted to the Engineer listed on the approved task order with the draft pay estimate. Following the Engineer's review, the Contractor shall prepare an original pay estimate with all required documentation attached and submit electronically using Adobe PDF file format to [cpinvoices@portoftacoma.com](mailto:cpinvoices@portoftacoma.com).

### **1.02 TASK ORDER PRICING**

- A. The rate includes required certifications, insurance, benefits and other labor costs not covered by the prevailing wage rate, performance and payment bond, insurance required by the General Conditions, estimating, supervision, overhead and profit, taxes (except that Washington State Sales Tax will be added to each Task Order) and all other costs of supplying labor, equipment and materials and performing the Work.
- B. The Engineer shall require an estimate of the Work, which shall be the total compensation to be paid for that Task Order. The Contractor shall provide to the Engineer a detailed cost estimate supporting the submitted proposal. The estimate shall adhere to the provisions of this section. Whenever it appears that the cost to complete the Task Order may exceed the estimate, the Contractor shall promptly notify the Engineer before proceeding with the Work.
- C. Some of the bid items descriptions are identical but have differing quantities. For each Task Order the Contractor shall estimate the total quantity for each item of work and provide the task order estimate based on the estimated total quantity. Final task order quantities will be determined based on actual quantities, measured as described in each bid item below, and shall be billed utilizing the final unit price quantity.

### **1.03 PAYMENT PRICING**

- A. Pricing for the various lump sum or unit prices in the Bid Form, as further specified herein, shall include all compensation to be received by the Contractor for furnishing all tools, equipment, supplies, and manufactured articles, and for all labor, operations, and incidentals appurtenant to the items of work being described, as necessary to complete the various items of the work in accordance with the requirements of the Contract Documents and issued Task Order.
- B. Pricing also includes all costs of compliance with the regulations of public agencies having jurisdiction, including safety and health requirements of the Occupational Safety and Health Administration of the U.S. Department of Labor (OSHA).
- C. All incidental work, including work not specifically identified in the measurement and payment sections identified below, but necessary to complete each line item listed below, shall be included in the bid item prices. Temporary Facilities and Controls, Temporary Erosion and Sediment Control and Construction Pollution Prevention, and traffic control are incidental to the work and shall be included in the bid item prices as appropriate.

- D. For tasks that are necessary for the completion of the Task Order but fall outside the scope of services included as a bid item, the additional work will be paid preferably as negotiated unit price(s) or lump sum(s) or on a time and material basis if unit pricing or lump sums cannot be negotiated at the time of Task Order negotiation.

#### 1.04 MEASUREMENT PROCEDURES

- A. Measurement will be made in whole units for all types of material, labor, and equipment utilized.
- B. Measurement by weight shall be with State of Washington certified accurate scales at a location or locations approved by the Engineer.
- C. The tonnage claimed by the Contractor for all such bid items shall be verified with weigh tickets from the material supplier. One (1) copy of each load ticket shall be attached to the daily report for the day of delivery and shall not be valid for payment unless each daily and ticket(s) have been reviewed and approved by the Engineer.
- D. The Engineer reserves the right to reduce the stated tonnage for material which, in the Engineer's opinion, has more than the moisture content required for good compaction.
- E. Material received at the job site but not satisfactory to the Engineer shall be rejected. All costs associated with the unsuitable material, including the expense of disposal in waste areas, shall be borne solely by the Contractor.
- F. Weighing will be considered incidental to construction and all costs thereof shall be included by the Contractor in the appropriate bid prices for the material being weighed.
- G. All equipment, materials, and labor used shall be entered on Daily Report Forms and submitted to the Engineer for Verification against Contractor's application for payment. Submit all daily reports to the Engineer for work performed the previous week no later than the following Monday for concurrence and approval.
- H. The unit price paid per ton for these items and the quantities listed in the Schedule of Unit Prices shall include all labor and equipment associated with the furnishing and loading of these materials into truck or trucks and placement as designated in the individual Task Orders.

#### 1.05 MEASUREMENT FOR PAYMENT

- A. Measurement for payment will be at the Lump sum or Unit Price as stipulated in the Bid Form for the items listed below. Payment shall be considered full compensation for furnishing all labor, materials and equipment to complete the Work specified.

Payment for equipment will not start until the equipment is on-site, ready to operate. No payment will be made for equipment that will not function properly, requiring or being repaired or for lack of the proper personnel to operate it. Equipment is furnished complete with operator or driver and other required service personnel, ready to work, etc.

The Port will pay the proposed rate for the required equipment only as long as the operator is required. The Port will not pay for standby or non-operating time for equipment. The Contractor's general superintendent further agrees to inform the Port Project Manager when the task order is complete prior to release of equipment and operator.

The following sets forth a general description of the work covered in each bid item and may not be all inclusive. All work specifically indicated to be within these Specifications shall be performed whether or not specifically listed under an item description.

##### 1. BID ITEM NO. 1 - MOBILIZATION AND DEMOBILIZATION

- a. Payment for MOBILIZATION AND DEMOBILIZATION shall be for preparatory and cleanup work and operations performed by the Contractor including, but not limited to, those necessary for the movement of its personnel, equipment, supplies and incidentals to and from the Project Site; for premiums on bonds and insurance for the Project, L&I Intents and Affidavits, and for other work and operations which must be performed, or costs incurred before beginning work on the various items on the Project Site.  

Individual Task Orders will have a single mobilization / demobilization cost to the site from the Contractor's facility unless approved by the Engineer in the original estimate.
- b. Mobilization and Demobilization shall be paid at the per each unit price listed in the bid form for each Task Order.
2. BID ITEM NO. 2 - MOBILIZATION AND DEMOBILIZATION (NIGHTS & WEEKENDS)
  - a. Payment for MOBILIZATION AND DEMOBILIZATION (NIGHTS & WEEKENDS) shall be for preparatory and cleanup work and operations performed by the Contractor during night and weekend hours including, but not limited to, those necessary for the movement of its personnel, equipment, supplies and incidentals to and from the Project Site; for premiums on bonds and insurance for the Project, L&I Intents and Affidavits, and for other work and operations which must be performed, or costs incurred before beginning work on the various items on the Project Site.
  - b. Mobilization and Demobilization for nights and weekends shall be paid at the per each unit price listed in the bid form for each Task Order.
3. BID ITEMS NO. 3 THROUGH 6 - ASPHALT PAVING
  - a. The unit price paid per ton for these items and the quantities listed in the Schedule of Unit Prices shall include all labor, material, and equipment associated with the preparation of grade, and the preparing, furnishing, hauling, placing, spreading, and compacting of the material. Truck weigh tickets shall be used to determine measurement for payment quantities.
4. BID ITEMS NO. 7 THROUGH 10 - ASPHALT PAVING (NIGHTS & WEEKENDS)
  - a. The unit price paid per ton for these items and the quantities listed in the Schedule of Unit Prices shall include all labor, material, and equipment associated with the preparation of grade, and the preparing, furnishing, hauling, placing, spreading, and compacting of the material during night and weekend hours. Truck weigh tickets shall be used to determine measurement for payment quantities.
5. BID ITEMS NO. 11 THROUGH 12 - CONCRETE REPAIR
  - a. The unit price paid per cubic yard for these items and the quantities listed in the Schedule of Unit Prices shall include all labor, material, and equipment associated with the preparation of grade or surface, and the preparing, furnishing, hauling, placing, spreading, compacting, finishing, and curing of the material. Final Task Order quantities shall be used to determine measurement for payment quantities.
6. BID ITEMS NO. 13 - CRUSHED SURFACING BASE COURSE

- a. The unit price paid per ton for these items and the quantities listed in the Schedule of Unit Prices shall include all labor, material, and equipment associated with the preparation of grade, and the preparing, furnishing, hauling, placing, spreading, and compacting of the material. Truck weigh tickets shall be used to determine measurement for payment quantities.
7. BID ITEMS NO. 14 - CRUSHED SURFACING TOP COURSE
    - a. The unit price paid per ton for these items shall include all labor, material, and equipment associated with the preparation of grade, and the preparing, furnishing, hauling, placing, spreading, and compacting of the material. Truck weigh tickets shall be used to determine measurement for payment quantities.
  8. BID ITEM NO. 15 - GRAVEL BASE
    - a. The unit price paid per ton for this item shall include all labor, material, and equipment associated with the preparation of grade, and the preparing, furnishing, hauling, placing, spreading, and compacting of the material. Truck weigh tickets shall be used to determine measurement for payment quantities.
  9. BID ITEM NO. 16 - GRAVEL BORROW
    - a. The unit price paid per ton for this item shall include all labor, material, and equipment associated with the preparation of grade, and the preparing, furnishing, hauling, placing, spreading, and compacting of the material. Truck weigh tickets shall be used to determine measurement for payment quantities.
  10. BID ITEM NO. 17 - EXCAVATION
    - a. The unit price paid per cubic yard for this item shall include all labor and equipment associated with the preparation, removing, stockpiling for characterization, handling, hauling, and disposing of the material. Final Task Order quantities shall be determined based on approved daily reports submitted by the Contractor.
  11. BID ITEM NO. 18 - EXCAVATION (NIGHTS & WEEKENDS)
    - a. The unit price paid per cubic yard for this item shall include all labor and equipment associated with the preparation, removing, stockpiling for characterization, handling, hauling, and disposing of the material during night and weekend hours. Final Task Order quantities shall be determined based on approved daily reports submitted by the Contractor.
  12. BID ITEM NO. 19 - GEOTEXTILE
    - a. The unit price paid per square yard for this item shall include all labor, material, and equipment associated with the preparation of grade, and the preparing, furnishing, hauling, and placing of the material. Final Task Order quantities shall be determined based on approved daily reports submitted by the Contractor.
  13. BID ITEM NO. 20 - MANAGEMENT OF REGULATED MATERIALS (Subtitle D)
    - a. The unit price paid per cubic yard for this item shall include all labor, material, and equipment associated with the handling, loading, hauling, and disposal of the material. Disposal tickets shall be used to determine measurement for payment quantities and shall be submitted to the Engineer with the Daily Report.
  14. BID ITEM NO. 21 - CRACK SEALANT
-

- a. The unit price paid per linear foot for this item shall include all material, labor, and equipment associated with furnishing and placing crack sealant. Final Task Order quantities shall be determined based on approved daily reports submitted by the Contractor.
15. BID ITEM NO. 22 THROUGH 23 - CONCRETE SAW CUTTING
- a. The unit price paid per linear foot for this item shall include all labor and equipment associated with the cutting of existing concrete. The maximum depth of the concrete per area shall be used to determine which CONCRETE SAW CUTTING bid item will be used for payment. Final Task Order quantities shall be determined based on approved daily reports submitted by the Contractor.
16. BID ITEMS NO. 24 - CONCRETE REMOVAL
- a. The unit price paid per cubic yard for these items shall include all labor and equipment associated with the removal of the existing concrete, and the hauling and dumping of the waste material. The maximum depth of the concrete per area shall be used to determine which CONCRETE REMOVAL bid item will be used for payment. Final Task Order quantities shall be determined based on approved daily reports submitted by the Contractor.
17. BID ITEM NO. 25 - ASPHALT SAW CUTTING
- a. The unit price paid per linear foot for this item shall include all labor and equipment associated with the cutting of existing asphalt. Final Task Order quantities shall be determined based on approved daily reports submitted by the Contractor.
18. BID ITEMS NO. 26 THROUGH 27 - ASPHALT REMOVAL
- a. The unit price paid per square yard for these items shall include all labor and equipment associated with removing, hauling, and dumping of the existing asphalt. The maximum depth of the asphalt per area shall be used to determine which ASPHALT REMOVAL bid item will be used for payment. Final Task Order quantities shall be determined based on approved daily reports submitted by the Contractor.
19. BID ITEMS NO. 28 THROUGH 29 - ASPHALT REMOVAL (NIGHTS AND WEEKENDS)
- a. The unit price paid per square yard for these items shall include all labor and equipment associated with removing, hauling, and dumping of the existing asphalt during night and weekend hours. The maximum depth of the asphalt per area shall be used to determine which ASPHALT REMOVAL bid item will be used for payment. Final Task Order quantities shall be determined based on approved daily reports submitted by the Contractor.
20. BID ITEMS NO. 30 THROUGH 31 - PROFILING/GRINDING ASPHALT
- a. The unit price paid per square yard for these items shall include all labor and equipment associated with the profiling, grinding, hauling, and dumping of the existing asphalt. The maximum depth of the profiling/grinding per area shall be used to determine which PROFILING/GRINDING ASPHALT bid item will be used for payment. Final Task Order quantities shall be determined based on approved daily reports submitted by the Contractor.
21. BID ITEMS NO. 32 THROUGH 33 - PROFILING/GRINDING ASPHALT (NIGHTS AND WEEKENDS)

- a. The unit price paid per square yard for these items shall include all labor and equipment associated with the profiling, grinding, hauling, and dumping of the existing asphalt during night and weekend hours. The maximum depth of the profiling/grinding per area shall be used to determine which PROFILING/GRINDING ASPHALT bid item will be used for payment. Final Task Order quantities shall be determined based on approved daily reports submitted by the Contractor.
22. BID ITEM NO. 34 - ASPHALT SEAL COAT
- a. The unit price paid per square yard for this item shall include all material, labor, and equipment associated with the preparation, furnishing, hauling, placing, and spreading of the material.
23. BID ITEM NO. 35 - STRIPING
- a. The unit price paid per linear foot for this item shall include all labor, material, and equipment associated with the preparation of the surface, and furnishing and placing of the material. Final Task Order quantities shall be determined based on approved daily reports submitted by the Contractor.
24. BID ITEM NO. 36 - STRIPING (NIGHTS AND WEEKENDS)
- a. The unit price paid per linear foot for this item shall include all labor, material, and equipment associated with the preparation of the surface, and furnishing and placing of the material during night and weekend hours. Final Task Order quantities shall be determined based on approved daily reports submitted by the Contractor.
25. BID ITEM NO. 37 - OTHER STRIPING & PAINTING
- a. The unit price paid per square foot for this item shall include all labor, material, and equipment associated with the preparation of the surface, and furnishing and placing of the material. Final Task Order quantities shall be determined based on approved daily reports submitted by the Contractor.
26. BID ITEM NO. 38 - SKID-STEER LOADER with ATTACHMENT AND OPERATOR
- a. Use of SKID-STEER LOADER with ATTACHMENT AND OPERATOR shall be measured and paid per hour based on the rate set on the bid form.
27. BID ITEM NO. 39 - STREET SWEEPER WITH DRIVER
- a. Use of STREET SWEEPER WITH DRIVER shall be measured and paid per hour based on the rate set on the bid form.
28. BID ITEM NO. 40 - WATER TRUCK WITH DRIVER
- a. Use of WATER TRUCK WITH DRIVER shall be measured and paid per hour based on the rate set on the bid form. The hourly rate shall include all labor, materials and equipment associated with the work.
  - b. The Contractor shall make arrangements with the City of Tacoma or other sources to supply and is responsible for the cost of construction water for the duration of this Contract.
29. BID ITEM NO. 41 - WATER TRUCK WITH DRIVER (NIGHTS AND WEEKENDS)
- a. Use of WATER TRUCK WITH DRIVER shall be measured and paid per hour based on the rate set on the bid form. The hourly rate shall include all labor, materials and equipment associated with the work during night and weekend hours.

- b. The Contractor shall make arrangements with the City of Tacoma or other sources to supply and is responsible for the cost of construction water for the duration of this Contract.
30. BID ITEM NO. 42 - DUMP TRUCK WITH DRIVER
- a. Use of DUMP TRUCK WITH DRIVER shall be measured and paid per hour based on the rate set on the bid form. The hourly rate shall include all labor, materials and equipment associated with the work.
31. BID ITEM NO. 43 - DUMP TRUCK WITH DRIVER (NIGHTS AND WEEKENDS)
- a. Use of DUMP TRUCK WITH DRIVER shall be measured and paid per hour based on the rate set on the bid form. The hourly rate shall include all labor, materials and equipment associated with the work during night and weekend hours.
32. BID ITEMS NO. 44 THROUGH 46 - EMBEDDED STRUCTURES
- a. The unit price paid per each for these items shall include all labor, material, and equipment associated with the removal of the castings and leveling blocks, the adjustment rings necessary in raising or lowering these items, providing and placing of a steel plate cover over the structure as required, the re-installation of these items to grade, and all concrete, asphalt, crack sealant and tack coat material needed. Final Task Order quantities shall be determined based on approved daily reports submitted by the Contractor.
33. BID ITEM NO. 47 - PLANT OPENING FEES
- a. The unit price for PLANT OPENING FEES shall include all costs associated with opening an asphalt or concrete plant outside of its normal operating hours, at the request of the Port. This may include, but is not limited to, labor, equipment startup, utility usage, and administrative overhead required to produce and supply materials during nights, weekends, or holidays.
  - b. Payment shall be made on a per occurrence basis, as listed on the Bid Form, and shall only apply with the Port specifically requests material production on off-hours. No separate payment will be made for plant opening fees if the plant is already operating for other work or if the Contractor elects to work during off-hours for their own convenience.

**PART 2 - PRODUCTS - NOT USED**

**PART 3 - EXECUTION - NOT USED**

**END OF SECTION**

This page intentionally left blank

## **PART 1 - GENERAL**

### **1.01 SUMMARY**

- A. Section includes administrative and procedural requirements for handling and processing Contract modifications.

### **1.02 SUBMITTALS**

- A. The Contractor shall submit for approval the following documentation to the Port for force account change orders:
  - 1. List of Labor Rates
    - a. For the Contractor and each subcontractor, a list of labor rates for each trade applicable to the scope of work to be performed. These submitted rates shall be broken down to include the base wage, fringes, FICA, SUTA, FUTA, industrial insurance, and medical aid premiums as stated in the General Conditions. The rates shall not contain any travel time, safety, loss efficiency factors, overhead, or profit. Rates shall be submitted for straight time, overtime, and double time in a form acceptable to the Engineer. Contractor shall provide proof of all labor rate costs as required by the Engineer, including the submission of a copy of the most current Workers Compensation Rate Notice from Labor & Industries and a copy of the Unemployment Insurance Tax Rate notice from the Employment Security Department.
      - 1) If labor rates change during the course of the project or additional labor rates become required to complete the work, the Contractor shall submit new rates for approval.
  - 2. List of Equipment.
    - a. Submit for the Contractor and each subcontractor, a list of equipment and rates applicable to the scope of work to be performed. The equipment rates shall conform to the rates shown on Equipment Watch. A separate page from equipment watch detailing the hourly rate shall be submitted as backup documentation for each piece of equipment.
      - 1) If the list of equipment and/or equipment rates changes during the course of the project or additional equipment becomes required to complete the work, the Contractor shall submit a new list and rates for approval.

### **1.03 METHOD TO CALCULATE ADJUSTMENTS TO CONTRACT PRICE**

- A. One of the following methods shall be used:
  - 1. Unit Price Method;
  - 2. Firm Fixed Price Method (Lump Sum); or,
  - 3. Time and Materials Method (Force Account).
- B. The Port preferred methods are firm fixed price or unit prices.

### **1.04 MINOR CHANGES IN THE WORK**

- A. Engineer will issue a written directive authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time.

### 1.05 PROPOSAL REQUESTS

- A. Port-Initiated Proposal Requests: The Engineer will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
1. Work Change Proposal Requests issued by Engineer are not instructions either to stop work in progress or to execute the proposed change.
  2. Contractor shall submit a written proposal within the time specified in the General Conditions. The proposal shall represent the Contractor's offer to perform the requested work, and the pricing set forth within the proposal shall represent full, complete, and final compensation for the proposed change and any impacts to any other Contract Work, including any adjustments in the Contract Time.
    - a. Include a breakdown of the changed work in sufficient detail that permits the Engineer to substantiate the costs.
      - 1) Generally, the cost breakdown should be divided into the time and materials categories listed in the General Conditions under Article 8.02.B for either Lump Sum Proposals or Force Account Proposals.
      - 2) For Unit Price Proposals, include the quantity and description of all work involved in the unit pricing being proposed, along with a not to exceed total cost.
    - b. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
- B. Contractor-Initiated Proposals: If latent or differing site conditions require modifications to the Contract, the Contractor may initiate a claim by submitting a request for a change to the Engineer.
1. Notify the Engineer immediately upon finding differing conditions prior to disturbing the site.
  2. Provide follow-up written notification and differing site conditions proposal within the time frames set forth in the General Conditions.
  3. Provide the differing site condition change proposal in the same or similar manner as described above under 1.05.A.
  4. Comply with requirements in Section 00 26 00 Substitution Procedures if the proposed change requires substitution of one product or system for product or system specified.
  5. Proposal Request Form: Use form acceptable to Engineer.

### 1.06 PROCEEDING WITH CHANGED WORK

- A. The Engineer may issue a directive instructing the Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order per the General Conditions, Article 8.01.E.
1. The directive will contain a description of change in the Work and a not-to-exceed amount. It will designate the method to be followed to determine the change in the Contract Sum or the Contract Time.

### 1.07 CHANGE ORDER PROCEDURES

- A. Issuance of Change Order

1. On approval of the Contractor's proposal, and following successful negotiations, the Engineer will issue a Change Order for signature by the Contractor and execution by the Engineer.
  - a. The Contractor shall sign and return the Change Order to the Engineer within **four (4) days** following receipt of the Change Order from the Engineer. If the Contractor fails to return the signed Change Order within the allotted time, the Engineer may issue a Unilateral Change Directive.

**PART 2 - PRODUCTS - NOT USED**

**PART 3 - EXECUTION - NOT USED**

**END OF SECTION**

This page intentionally left blank

## **PART 1 - GENERAL**

### 1.01 SUMMARY

- A. This section includes specifications for preparation, format, and submittal of Schedule of Values.
- B. The Schedule of Values will establish unit prices for individual items of work.
- C. The Schedule of Values will be the basis for payment of contract work.

### 1.02 PREPARATION

- A. To facilitate monthly pay requests, develop the Schedule of Values based on the Contractor's submitted Bid Items. The Schedule of Values shall be used to provide an allocation of the Work for measurement and payment to a level of detail to ensure accurate payment for the Work accomplished. The Schedule of Values is based on unit priced bid items and a breakdown of each lump-sum bid item. The total dollars for the Schedule of Values shall total the bid amount.
- B. Obtain the agreement of the Contract Administrator and Engineer on the Schedule of Values. No payment will be made prior to an agreed upon Schedule of Values.
- C. Include an updated version of the Schedule of Values as changes occur. Update the Schedule of Values to include:
  - 1. Dollars earned and percent complete for the current progress payment period,
  - 2. Dollars earned and percent complete to-date, excluding the current progress payment period,
  - 3. Total dollars earned and percent complete to-date,
  - 4. Total dollars remaining, and
  - 5. Changes resulting from Change Orders.
- D. The total value of the line items in the Schedule of Values plus any approved Change Orders shall be equal to the current approved contract price.
- E. The value of stored material shall be identified in the Schedule of Values with both a material-purchase activity and a separate corresponding installation activity in the Construction Schedule(s).

### 1.03 SUBMITTAL

- A. Submit preliminary Schedule of Values within 10 days of the effective date of the Notice to Proceed.
- B. Submit corrected Schedule of Values within 10 days upon receipt of reviewed Schedule of Values.
- C. At the Contract administrator or Engineer's request, submit documentation substantiating the cost allocations for line items within the Schedule of Values.

## **PART 2 - PRODUCTS - NOT USED**

## **PART 3 - EXECUTION**

### 3.01 SCHEDULE OF VALUES

- A. Submit the Schedule of Values in a form acceptable to the Contract Administrator and Engineer.

- B. Provide updated Schedule of Values as required by the Contract Administrator or Engineer, and as indicated in the Contract Documents.

**END OF SECTION**

## **PART 1 - GENERAL**

### **1.01 SCOPE**

- A. The purpose of this section is to provide the framework for communication between the Port and the Contractor by defining the types and timing of administrative tasks, including meetings and other items related to communications.

### **1.02 NOTICE TO PROCEED**

- A. Contract execution will be made per the requirements of the Contract Documents. Once the contract has been executed and all pre-work submittals have been received, the Engineer will issue a Notice to Proceed (NTP).
  - 1. In certain instances, the Engineer may issue to the Contractor a Limited NTP for specified elements of the work described in these Contract Documents.
- B. The Contractor shall submit all pre-work submittals within DD days of contract execution.
  - 1. No contract time extension shall be granted for any delays in issuance of the NTP by the Engineer due to the Contractor's failure to provide acceptable submittals required by the Contract Documents.

### **1.03 COORDINATION**

- A. The Contractor shall coordinate all its activities through the Engineer.
- B. The Contractor shall coordinate construction operations as required to execute the Work efficiently, to obtain the best results where installation of one part of the Work depends on other portions.

### **1.04 PROJECT MEETINGS**

- A. Pre-Construction Meeting
  - 1. After execution of the contract, but prior to commencement of any work at the site, a mandatory one time meeting will be scheduled by the Engineer to discuss and develop a mutual understanding relative to the administration of the safety program, preparation of the Schedule of Values, change orders, RFI's, submittals, scheduling prosecution of the work. Major subcontractors who will engage in the work shall attend.
  - 2. Suggested Agenda: The agenda will include items of significance to the project.
  - 3. Pre-Construction Meeting will be held at the Port of Tacoma Administration Building, or virtually, as scheduled by the Engineer.
- B. Weekly Progress Meetings – Progress meetings include the Contractor, Engineer, consultants and others affected by decisions made.
  - 1. The Engineer will arrange meetings, prepare standard agenda with copies for participants, preside at meetings, record minutes and distribute copies within ten working days to the Contractor, meeting participants, and others affected by decisions made.
    - a. The Engineer will approve submitted meeting minutes in writing within 10 working days.
  - 2. Attendance is required for the Contractor's job superintendent, major subcontractors and suppliers, Engineer, and representatives of the Port as appropriate to the agenda topics for each meeting.

3. Standard Agenda

- a. Review minutes of previous meeting
- b. Review of work progress
- c. Field observations, problems, and decisions
- d. Identification of problems that impede planned progress
- e. Maintenance of Progress Schedule (3 weeks ahead; 1 week back)
- f. Corrective measures to regain projected schedules
- g. Planned progress during succeeding work period
- h. Coordination of projected progress
- i. Maintenance of quality and work standards
- j. Effect of proposed changes on progress schedule and coordination
- k. Demonstration that the project record drawings are up-to-date
- l. Other business relating to the work

C. Cost Meeting

- 1. A separate cost meeting may be set up by the Engineer to discuss RFI's (or any other issues) that may cause scope, schedule or monetary changes to the contracts in more detail than necessary at the progress meeting. The Engineer will arrange, host and provide an agenda for cost meetings. Attendees would include the Engineer, Contractor's job superintendent and others as invited.

**PART 2 - PRODUCTS - NOT USED**

**PART 3 - EXECUTION - NOT USED**

**END OF SECTION**

## **PART 1 - GENERAL**

### **1.01 SUMMARY**

- A. The Port and Contractor shall use the Port's provided Project Management applications for electronic information exchange throughout the duration of the Contract, as later described. The joint use of these systems is to facilitate and coordinate the electronic exchange of Requests for Information, Submittals, Change Order Proposals, and project specific correspondence.

### **1.02 USER ACCESS LIMITATIONS**

- A. Contractor's access to Port provided applications is granted and controlled by the Engineer.
  - 1. The users assigned by the Contractor shall be competent and experienced with the practices commonly employed in the industry for electronically submitting requests for information, submittals, product data, shop drawings and related items as required by the contract and the methods commonly used for project correspondence transmission and filing.
  - 2. Any users assigned by the Contractor whom the Engineer determines is incapable of performing the prescribed tasks in an accurate, competent and efficient manner will be removed upon request from the Engineer. The qualifications and identity of a replacement user shall be submitted within 24 hours for consideration by the Engineer. Once accepted by the Engineer, the user account will be modified accordingly.
  - 3. Each user must have their own account. Sharing accounts or login credentials is not allowed.

### **1.03 CONTRACTOR TECHNOLOGY REQUIREMENTS**

- A. The Contractor is responsible for providing and maintaining web enabled devices capable of operating the Trimble Unity Construct web based application and any additional project specific software required by the Engineer effectively.

### **1.04 CONTRACTOR SOFTWARE REQUIREMENTS**

- A. The Contractor is responsible for providing and maintaining the following:
  - 1. An office suite that is Microsoft Office 2013 compatible for generation and manipulation of correspondence.
  - 2. A program capable of editing, annotating and manipulating Adobe pdf files for inserting the Contractor's review stamp, clouding and adding notation to the files as necessary for review by the Engineer.

### **1.05 CONTRACTOR RESPONSIBILITY**

- A. Provide all the equipment, internet connections, software, personnel and expertise required to support the use of Trimble Unity Construct as described in the contract documents.
  - 1. User account creation. Submit the full name and email of each requested user to the Engineer, or their designee. Trimble User Accounts cannot be shared and require a unique email for each user.

### **1.06 PORT RESPONSIBILITY**

- A. Provide the Contractor with the following:

1. Two (2) User Accounts to access Trimble Unity Construct as described above. Additional user accounts may be assigned at the Engineer's discretion.
2. Information, basic user guides and requirements on methods for using Trimble Unity Construct.
3. Instruction for the Contractor's staff utilizing Trimble Unity Construct.

**PART 2 - PRODUCTS - NOT USED**

**PART 3 - EXECUTION**

**3.01 UTILIZATION OF TRIMBLE UNITY CONSTRUCT**

- A. The Contractor shall provide required information in a timely manner that also supports the project schedule and meets the requirements of the Contract.
- B. The Contractor shall provide and maintain competent and qualified personnel to perform the various tasks required to support the work within Trimble Unity Construct
- C. The Port will not be liable for any delays associated from the usage of Trimble Unity Construct including, but not limited to: slow response time, Port maintenance and off-line periods, connectivity problems or loss of information. Under no circumstances shall the usage of Trimble Unity Construct software be grounds for a time extension or cost adjustment to the contract.

**END OF SECTION**

## **PART 1 - GENERAL**

### 1.01 SUMMARY

- A. This section includes the requirements to provide a submittal log and project submittals.

### 1.02 SUBMITTAL LOG

- A. Contractor shall, within 14 days of contract execution prepare and submit for Engineer approval a detailed log of all the submittals required under this Contract, along with any other submittals identified by the Port or Contractor. The log shall include, but not be limited to, schedules, required construction Work plans, equipment and material cut sheets, shop drawings, project record documents, test results, survey records, record drawings, results of QC testing, and all other items for which a submittal is required. The submittal log shall be organized by CSI Specification Division, and Section number and include the following information:
  - 1. Item Description
  - 2. Category
  - 3. Specification Section information of the applicable section
  - 4. After the submittal log is reviewed and approved by the Engineer, it shall become the basis for the submittal of all items by Contractor.

### 1.03 COMPLIANCE

- A. Failure to comply with these requirements shall be deemed as the Contractor's agreement to furnish the exact materials specified or materials selected by the Engineer based on these specifications.

### 1.04 SHOP DRAWINGS AND MANUFACTURERS' LITERATURE

- A. The Port will not accept shop drawings that prohibit the Port from making copies for its own use.
- B. Shop drawings shall be prepared accurately and to a scale sufficiently large to indicate all pertinent features of the products and the method of fabrication, connection, erection, or assembly with respect to the Work.
- C. All drawings submitted to the Engineer for approval shall be drawn to scale as ANSI D.
- D. Required electronic formats for these drawings are as follows:
  - 1. AutoCad DWG
  - 2. PDF - Formatted to print to half-scale using 11x17 paper
- E. Catalog cuts or brochures shall show the type, size, ratings, style, color, manufacturer, and catalog number of each item and be complete enough to provide for positive and rapid identification in the field. General catalogs or partial lists will not be accepted. Manufacturers' original electronic files are required for submitting.

### 1.05 SUBMITTAL REVIEW

- A. After review of each of Contractor's submittals, the submittal will be returned to Contractor with a form indicating one or more of the following:

1. No Exceptions Taken - Means, accepted subject to its compatibility with future submittals and additional partial submittals for portions of the work not covered in this submittal. But it does not constitute approval or deletion of specified or required items not shown in the partial submittal.
  2. Make Corrections Noted - Same as Item 1, except that minor corrections as noted shall be made by Contractor.
  3. Reviewed - Submittal has been reviewed by the Port, does not constitute approval, and the Contractor is responsible for requirements in submittal.
  4. Review as Noted - Submittal has to be reviewed by the Port with comments as noted.
  5. Revise and Resubmit - Means, rejected because of major inconsistencies or errors. Resolve or correct before next submittal.
  6. Rejected - Means, submitted material does not conform to the Contract Documents in a major respect (e.g., wrong material, size, capacity, model, etc.).
- B. Submittals marked "No Exceptions Taken," "Make Corrections Noted," or "Reviewed as Noted" authorizes Contractor to proceed with construction covered by those data sheets or shop drawings with corrections, if any, incorporated.
- C. When submittals or prints of shop drawings have been marked "Revise and Resubmit" or "Rejected," Contractor shall make the necessary corrections and submit required copies. Every revision shall be shown by number, date, and subject in a revision block, and each revised shop drawing shall have its latest revision numbers and items clearly indicated by clouding around the revised areas on the shop drawing.
- D. Submittals authorized by the Engineer do not in any case supersede the Contract Documents. The approval by the Engineer shall not relieve the Contractor from responsibility to conform to the Drawings or Specifications, or correct details when in error, or ensure the proper fit of parts when installed. A favorable review by the Port of shop drawings, method of work, or information regarding material and equipment Contractor proposes to furnish shall not relieve Contractor of its responsibility for errors therein and shall not be regarded as assumption of risk or liability by the Port or its officers, employees, or representatives. Contractor shall have no claim under the Contract on account of failure or partial failure, or inefficiency or insufficiency of any plan or method of work, or material and equipment so accepted. Favorable review means that the Port has no objection to Contractor using, upon its own full responsibility, the plan or method of work proposed, or furnishing the material and equipment proposed.
- E. It is considered reasonable that the Contractor's submittals shall be complete and acceptable by at least the second submission of each submittal. The Port reserves the right to deduct monies from payments due Contractor to cover additional costs for review beyond the second submission.

## **PART 2 - PRODUCTS - NOT USED**

## **PART 3 - EXECUTION**

### **3.01 PREPARATION OF SUBMITTALS**

- A. The Contractor shall submit all shop drawings, catalog cuts, brochures and physical samples using Trimble Unity Construct (a web based construction management software). All post-document-generated notations such as notes, arrows, stamps, clouding, or other items, are required to be shown directly on the submittal document. **Each submittal shall be accompanied by a transmittal developed within the Trimble Unity Construct software.**

- B. A separate submittal shall be prepared for each product or procedure and shall be further identified by referencing the Specification Section and paragraph number and each submittal shall be numbered consecutively.
- C. Product submittals that cannot be accomplished electronically shall be submitted electronically without attachments, marked as being hand delivered, and accompanied by a printed version of a transmittal.
- D. Shop and detail drawings shall be submitted in related packages. All equipment or material details which are interdependent, or are related in any way, must be submitted indicating the complete installation. Submittals shall not be altered once marked "No Exceptions Taken" Revisions shall be clearly marked and dated. Major revisions must be submitted for approval.
- E. The Contractor shall thoroughly review all shop and detail drawings, prior to submittal, to assure coordination with other parts of the work.
- F. Components or materials which require shop drawings and which arrive at the job site prior to approval of shop drawings shall be considered as not being made for this project and shall be subject to rejection and removal from the premises.
- G. All submittal packages including, but not limited to, product data sheets, mix designs, shop drawings and other required information for submittal must be submitted, reviewed and approved before the relevant scheduled task may commence. It is the responsibility of the Contractor to provide the submittal information which may drive a task on the construction schedule to submit items well enough in advance as to provide adequate time for review and comment from the Engineer without adversely impacting the construction schedule.
- H. When completing the Trimble Unity Construct submittal form, a Date Due field is required to be completed. This field is intended to inform the Port of the urgency of the submittal. Failure of the Port to return the submittal by the date provided by the Contractor will not be considered grounds for a contract time extension.

### 3.02 PRE-WORK SUBMITTALS

- A. Prior to issuance of Notice to Proceed, the following submittals must be submitted and returned to the Contractor as No Exceptions Taken, Make Corrections Noted, Reviewed, or Reviewed as Noted.
  - 1. Per 00 72 00 and 01 32 16, Baseline Project Schedule
  - 2. Per 00 73 63, Emergency Contact Numbers
  - 3. Per 01 35 29, Health and Safety Plan (HASP)
  - 4. Per 01 35 29, Spill Prevention and Countermeasures Plan (SPCC)
  - 5. Per 01 35 47, List of equipment and written certification

### 3.03 MAINTENANCE OF SUBMITTAL LOG

- A. Prepare and submit for Port review a detailed submittal log conforming to the requirements of paragraph 1.02 of this section. When approved by the Engineer, use the submittal log to track the transmittal of submittals to the Engineer, the receipt of submittal comments from the Engineer, and all subsequent action with respect to each submittal. Provide an updated copy of the submittal log to the Engineer during each weekly progress meeting, unless otherwise approved by the Engineer.

**END OF SECTION**

This page intentionally left blank

## **PART 1 - GENERAL**

### **1.01 SUMMARY**

- A. The work includes the requirements for health and safety provisions necessary for all work at the site for this project. The work also includes compliance with all laws, regulations and ordinances with respect to safety, noise, dust, fire and police action, civil disobedience, security or traffic.
- B. Some of the work tasks may place workers in the potential position of coming into contact with regulated building materials, waste, or environmental media. Detailed information regarding the known nature and extent of refuse and regulated materials in the project area is included in Section 00 31 26 Existing Hazardous Material Information.
- C. The Contractor shall monitor site conditions for indications of identified and other potentially hazardous, dangerous, and/or regulated materials (suspicious material). Indicators of suspicious material include, but are not limited to, refuse, oily sheen or coloring on soil or water, or oily or chemical odors. If suspicious materials are encountered, the Contractor shall stop all work in that area and notify the Engineer immediately.
- D. This project is a Washington State Department of Ecology (Ecology) Remedial Action, subject to Ecology oversight.
- E. Landfill have the potential to create hazardous conditions if not controlled or recognized. Some of the hazards include:
  - 1. Fires that may start spontaneously from exposed and/or decomposed refuse.
  - 2. Fires and explosions that may occur from the presence of methane gas.
  - 3. Landfill gases and other trace gases may cause an oxygen deficiency in confined spaces such as trenches, vaults, conduits, and structures.
  - 4. Hydrogen sulfide, a highly toxic and flammable gas, and/or other toxic gases may be present.
  - 5. Possible caving of trenches and excavations when working over or in refuse fills.
- F. The Contractor is alerted to the presence of odorous conditions during excavation and stockpiling of materials due to hydrogen sulfide and possibly other odorous gases. Section 00 31 26 Existing Hazardous Material Information describes odorous conditions encountered during site investigations. The Contractor shall take appropriate health and safety measures to assess concentrations of these gases, and mitigate as required. Mitigation measures shall include the use of personal protective equipment, if required.

### **1.02 SUBMITTALS**

- A. Prior to Notice to Proceed, the Contractor shall provide a site specific Health and Safety Plan (HASP), which meets all the requirements of local, state and federal laws, rules and regulations. The HASP shall address all requirements for general health and safety and shall include, but not be limited to:
  - 1. Description of work to be performed and anticipated chemical and/or physical hazards associated with the work;
  - 2. Map of the site(s) illustrating the location of the anticipated hazards and areas of control for those hazards (including containments, exclusion/work zones, and contaminant reduction/decontamination zones);

3. Hazardous material inventory and safety data sheets (SDSs) for all chemicals which will be brought on site;
4. Signage appropriate to warn site personnel and visitors of anticipated site hazards;
5. Documentation that the necessary workers have completed the required Hazardous Waste Operations and Emergency Response (HAZWOPER) training;
6. Engineering controls/equipment to be used to protect against anticipated hazards;
7. Personal protective equipment and clothing including head, foot, skin, eye, and respiratory protection;
8. Procedures which will be used for:
  - a. Lockout/Tagout,
  - b. Fall protection,
  - c. Trenching and shoring,
  - d. Hot work,
  - e. Explosive conditions due to methane,
  - f. Oxygen deficient conditions,
  - g. Asbestos and lead hazards,
  - h. Suspicious materials and/or unidentified materials,
  - i. Confined-space entry (could include dewatering storage tanks, manholes, or other items),
  - j. Confined-space rescue, and
  - k. Odorous conditions and toxic gases;
9. Exposure monitoring to be used to evaluate actual hazards compared with anticipated conditions, including but not limited to arsenic exposure assessment;
10. Site housekeeping procedures and personal hygiene practices;
11. Personnel and equipment decontamination plan;
12. Railroad safety procedures;
13. Administrative controls;
14. Emergency plan including locations of and route to nearest hospital;
15. Medical surveillance program for site personnel before, during, and after completion of site work;
16. Recordkeeping including:
  - a. Documentation of appropriate employee training (e.g., Hazardous Waste Operations and Emergency Response [HAZWOPER] 40-hour training for staff involved with excavation and handling of soil),
  - b. Respirator fit testing, and
  - c. Arsenic exposure assessment results;

17. Name and qualification of person preparing the HASP and person designated to implement and enforce the HASP;
  18. Name and qualifications for Certified Safety Professional (CSP) or Certified Industrial Hygienist (CIH) and a copy of the CIH's or CSP's certification and resume;
  19. Excavation, stockpiling, and truck loading procedures;
  20. Lighting and sanitation; and
  21. Signatory page for site personnel to acknowledge receipt, understanding, and agreement to comply with the HASP.
- B. Prior to the start of any Work, the Contractor shall provide a site specific Spill Prevention, Control and Countermeasures (SPCC) Plan, which meets all the requirements of local, state and federal laws, rules and regulations.
- C. Contractor may submit the HASP and SPCC Plan as one comprehensive document or may submit the plans as separate documents.

### 1.03 POTENTIAL CHEMICAL HAZARDS

#### A. Site Contaminants

1. The Contractor must provide site workers with Hazard Communication standard information for potential site contaminants (in accordance with WAC 296-843). The Contractor shall ensure that all site workers are aware of and understand this information. Additional information shall also be provided by the Contractor, as necessary, to meet the Hazard Communication Standard and HASP requirements as noted in WAC 296-901-14010 and 296-843. Workers shall be instructed on basic methods or techniques to assist in detecting suspicious material.
2. The Project soils, in many areas, contain greater than 20 ppm of inorganic arsenic and the Contractor shall comply with all applicable requirements of Washington Department of Labor and Industries Division of Occupational Safety and Health (DOSH) Arsenic Standard, WAC 296-848 including but not limited to personal exposure monitoring, use of respirators and PPE, and worker training. Refer to WAC 296-848-100 Table 1 to determine applicable sections. Arsenic remnant soils are present throughout the site.

#### B. Potential Exposures Routes

1. Inhalation: Airborne dusts, fibers, particulates, or vapors may be released during site activities. Inhalation of airborne inorganic arsenic may occur.
2. Skin and Eye Contact: Dusts generated during site work activities may settle on the skin or clothing of site workers. Also, workers may contact potentially regulated sediments, or water, in the normal course of their work. Precautions to prevent skin or eye contact with hazardous materials will be included in the HASP. Arsenic exposure may cause skin irritation.
3. Ingestion: Inadvertent transfer of site contaminants from hands or other objects to the mouth could occur if site workers eat, drink, smoke, chew tobacco, or engage in similar activities in work areas. This could result in ingestion of site contaminants. Precautions to prevent accidental or inadvertent ingestion of hazardous materials will be included in the HASP.

- C. Chemical hazards may also result from Contractor operations resulting in inadvertent release of fuel, oil, or other chemicals in a manner that would expose workers.

#### 1.04 POTENTIAL PHYSICAL AND OTHER HAZARDS

- A. The Work of the Contractor is described elsewhere in these specifications. Precautions to prevent all anticipated physical and other hazards, including heavy equipment and vessels, shall be addressed in the HASP.
- B. Specific aspects of construction resulting in physical hazards anticipated for this project include, but are not limited to the following:
  - 1. Work over or adjacent to water, presenting hazards of falling into water, hypothermia from exposure to the elements, and drowning;
  - 2. Operation of marine equipment, including winches, dredges, and related equipment, entrapment, ensnarement, and being struck by moving parts hazards;
  - 3. Completion of diver surveys with specific health and safety elements;
  - 4. Major hazards associated with earthwork impacts from moving construction vehicles and trucks, noise, thermal stress, contact with unguarded machines, excavation hazards (i.e., cave-in, utility, etc.), strains from heavy lifting, and reduced visibility and communications difficulties in work area; and
  - 5. Operation of equipment, including excavators, loaders, and related equipment, presenting hazards of entrapment, ensnarement, and being struck by moving parts.
- C. Other anticipated physical hazards:
  - 1. Heat stress, such as that potentially caused by impermeable clothing (may reduce the cooling ability of the body due to evaporation reduction);
  - 2. Cold stress, such as that potentially caused during times when temperatures are low, winds are high, especially when precipitation occurs during these conditions;
  - 3. Biological hazards, such as mold, insect stings, or bites, poisonous plants (i.e., poison oak, sumac, etc.); and
  - 4. Trips and falls.
- D. Firewatch Procedures
  - 1. A firewatch is implemented to ensure the fire-safety of a building, structure or area in the event of any act (e.g., hot work) or situation instigating an increased risk of fire. The term "firewatch" is used to describe a dedicated person or persons whose sole responsibility is to look for fires within an established area.
  - 2. A firewatch is required when all hot work is being performed.
  - 3. The firewatch is to perform the following functions:
    - a. Firewatch personnel are to keep diligent watch for fires in the general area where the work is being performed.
    - b. Firewatch personnel are to be familiar with facilities and procedures for sounding an alarm in the event of a fire.
    - c. Firewatch personnel are to have fire extinguishing equipment readily available and be trained in its use, including practice on test fires.

- d. Firewatch personnel are to inspect the site prior to hot work activities to ensure that combustibles are removed or covered and that any nearby holes or penetrations in the ground and walls are sealed or covered with fire-safe materials.
- e. Firewatch personnel are to watch for fires in all exposed areas. If a fire is located, firewatch personnel are to sound the evacuation alarm immediately and after that try to extinguish the fire, only when obviously within the capacity of the equipment available.
- f. The firewatch is to be maintained for at least 120 minutes after completion of hot work such as cutting, welding, or other open flame operations, in order to detect and extinguish smoldering and flaming fires. During this time, the work area and other adjacent areas where sparks or flame may have traveled are to be searched for signs of combustion.

## **PART 2 - PRODUCTS**

### **2.01 SAFETY SIGNAGE**

- A. The Contractor shall provide signage at strategic locations within the project site to alert jobsite workers and visitors of the remediation work, associated hazards, and required precautions.

### **2.02 PRODUCTS SPECIFIED FOR HEALTH AND SAFETY**

- A. Provide the equipment and supplies necessary to support the work as described in the site-specific HASP. Equipment and supplies may include, but are not limited to:
  - 1. All chemicals to be used on site;
  - 2. A hazardous materials inventory and SDSs for the chemicals brought on site;
  - 3. Enclosure equipment (for dust and asbestos fiber control);
  - 4. Fencing and barriers;
  - 5. Warning signs and labels;
  - 6. Trenching equipment;
  - 7. Fire extinguishers;
  - 8. Equipment to support hot work;
  - 9. Equipment to support lockout/tagout procedures;
  - 10. Scaffolding and fall protection equipment;
  - 11. Personal protective equipment (hard hats, foot gear, skin, eye, and respiratory protection);
  - 12. Area and personnel exposure monitoring equipment;
  - 13. Demolition equipment and supplies;
  - 14. Decontamination equipment and supplies;
  - 15. First aid equipment;
  - 16. Spill response and spill prevention equipment; and
  - 17. Field documentation logs/supplies.

## **PART 3 - EXECUTION**

### **3.01 WORK AREA PREPARATION**

- A. Contractor shall comply with health and safety rules, regulations, ordinances promulgated by the local, state, and federal government, the various construction permits, and other sections of the Contract Documents. Such compliance shall include, but not be specifically limited to: any and all protective devices, equipment and clothing; guards; restraints; locks; latches; switches; and other safety provisions that may be required or necessitated by state and federal safety regulations. The Contractor shall determine the specific requirements for safety provisions and shall have inspections and reports by the appropriate safety authorities to be conducted to ensure compliance with the intent of the regulations.
- B. Contractor shall inform employees, subcontractors and their employees of the potential danger in working with any potentially regulated materials, equipment, soils and groundwater at the project site.
  - 1. The Contractor shall not proceed with jobsite activities that might result in exposure of employees to hazardous materials, including arsenic, until the HASP is reviewed by the Engineer.
  - 2. In addition, the Engineer will submit a copy of the Contractor's HASP to Ecology for review. Ecology and the Engineer will review but not approve HASP.
- C. All Contractor employees expected to work at the jobsite or individuals entering the jobsite shall read the Contractor HASP before they enter the jobsite, and will sign a statement provided by the Contractor that they have read and understand the HASP. A copy of the Contractor's HASP shall be readily available at the site at all times the work is being performed.
- D. The Contractor's HASP shall be amended as needed by the CIH or CSP to include special work practices warranted by jobsite conditions actually encountered. Special practices could include provisions for decontamination of personnel and equipment, and the use of special equipment not covered in the initial plan.
- E. Contractor shall perform whatever work is necessary for safety and be solely and completely responsible for conditions of the job site, including safety of all persons (including employees of the Engineer, Engineer's Representative, and Contractor) and property during the Contract period. This requirement applies continuously and is not limited to normal working hours.
- F. The Engineer's review of the Contractor's performance does not include an opinion regarding the adequacy of, or approval of, the Contractor's safety supervisor, the site-specific HASP, safety program or safety measures taken in, on, or near the job site.
- G. Accidents causing death, injury, or damage must be reported immediately to the Engineer and the Port Security Department in person or by telephone or messenger. In addition, promptly report in writing to the Engineer all accidents whatsoever arising out of, or in connection with, the performance of the work whether on, or adjacent to, the site, giving full details and statements of witnesses.
- H. If a claim is made by anyone against the Contractor or any subcontractor on account of any accident, the Contractor shall promptly report the facts in writing within 24 hours after occurrence, to the Engineer, giving full details of the claim.

### 3.02 SITE SAFETY AND HEALTH OFFICER

- A. Contractor shall provide a person designated as the Site Safety and Health Officer, who is thoroughly trained in rescue procedures, has a minimum current 40-hour HAZWOPER certification (minimum), and trained to use all necessary safety equipment, air monitoring equipment, and gas detectors. The person must be available and/or present at all times while work is being performed, and conduct testing, as necessary.
- B. The Site Safety and Health Officer shall be empowered with the delegated authority to order any person or worker on the project site to follow the safety rules. Failure to observe these rules is sufficient cause for removal of the person or worker(s) from this project.
- C. The Site Safety and Health Officer is responsible for determining the extent to which any safety equipment must be utilized, depending on conditions encountered at the site.

### 3.03 GENERAL SAFETY GUIDELINES FOR HAZARDOUS GASES

- A. The generally accepted procedure to protect the worker from the effects of the dangers from hazardous gases is through the use of four safeguard measures:
  - 1. Test the atmosphere: Before entering a trench, underground vault, or any other excavation, the atmosphere shall be tested to detect any adverse environmental conditions with a gas detector instrument. Test instruments shall be properly maintained and calibrated. The test shall be conducted from top to bottom of the excavation or every four (4) feet.
  - 2. Ventilate all confined spaces: Before entry and during the entire time workers are in the confined space. Forced ventilation is the generally accepted procedure.
  - 3. Use appropriate safety equipment: All personnel shall be trained to operate the appropriate safety equipment that are to be utilized during the course of their work. It is the responsibility of the Contractor's Site Safety and Health Officer to ascertain that all safety equipment is being used when appropriate.
  - 4. Provide backup safety personnel: Prior to any personnel entering an excavation or confined space, a separate individual shall be positioned outside the space.
- B. Safety Monitoring Instrumentation: The Safety and Health Officer shall have appropriate instruments (detector[s]) to test for oxygen deficiency and for the presence of methane gas, hydrogen sulfide, and/or other known or suspected vapors and gases. The Site Safety and Health Officer shall periodically calibrate the instruments, regularly test the excavation or space areas and other work areas for safe working conditions, and ensure that appropriate safety equipment is available.

### 3.04 SUPPLEMENTAL SAFETY PROGRAM FOR GASES

- A. Supplemental to the Contractor's regular safety program, the Contractor shall develop and institute procedures to inform all workers at the site of the potential for the presence of methane and other landfill gases emanating from the natural decomposition of refuse buried at or near the job site, and the importance of safety precautions to ensure the safety of workers and the public.
- B. Recommended Precautions: In addition to conforming to safety rules and regulations of governmental authorities having jurisdiction, the Contractor shall conform to the following minimum precautionary measures:

1. Frequently monitor for all possible hazardous gases, oxygen deficiency and other known or suspected vapors and gases.
  2. Prohibit smoking in or near open excavations, exposed refuse, and in the vicinity of underground pipe laying activities. Smoking will be permitted only in those areas designated by the Site Safety and Health Officer.
  3. In the event toxic gas is present in sufficient quantities to trigger a gas detection alarm, the Contractor shall immediately evacuate all personnel from the area until determined safe by the Site Safety and Health Officer.
  4. Do not use explosives.
  5. Do not leave refuse exposed overnight, unless otherwise approved by the Engineer. Any refuse exposed during construction activities shall be covered with at least a 6-inch layer of earth, tarps, or membrane.
  6. Do not weld in trenches, enclosed areas, or over refuse unless performed in areas tested and approved by the Site Safety and Health Officer.
  7. Construction equipment used in excavation activities and/or refuse removal operations shall be equipped with vertical exhaust and spark arresters.
  8. Electric motors utilized in excavation areas and below ground shall be explosion-proof.
  9. As construction progresses, all pipe openings and valves shall be closed as soon as installed to prevent the migration of gases through the pipeline system.
- C. Suggested Measures: If not already included in the Contractor's standard safety practices, the Contractor shall add the following measures to their safety program:
1. Workers shall be cautioned on the possibility of collapsing excavations during construction operations near and in open excavations particularly in refuse-filled areas. Anyone working near the edge of deep excavations should be secured with a safety belt, harness, or limit line to preclude the possibility of falling into the opening. Refuse filling operations and compaction is quite variable and therefore may not provide the same slope stability as excavations in native soils.
  2. Any personnel working near the edge of well excavations or similar construction should wear a harness securely attached to a lanyard. The lanyard shall be made as short as possible and securely fastened to a safe object.
  3. Safe and suitable ladders that project 2 feet above the top of the trench shall be provided for all trenches over 4 feet in depth. A minimum of one ladder shall be provided for each 25 feet of open trench, and be so located that workers in the trench need not move more than 25 feet to a ladder.
  4. No worker shall be allowed to work alone in an excavation. An individual shall be positioned outside the excavation, but within eyesight of the workers in the excavation, and assist them should an emergency develop.
  5. Work upwind of an excavation where possible, unless the excavation is constantly monitored and declared safe.
  6. Workers should avoid contact with exposed refuse where possible.
  7. No excavation or drilled hole greater than 2 feet deep shall be left unattended or open overnight unless it is securely covered in a manner acceptable to the Engineer.

8. Fire extinguishers with a rating of at least A, B, and C shall be available onsite.
9. Startup and shutdown of equipment shall be avoided in areas of exposed refuse.
10. Personnel in an open excavation or in the presence of landfill gas shall be fully clothed with appropriate personal protection equipment. Workers shall immediately vacate the excavation if gases are detected therein, and shall not be permitted to re-enter the excavation unless satisfactory precautionary measures are implemented.

### 3.05 SPILL PREVENTION AND CONTROL

- A. The Contractor shall be responsible for prevention, containment and cleanup of spilling petroleum and other chemicals/hazardous materials used in the Contractor's operations. All such prevention, containment and cleanup costs shall be borne by the Contractor.
- B. The Contractor is advised that discharge of oil, fuel, other petroleum, or any chemicals/hazardous materials from equipment or facilities into state waters or onto adjacent land is not permitted under state water quality regulations.
- C. In the event of a discharge of oil, fuel or chemicals/hazardous materials into waters, or onto land with a potential for entry into waters, containment and cleanup efforts shall begin immediately and be completed as soon as possible, taking precedence over normal work. Cleanup shall include proper disposal of all spilled material and used cleanup materials.
- D. The Contractor shall, at a minimum, take the following measures regarding spill prevention, containment and cleanup:
  1. Fuel hoses, lubrication equipment, hydraulically operated equipment, oil drums and other equipment and facilities shall be inspected regularly for drips, leaks or signs of damage, and shall be maintained and stored properly to prevent spills. Proper security shall be maintained to discourage vandalism.
  2. All land-based chemical, oil and products' storage tanks shall be diked, contained and/or located so as to prevent spills from escaping into the water. Dikes and containment area surfaces shall be lined with impervious material to prevent chemicals or oil from seeping through the ground and dikes.
  3. All visible floating sheen shall be immediately contained with booms, dikes or other appropriate means and removed from the water prior to discharge into state waters. All visible spills on land shall be immediately contained using dikes, straw bales or other appropriate means and removed using sand, sawdust or other absorbent material, which shall be properly disposed of by the Contractor. Waste materials shall be temporarily stored in drums or other leak-proof containers after cleanup and during transport to disposal. Waste materials shall be disposed offsite in accordance with applicable local, state and federal regulations.
  4. In the event of any oil or product discharges into public waters, or onto land with a potential for entry into public waters, the Contractor shall immediately notify the Port Security at their listed 24-hour response number:
    - a. Port Security: 253-383-9472
- E. The Contractor shall maintain the following materials (as a minimum) at each of the project sites:
  1. Oil-absorbent booms: 100 feet;

2. Oil-absorbent pads or bulk material, adequate for coverage of 200 square feet of surface area;
3. Oil-skimming system; and
4. Oil dry-all, gloves, and plastic bags.

**END OF SECTION**

## **PART 1 - GENERAL**

### **1.01 SUMMARY**

- A. This Section discloses procedures to follow if unknown regulated materials are encountered.

### **1.02 NOTIFICATION AND SUSPENSION**

- A. In the event the Contractor detects the presence of potentially regulated materials not previously identified in this specification, the Contractor shall stop work and immediately notify the Port. Following such notification by the Contractor, the Port shall in turn notify the various governmental and regulatory agencies concerned with the presence of regulated materials, if warranted. Depending upon the type of materials identified, the Port may suspend work in the vicinity of the discovery under the provisions of General Conditions.
1. Following completion of any further testing necessary to determine the nature of the materials involved, the Port will determine how the material shall be managed. Although the actual procedures used in resuming the work shall depend upon the nature and extent of the regulated material, the following alternate methods of operation are foreseen as possible:
    - a. Contractor to resume work as before the suspension.
    - b. Contractor to move its operations to another portion of the work until measures to eliminate any hazardous conditions can be developed and approved by the appropriate regulatory agencies.
    - c. The Port to direct the Contractor to dispose or treat the material in an approved manner.
    - d. The Port to terminate or modify the Contract accordingly, for unforeseen conditions.

## **PART 2 - PRODUCTS - NOT USED**

## **PART 3 - EXECUTION - NOT USED**

**END OF SECTION**

This page intentionally left blank

## **PART 1 - GENERAL**

### **1.01 SUMMARY**

- A. Soils that cannot be reused onsite and are anticipated to be exported to an off-site facility must have a completed soil profile prior to export. The Port will conduct testing of material as defined further in this specification. The Contractor is responsible for any additional testing necessary to satisfy requirements of the Contractor's receiving facility.
- B. Soils excavated within the project area, as shown on the drawings, are anticipated to be free of regulated material; however, should the Contractor identify soil that cannot be reused as part of the project, the Contractor shall notify the Engineer to determine if the soil requires special handling.
  - 1. Soil with unexpected regulated material, as identified by visual and/or olfactory methods, shall be segregated from other excavated material until such time as appropriate testing and analysis can be completed by the Port. Upon completion of the soil profile, the Engineer will inform the Contractor of any special handling requirements based on the results.
  - 2. Soil beyond construction excavation limits will not require excavation unless free draining product is observed or other special conditions exist; in which case the Engineer will direct the Contractor in additional excavation. Soils determined to require special handling will be hauled and disposed of at an approved disposal facility.
- C. No soil shall be removed from the site without prior notification to the Engineer. The notification shall include:
  - 1. An estimate of the number of truck-trips, the haul destination, and the period in which these trips will be made (e.g., 20 truck-trips to the Waste Management Facility over the two-week period beginning on March 1, 2012).

### **1.02 DEFINITIONS**

- A. Olfactory Indications (methods): Of or relating to the sense of smell. Soils containing petroleum and other volatile constituents typically exhibit characteristic odors that can be detected (and sometimes identified) by smell.
- B. Regulated Material: Any chemical, physical, biological, or radiological substance that does not occur naturally in the environment, or that occurs at concentrations higher than natural background levels, and is regulated by agencies as to the disposal/recycling facility(ies) the material can and cannot go (i.e., EPA, Department of Ecology, Tacoma-Pierce County Health Department).
- C. Soil (waste) Profile: A characterization of the chemical and physical properties of soil material designated for off-site disposal, including the presence of pollutants and their concentrations as measured by approved laboratory analytical methods. A profile is required by the receiving permitted disposal or recycling facility.
- D. Special Handling: Refers to hauling and disposal of soils that cannot be reused in place as backfill or as general fill at another (off-site) location due to the presence of pollutants in concentrations above allowable limits. Such soils must be hauled to and managed at a permitted disposal facility.

- E. Type A Regulated Soil: Soil that must be removed from the Project site and has been determined by the Engineer to contain pollutants in concentrations that exceed state or federal dangerous or hazardous designations (respectively), or other special Port-determined criteria. Type A Regulated Soil requires disposal at an approved Subtitle C hazardous waste landfill.
- F. Type B Regulated Soil: Soil that must be removed from the Project site and has been determined by the Engineer to contain pollutants in concentrations that are below dangerous or hazardous levels, but could negatively impact the quality of air, waters of the state, soils or sediments, or pose a threat to the health of humans or other living organisms, depending on where the soil is disposed. Type B Regulated Soil requires disposal an approved Subtitle D solid waste landfill.
- G. Type C Regulated Soil: Soil that must be removed from the Project site and has been determined by Engineer to contain unknown constituent(s) and/or in unknown concentration(s) and requires further analysis and characterization. Type C Regulated soil will require disposal at an approved Subtitle C hazardous waste landfill or Subtitle D solid waste landfill if additional soil characterization indicates special handling is required.
- H. Type D Soil: Soil determined by the Engineer not to require special handling with regard to this Contract. Classification of material as Type D Soil by the Port is not a certification nor does it release the Contractor of liability or obligation to meet any disposal or storage facility acceptance or testing requirements.
- I. Unexpected Regulated Material: Regulated material unexpectedly found in an excavation or in other locations where there is no prior knowledge, information, or history to indicate possible spills or releases of regulated material.
- J. Visual Indications (methods): A preliminary evaluation of the potential presence of contamination based on visual observation. For example, soils containing petroleum are frequently discolored or stained relative to non-petroleum impacted native soils or clean fill.

### 1.03 HEALTH AND SAFETY

- A. The Contractor is required to implement all health and safety provisions as required by Specification 01 35 29 – Health, Safety and Emergency Response. These provisions include any special monitoring, personal protective equipment, or work plans to accommodate regulated soil or material special handling. Use of environmental characterization data may not be appropriate for health and safety purposes.

### 1.04 SUBMITTALS

- A. Prior to excavation of any subsurface materials, the Contractor shall submit a Soils Management Plan to the Engineer. The Soils Management Plan must be approved by the Engineer prior to any excavation of subsurface materials. The Soils Management Plan must include the following:
  - 1. Identification of all soil disposal facilities anticipated to be used for soils that are determined to be Type A or Type B Regulated Soil.
  - 2. Identification of all fill sites, disposal/recycling facilities and/or end uses anticipated to be used for soil determined to be Type D Soil in accordance with paragraph 3.02 of this section.
  - 3. Contingency for delivery and placement of Type C Regulated Soil at an on-site soil stockpile area.

4. Contingency for managing soil/debris encountered during excavation that may disqualify soil for disposal or recycle at the anticipated facilities.
  5. General description of how equipment operators, safety staff and other applicable on-site personnel will identify and respond to soil containing potentially regulated material.
  6. Contractor shall coordinate with the Engineer to facilitate handling of regulated soil in accordance with this specification.
  7. Description of all haul routes to be used on the project.
- B. A completed soil profile prior to export to an off-site receiving facility.

## **PART 2 - PRODUCTS - NOT USED**

## **PART 3 - EXECUTION**

### **3.01 EXCAVATION/TESTING**

- A. The field-testing for soil to be exported offsite will be performed by the Port and will result in the following classification of material:
1. Type A Regulated Soil as defined in 1.02(E) of this Section
  2. Type B Regulated Soil as defined in 1.02(F) of this Section
  3. Type C Regulated Soil as defined in 1.02(G) of this Section
  4. Type D Soil as defined in 1.02(H) of this Section
- B. Contractor shall give Port no less than one week notice for sampling export soil prior to disposal offsite. Contractor shall anticipate at least two weeks for lab results.
- C. Laboratory turnaround times may require additional time for analytical results; therefore, Contractor should coordinate with Engineer well in advance of anticipated disposal date. Samples that are required to have "rush" analysis performed due to the Contractor's failure to disclose the anticipated disposal date shall have the difference in service fees paid by the Contractor, or the Contractor may delay the disposal until the standard analysis turnaround time is complete, at no additional cost to the Port.

### **3.02 TRANSPORTATION AND OFF-SITE DISPOSAL OF SOILS**

- A. The Contractor shall be responsible for handling, re-handling, loading, transporting, and legal off-site removal of all waste materials and excavated soils not reused onsite.
1. Contractor shall ensure that transport truck gross weight meets federal and/or state Department of Transportation (DOT) requirements and the requirements of the receiving facility, whichever is more stringent.
  2. Contractor shall take measures to prevent debris from being spilled from trucks or tracked from the site to local streets. Contractor shall sweep streets adjacent to the site as necessary or as directed by the Engineer.
  3. Contractor shall ensure that any vehicle transporting materials offsite are properly labeled and placarded in accordance with federal and state DOT requirements.
- B. Type A Regulated and Type B Regulated Soil shall be hauled to an approved facility by the Contractor for disposal.

- C. Type C Regulated Soil is of unknown origin or special circumstances. Type C Regulated Soil shall be hauled to an on-site segregated stockpile area. The Contractor shall protect the material from weather and other disturbances once stockpiled. The Port will inform the Contractor of the soil profile following additional analysis of the suspect material (as needed), and the soil will be categorized as either Type A Regulated, Type B Regulated or Type D Soil and disposed of accordingly.
- D. Type D Soil that is not reused onsite shall be hauled by the Contractor to a site determined by the Contractor. If the receiving/disposal facility requires additional testing or certification of this soil, Contractor shall complete these requirements, at no additional cost to the Port. The Port will not certify or declare the material suitable for unrestricted use.

### 3.03 OTHER REQUIREMENTS

- A. Type A, Type B or Type C Regulated Soil may be, upon approval of the Engineer, temporarily stockpiled within the construction area. Contractor shall place an impervious liner beneath the soil and securely cover the stockpile with waterproof covering (e.g., plastic sheeting). Additional measures (e.g., berm, jersey barriers, silt fence, etc.) may be required to minimize soil runoff from the stockpile area. The soil shall be removed prior to completion of Work.
- B. Contractor shall provide the Engineer with all hauling receipts (or copies of receipts) from the disposal facility for all Type A, Type B or Type C Regulated Soil at least weekly.
- C. The Engineer may shut down excavation activities should unexpected regulated material be encountered during excavation.

**END OF SECTION**

## **PART 1 - GENERAL**

### 1.01 SUMMARY

- A. The Work includes the requirements to provide air and noise control measures until Final Completion of the Work.

### 1.02 SUBMITTALS

- A. Prior to Notice to Proceed, the Contractor shall submit a list of equipment to be used on the project and written certification that all equipment on the list and any additional equipment, including Contractor's, subcontractors or supplier's equipment, shall meet the requirements of 3.01 below.

## **PART 2 - PRODUCTS - NOT USED**

## **PART 3 – EXECUTION**

### 3.01 AIR POLLUTION CONTROL

- A. The Contractor shall meet or exceed EPA Tier 2 off-road diesel engine emission standards for off-road equipment  $\geq$  25hp and meet or exceed EPA 1994 on-road diesel engine emission standards for on-road equipment except as follows:
  - 1. Equipment being used in an emergency or public safety capacity
- B. The Contractor shall not discharge smoke, dust, and other hazardous materials into the atmosphere that violate local, state or federal regulations.
- C. No vehicles can idle for more than 5 consecutive minutes, except as follows:
  - 1. Idling is required to bring or maintain the equipment to operating temperature;
  - 2. Engine idling is necessary to accomplish work for which the equipment was designed (i.e. operating a crane); or
  - 3. Idling vehicles being used in an emergency or public safety capacity.
- D. The Contractor shall minimize nuisance dust by cleaning, sweeping, vacuum sweeping, sprinkling with water, or other means. Equipment for this operation shall be on the job site or available at all times.

### 3.02 NOISE CONTROL

- A. The Contractor shall comply with all local controls and noise level rules, regulations and ordinances which apply to work performed pursuant to the Contract.
- B. All internal combustion engines used on the job shall be equipped with a muffler of a type recommended by the manufacturer.

**END OF SECTION**

This page intentionally left blank

## **PART 1 – GENERAL**

### **1.01 SUMMARY**

- A. The Work shall consist of the procedures to be followed in the event that cultural and/or historical resources are inadvertently discovered during Project activities.
- B. The project is located in an area previously inventoried for cultural and historical resources; however, it is possible that additional, previously unidentified archaeological resources and/or skeletal remains could be inadvertently discovered during project activities. In the event that prehistoric, historic-era archaeological materials or skeletal remains are discovered, the appropriate protection measures and protocols described in this section must be followed.
- C. The Port will provide archaeological monitoring by or under the guidance of a professional archaeologist (archaeologist).
  - 1. All ground disturbing activities in native soils must be observed by the archaeologist.
- D. All Contractor employees shall be aware of the Inadvertent Discovery Plan and shall notify the Engineer if a suspected archeological resource is discovered.
- E. A copy of the Inadvertent Discovery Plan shall be kept on site and available at all times during ground disturbing activities.

### **1.02 REFERENCES**

- A. The rules, requirements, and regulations that apply to this Work include, but are not necessarily limited to the following:
  - 1. Port of Tacoma's "Archaeological Monitoring and Inadvertent Discovery Plan." A copy of this Plan is located in Appendix \_\_\_\_ .

### **1.03 AUTHORITY OF ARCHAEOLOGIST**

- A. At any time, when the archaeologist determines that possible cultural resources or skeletal remains might be present, they have the authority to stop work, secure the area of the find and determine a work stoppage zone. This area shall remain protected until further decisions can be made regarding the work site.
- B. The archaeologist will stand in close proximity of the construction equipment to view subsurface deposits as they are exposed and will be in close communication with the equipment operators to ensure adequate opportunity for observation and documentation. The archaeologist will coordinate the depths of the lifts with the Engineer and the Contractor.
- C. The archaeologist will be provided the opportunity to screen excavated sediments and matrix samples when this is judged to be useful.
- D. Archaeological monitoring will proceed until it can be determined by the archaeologists that skeletal remains or other cultural resources are not likely to be impacted by construction activities.

## **PART 2 – PRODUCTS – NOT USED.**

## **PART 3 – EXECUTION**

### **3.01 PROTOCOLS FOR DISCOVERY OF ARCHAEOLOGICAL RESOURCES**

- A. In the event that archaeological resources are encountered within the project, the following actions will be taken:

1. All ground disturbing and construction activity at the specific location will stop and the area will be protected via temporary fencing or other appropriate measures.
2. The Contractor's work supervisor will be notified immediately.
3. Contact the Port's Engineer and Environmental Project Manager immediately.
4. A work stoppage zone, as determined by the Archaeologist and Port, will be established.
5. The Port's Environmental Project Manager will contact the appropriate agencies.
6. The Work Stoppage Zone will remain protected until further decisions can be made regarding the area.
7. The Contractor will be allowed to continue ground disturbing and other construction activities outside of the established work stoppage zone.

### 3.02 PROTOCOLS FOR DISCOVERY OF HUMAN REMAINS

- A. In the event that suspected human remains are encountered within the project, the following actions, consistent with RCWs 68.50.645, 27.44.055 and 68.60.055 will be taken:
1. All ground disturbing and construction activity at the specific location will stop and the area will be protected via temporary fencing or other appropriate measures. The remains will not be photographed, touched, moved or further disturbed.
  2. The Contractor's work supervisor will be notified immediately.
  3. Contact the Port's Engineer and Environmental Project Manager immediately.
  4. The Environmental Project Manager will notify the county medical examiner / coroner and local law enforcement.
  5. A Work Stoppage Zone will be determined and remain protected until further decisions can be made regarding the area.
  6. The Contractor will be allowed to continue ground disturbing and other construction activities outside of the established work stoppage zone.

### 3.03 PROTOCOLS FOR CONFIDENTIALITY

- A. In the event that human remains or cultural resources are discovered within the project area, the Port and the Contractor shall keep and maintain all information regarding any discovery confidential.
1. At no time shall the Contractor contact the media, any third party or otherwise share information regarding the discovery with any member of the public.
  2. If the Contractor is contacted by the media or the public regarding any discovery, they shall refrain from comment, and contact the Engineer or Environmental Project Manager immediately.

**END OF SECTION**

## **PART 1 - GENERAL**

### **1.01 PERMITS, CODES, AND REGULATIONS**

- A. The following permits/approvals have been applied for (or are on file) and incorporated into the Contract:
  - 1. State Environmental Policy Act (SEPA) Compliance
  - 2. Shoreline Management Act / Critical Areas Compliance
  - 3. Hydraulic Code Compliance
  - 4. Section 404 of CWA and Section 10 of RHA Compliance
  - 5. Section 106 of NHPA Compliance
- B. Conform with the requirements of listed permits and additional or other applicable permits, codes, and regulations as may govern the Work.
- C. Obtain and pay fees for licenses, permits, inspections, and approvals required by laws ordinances, and rules of appropriate governing or approving agencies necessary for proper completion of Work (other than those listed under item 1.01.A above and Special Inspections called for by the International Building Code).
- D. Conform with current applicable codes, regulations and standards, which is the minimum standard of quality for material and workmanship. Provide labor, materials, and equipment necessary for compliance with code requirements or interpretations, although not specifically detailed in Drawings or specifications. Be familiar with applicable codes and standards prior to bidding.
- E. Process through Engineer, request to extend, modify, revise, or renew any of the permits (listed in 1.01.A above). Furnish requests in writing and include a narrative description and adequate Drawings to clearly describe and depict proposed action. Do not contact regulatory agency with requests for permit extensions, modifications, revisions, or renewals without the prior written consent of the Engineer.

### **1.02 VARIATIONS WITH CODES, REGULATIONS AND STANDARDS**

- A. Nothing in the Drawings and specifications permits Work not conforming to codes, permits, or regulations. Promptly submit written notice to the Engineer of observed variations or discrepancies between the Contract Documents and governing codes and regulations.
- B. Appropriate modifications to the Contract Documents will be made by Change Order to incorporate changes to Work resulting from code and/or regulatory requirements. Contractor assumes responsibility for Work contrary to such requirements if Work proceeds without notice.
- C. Contractor is not relieved from complying with requirements of Contract Documents which may exceed, but not conflict with requirements of governing codes.

## **PART 2 - PRODUCTS - NOT USED**

## **PART 3 – EXECUTION - NOT USED**

**END OF SECTION**

This page intentionally left blank

## **PART 1 - GENERAL**

### 1.01 SUMMARY

- A. This section includes requirements relating to referenced standards.

### 1.02 QUALITY ASSURANCE

- A. For products or workmanship specified by reference to a document or documents not included in the Project Manual, also referred to as reference standards, comply with requirements of the standard, except when more rigid requirements are specified or are required by applicable codes.
- B. Conform to reference standard of date of issue specified in this section, except where a specific date is established by applicable code.
- C. Should specified reference standards conflict with Contract Documents, request clarification from the Engineer before proceeding.
- D. Neither the contractual relationships, duties, or responsibilities of the parties in Contract nor those of the Engineer shall be altered by the Contract Documents by mention or inference otherwise in any reference document.

## **PART 2 - PRODUCTS - NOT USED**

## **PART 3 - EXECUTION - NOT USED**

**END OF SECTION**

This page intentionally left blank

## **PART 1 - GENERAL**

### **1.01 QUALITY CONTROL FOR COMPLIANCE:**

- A. The Contractor shall perform such detailed examination, inspection, quality control and assurance of the Work as to ensure that the Work is progressing and is being completed in strict accordance with the Contract Documents. The Contractor shall plan and lay out all Work in advance of operations so as to coordinate all Work without delay or revision. The Contractor shall be responsible for inspection of portions of the Work already performed to determine that such portions are in proper condition to receive subsequent Work. Under no conditions shall a portion of Work proceed prior to preparatory work having been satisfactorily completed. The Contractor shall ensure that the responsible Subcontractor has carefully examined all preparatory work and has notified the Contractor (who shall promptly notify the Port in writing) of any defects or imperfections in preparatory work that will, in any way, affect completion of the Work.

### **1.02 QUALITY ASSURANCE - CONTROL OF INSTALLATION**

- A. Monitor quality control over suppliers, manufacturers, products, services, site conditions, and workmanship, to produce Work of specified quality.
- B. Comply with manufacturers' instructions, including each step in sequence.
- C. Should manufacturers' instructions conflict with Contract Documents, request clarification from Engineer before proceeding.
- D. Comply with specified standards as minimum quality for the Work except where more stringent tolerances, codes, or specified requirements indicate higher standards or more precise workmanship.
- E. Perform Work by persons qualified to produce required and specified quality.
- F. Verify that field measurements are as indicated on shop Drawings or as instructed by the manufacturer.
- G. Secure Products in place with positive anchorage devices designed and sized to withstand stresses, vibration, physical distortion, or disfigurement.

### **1.03 TOLERANCES**

- A. Monitor fabrication and installation tolerance control of Products to produce acceptable Work. Do not permit tolerances to accumulate.
- B. Comply with manufacturers' tolerances. Should manufacturers' tolerances conflict with Contract Documents, request clarification from Engineer before proceeding.
- C. Adjust Products to appropriate dimensions; position before securing Products in place.

### **1.04 TESTING SERVICES**

- A. Tests, inspections and approvals of portions of the Work shall be made as required by the Contract Documents and by applicable laws, statutes, ordinances, codes, rules and regulations or lawful orders of public authorities.
  - 1. Neither observations by an inspector retained by the Port, the presence or absence of such inspector at the site, nor inspections, tests, or approvals by others, shall relieve the Contractor from any requirement of the Contract Documents, nor is any such inspector authorized to change any term or condition of the Contract Documents.

- B. Necessary materials testing shall be performed by an independent testing laboratory during the execution of the Work and paid for by the Port of Tacoma, unless otherwise specified. Access to the area necessary to perform the testing and/or to secure the material for testing, shall be provided by the Contractor.
- C. Testing does not relieve Contractor from performing work to contract requirements.
- D. Re-testing required because of non-conformance to specified requirements will be charged to the Contractor by deducting testing charges from the Contract Sum via Change Order.
- E. Material testing for initial material approval will be performed by an independent, certified laboratory and paid for by the Contractor. These tests must be dated within six (6) months of the submittal date.
- F. Subsequent sampling and testing, required as the work progresses to ensure continual control of materials and compliance with all requirements of the Contract documents, shall be the responsibility of the Port, except as required by other sections of these Specifications.

#### 1.05 MANUFACTURER'S FIELD SERVICES

- A. When specified in individual specification sections, require material or Product suppliers or manufacturers to provide qualified staff personnel to observe site conditions, conditions of surfaces and installation, quality of workmanship, start-up equipment, test, and adjust and balance equipment as applicable, and to initiate instructions when necessary.
- B. Submit qualifications of observer to Engineer 30 days in advance of required observations. Observer subject to approval of Engineer.
- C. Report observations and site decisions or instructions given to applicators or installers that are supplemental or contrary to manufacturers' written instructions.

**PART 2 - PRODUCTS - NOT USED**

**PART 3 - EXECUTION - NOT USED**

**END OF SECTION**

## **PART 1 - GENERAL**

### 1.01 SUMMARY

- A. This section includes requirements relating to the following:
  - 1. Temporary utilities,
  - 2. Temporary telecommunications services,
  - 3. Temporary sanitary facilities,
  - 4. Temporary Controls: Barriers, enclosures, and fencing, and

### 1.02 TEMPORARY UTILITIES

- A. Provide and pay for all electrical power, lighting, water, heating and cooling, and ventilation required for construction purposes. Contractor is responsible for getting required permits and meters from the City of Tacoma.
- B. Existing facilities shall not be used.
- C. New permanent facilities shall not be used.
- D. Use trigger-operated nozzles for water hoses, to avoid waste of water.

### 1.03 TELECOMMUNICATIONS SERVICES

- A. Provide, maintain, and pay for telecommunications services for field personnel at time of project mobilization. It is the Contractor's responsibility to be able to receive phone calls and emails at the job site.

### 1.04 TEMPORARY SANITARY FACILITIES

- A. Provide and maintain required facilities and enclosures, as needed, at time of project mobilization.
- B. Maintain daily in clean and sanitary condition.
- C. At end of construction, return facilities to same or better condition as originally found.

### 1.05 BARRIERS

- A. Provide barriers to prevent unauthorized entry to construction areas, to prevent access to areas that could be hazardous to workers or the public, to allow for Port's use of site, and to protect existing facilities and adjacent properties from damage from construction operations and demolition.
- B. Provide barricades and covered walkways required by governing authorities for public rights-of-way and for public access to existing building.
- C. Protect non-owned vehicular traffic, stored materials, site, and structures from damage.

### 1.06 FENCING

- A. Construction: Contractor's option.
- B. Provide 6 ft. (1.8 m) high fence around construction site; equip with vehicular gates with locks.

### 1.07 EXTERIOR ENCLOSURES

- A. Provide temporary insulated weather tight closure of exterior openings to accommodate acceptable working conditions and protection for Products, to allow for temporary heating and maintenance of required ambient temperatures identified in individual specification sections, and to prevent entry of unauthorized persons. Provide access doors with self-closing hardware and locks.

### 1.08 TREE AND VEGETATION PROTECTION

- A. The Contractor shall carefully protect existing trees and vegetation noted to remain from damage by construction activities.
- B. All trees and vegetation noted to remain shall have 4' high, high visibility fence installed at the drip line of the tree or vegetation or as noted and shown on the Drawings.
- C. If a tree or vegetation designated for protection is damaged or destroyed in the course of the Work, the Contractor shall replace it with new comparable in species and size as required by the Engineer. Where it is necessary to replace trees or vegetation damaged by construction, the Contractor shall bear all expenses associated with replacement and establishment of the replacement vegetation.
- D. The contractor shall provide any necessary irrigation and other care necessary to warrant the replacement vegetation for two growing seasons (April through September) following replacement.

### 1.09 REMOVAL OF UTILITIES, FACILITIES, AND CONTROLS

- A. Remove temporary utilities, equipment, facilities, materials, prior to start of inspection.
- B. Clean and repair damage caused by installation or use of temporary work.
- C. Restore existing facilities used during construction to original condition.
- D. Restore new permanent facilities used during construction to specified condition.

### **PART 2 - PRODUCTS - NOT USED**

### **PART 3 - EXECUTION - NOT USED**

**END OF SECTION**

## **PART 1 - GENERAL**

### 1.01 SUMMARY

- A. This section includes requirements relating to the following:
  - 1. Access roads
  - 2. Parking
  - 3. Construction parking controls
  - 4. Traffic Control
  - 5. Flares and lights
  - 6. Haul routes
  - 7. Maintenance
  - 8. Removal, repair
  - 9. Mud from site vehicles

## **PART 2 - PRODUCTS**

### 2.01 SIGNS, SIGNALS, AND DEVICES

- A. Post Mounted and Wall Mounted Traffic Control and Informational Signs, as specified.
- B. Traffic Cones and Drums, Flares and Lights: As approved by local jurisdictions.
- C. Flag Person Equipment: As required by local jurisdictions.

## **PART 3 - EXECUTION**

### 3.01 PREPARATION

- A. Clear areas, provide surface and storm drainage of road, parking, area premises, and adjacent areas.

### 3.02 ACCESS TO SITE

- A. Contractor shall conduct all business through the gate assigned by the Engineer.
  - 1. The Contractor may be required to relocate entry and related work areas as required by Port Operations.
- B. Provide unimpeded access for emergency vehicles. Maintain 20 foot (6 m) width driveways with turning space between and around combustible materials.
- C. Provide and maintain access to fire hydrants free of obstructions.

### 3.03 PARKING

- A. Arrange for temporary parking areas to accommodate need of construction personnel.

### 3.04 CONSTRUCTION PARKING CONTROL

- A. Control vehicular parking to prevent interference with public traffic and parking, access by emergency vehicles, and Port operations.
- B. Prevent parking on or adjacent to access roads or in non-designated areas.

### 3.05 TRAFFIC CONTROL

- A. Provide trained and equipped flag persons to regulate traffic when construction operations or traffic encroach on public traffic lanes.
- B. The Contractor shall erect and maintain all construction signs, warning signs, detour signs, flaggers and other traffic control devices necessary for the safe ingress and egress of the Project Site. Traffic control shall include but is not limited to:
  - 1. Flaggers to direct traffic as required by Tacoma Rail to accommodate the Contractor's work.
  - 2. The Contractor shall be liable for injuries and damages to persons and property suffered by reason of the Contractor's operations or any negligence in connection therewith.
  - 3. Flagging, signs, and all other traffic control devices furnished or provided shall conform to established WSDOT and City of Tacoma standards. No work shall be done on or adjacent to the above locations until all necessary signs and traffic control devices are in place. During the course of the work, the Contractor shall be responsible for providing and maintaining adequate traffic control measures for the protection of the Contractor's work and the public.

### 3.06 FLARES AND LIGHTS

- A. Use flares and lights during hours of low visibility to delineate traffic lanes and to guide traffic.

### 3.07 HAUL ROUTES

- A. Confine construction traffic to designated haul routes.
- B. Provide traffic control at critical areas of haul routes to regulate traffic, to minimize interference with public traffic.

### 3.08 MAINTENANCE

- A. Maintain traffic and parking areas in a sound condition free of excavated material, construction equipment, Products, mud, snow, and ice.
- B. Maintain existing paved areas used for construction. Promptly repair breaks, potholes, low areas, standing water, and other deficiencies, to maintain paving and drainage in original, or specified, condition.

### 3.09 REMOVAL, REPAIR

- A. Repair existing facilities damaged by use, to original condition.
- B. Repair damage caused by installation.

### 3.10 PUBLIC STREET AND ONSITE ROADWAY CLEANING

- A. The Contractor shall be responsible for preventing dirt and dust escaping from trucks and other vehicles operating on or departing the project site by sweeping, covering dusty loads, washing truck tires, and all other reasonable methods.
- B. When trucks and other equipment are operating on paved public streets and site roadways/paved surfaces, the Contractor will be required to clean said streets, roadways, and other paved surfaces at least daily, and at other times if required by the Engineer.

- C. In the event that the above requirements are violated and no action is taken by the Contractor after notification of infraction by the Engineer, the Port reserves the right to have the streets, roadways, and other paved surfaces in question cleaned by others and have the expense of the operation charged to the Contractor.

**END OF SECTION**

This page intentionally left blank

## **PART 1 – GENERAL**

### **1.01 SUMMARY**

- A. The Work shall consist of planning, installing, inspecting, maintaining and removing Temporary Erosion and Sediment Control (TESC) Best Management Practices (BMPs) to prevent pollution of air and water; and to control, respond to, and dispose of eroded sediment and turbid water during the term of the Contract.
- B. The Contractor shall use a project-specific Construction Stormwater Pollution Prevention Plan ("SWPPP") to meet or exceed the control measures required by the Washington Department of Ecology (Ecology). The SWPPP describes the proposed construction activities and all Temporary and Permanent Erosion and Sediment Control (ESC) measures, pollution prevention measures, inspection/monitoring activities, and recordkeeping that will be implemented during the proposed construction project. The Contractor shall have an individual who is a Certified Erosion and Sediment Control Lead (CESCL) on site or immediately available while the NPDES permit is active.
  - 1. The SWPPP consists of planning, installing, inspecting, maintaining, and removing TESC BMPs in accordance with Volume II of the Stormwater Management Manual for Western Washington (current version). The BMPs are designed to prevent pollution of air and water, to control peak volumetric flow rates and velocity of stormwater, and to control, respond to, and dispose of eroded sediment and turbid water during the term of the Contract.
  - 2. The Contractor will be responsible for updating the SWPPP to reflect changes to BMPs, as needed, to comply with the Construction Stormwater General Permit at no additional cost to the Port.
- C. These TESC requirements shall apply to all areas associated with the Work, including but not limited to the following:
  - 1. Work areas;
  - 2. Equipment and material storage areas;
  - 3. Staging areas;
  - 4. Stockpiles; and
  - 5. All discharge points within or adjacent to the Work areas that receive stormwater runoff from the site.
- D. Acceptance of TESC plans shall not constitute an approval of permanent Work or drainage design (e.g., size and location of roads, pipes, restrictors, channels, retention facilities, utilities, etc.).
- E. Contractor shall read and conform to all requirements set forth in Washington Department of Ecology's (Ecology) NPDES General Permit for Discharges Associated with Construction Activities (CSGP).

### **1.02 REFERENCES**

- A. The rules, requirements, and regulations that apply to this Work include, but are not necessarily limited to the following:
  - 1. Washington Department of Ecology, "Stormwater Management Manual for Western Washington," current version.

2. Washington Department of Ecology NPDES General Permit for Discharges Associated with Construction Activities (CSGP), current version.
3. Washington State Department of Transportation, current version, Standard Specification M41-10, Division 8-01 Erosion Control and Water Pollution Control.
4. Pierce County Stormwater and Site Development Manual, current version (if applicable).
5. City of Tacoma, "Surface Water Management Manual," Tacoma Public Works, Environmental Services, current version.
6. Administrative Order #\_XXXXX\_, Department of Ecology, current version (if applicable).

### 1.03 SUBMITTALS

- A. Prior to the start of any construction activities, the Contractor shall submit a Construction Stormwater Pollution Prevention Plan (SWPPP), as required by the CSGP.
  1. Contractor must adopt and comply with either a Port project SWPPP, or provide an alternative project SWPPP.
  2. Contractor shall be responsible for updating the project SWPPP during construction to reflect the required changes to BMPs and personnel, as needed, to comply with the CSGP at no additional cost to the Port.
- B. A Construction Stormwater Pollution Prevention Plan (SWPPP) per the requirements in Part 3.02 of this section;
  1. Copies of the updated SWPPP for each task order, including all additional TESC BMPs, as needed.
- C. Safety Data Sheet (SDS) for any dust palliative product.
- D. A copy of all Contractor site inspection logs and monthly Discharge Monitoring Reports (DMRs).
- E. The name and contact number of the Certified Erosion and Sediment Control Lead (CESCL).

### 1.04 AUTHORITY OF ENGINEER

- A. The Engineer has the authority to limit the surface area of erodible earth material exposed by clearing and grubbing, excavation, borrow and fill operations, based on observed Site conditions; and to direct the Contractor to provide immediate permanent or temporary pollution control measures to minimize impacts to adjacent streams or other watercourses, lakes, ponds, and other areas of water impoundment.
- B. In the event that areas adjacent to the work area are suffering degradation due to erosion, sediment deposit, water flows, or other causes, the Engineer may stop construction activities until the Contractor rectifies the situation.

## **PART 2 – PRODUCTS**

### 2.01 DUST CONTROL

- A. Dust palliative for dust control proposed by the Contractor and approved by the Engineer.

## **PART 3 – EXECUTION**

### **3.01 GENERAL**

- A. The Port is subject to a NPDES General Permit for Discharges Associated with Construction Activities (CSGP). The permit shall be transferred to the Contractor prior to ground disturbing activities. The Contractor shall be the responsible Operator and Permittee for the duration of the project.
- B. In the event of conflict between these requirements and pollution control laws, rules, or regulations of other federal, state, or local agencies, the more restrictive laws, rules, or regulations shall apply as determined by the Engineer.
- C. No project discharge of water shall be allowed that causes or contributes to an exceedance of regulated pollutant levels in Ecology's NPDES permit associated with the Project and any CSGP-associated Administrative Orders (if applicable).
- D. Contractor shall be solely responsible for all BMP modifications and upgrades to comply with the CSGP and the requirements of this Section, at no additional cost to the Port.
- E. Contractor shall be solely responsible for any damages and fines incurred because of Contractor, subcontractor, or supplier actions in implementing the requirements of this Section.
- F. The Contractor shall be solely responsible for schedule impacts incurred because of Contractor, subcontractor, or supplier actions in implementing the requirements of this Section.

### **3.02 TEMPORARY EROSION AND SEDIMENT CONTROL DEVELOPMENT**

- A. The Contractor is responsible for developing the TESC BMPs and incorporating them into the SWPPP. The Contractor shall address the following issues as part of developing and implementing the BMPs.
  - 1. The TESC notes and details shown in the Drawings and the information in this Section of these Specifications are minimum requirements for the anticipated site conditions during the construction period. During the construction period the Contractor shall, at no additional cost to the Port, upgrade the TESC measures as needed for unexpected storm events and modify these measures for changing site conditions (such as relocation of ditches and silt fences, etc.) and update the SWPPP to document the modifications made.
  - 2. The Contractor shall inspect the TESC measures daily and maintain these measures to ensure continued proper functioning during the construction period. The Contractor will keep written records on site of inspections on a weekly basis during the wet season (October 1 through April 30) and on a monthly basis during the dry season (May 1 through September 30). The Contractor shall provide the Port with copies of the TESC inspections, as stated in Section 1.03 above.
  - 3. Any areas needing TESC measures not requiring immediate attention shall be addressed by the Contractor at the Port's discretion.
  - 4. The TESC measures in an inactive site shall be inspected and maintained by the Contractor at a frequency described in the Project Construction Stormwater NPDES General Permit.
  - 5. The Contractor shall be responsible for implementing the SWPPP and shall modify the SWPPP as required to reflect on-site activities and personnel.
- B. Contractor shall develop project-specific TESC BMPs and incorporate them into the SWPPP.

1. The SWPPP shall comply with the requirements in Ecology's Volume II of the Stormwater Management Manual for Western Washington (current version) or equivalent.
  2. TESC notes and details shown in the Drawings and the information in this Section form a basis of the minimum requirements for a TESC Plan. Contractor shall develop a TESC Plan specific to the task order and proposed means and methods prior to commencing construction activities for the duration of the task order.
- C. Contractor shall inspect the existing system and report to the Engineer the levels of existing material prior to installation of TESC BMPs.

### 3.03 TEMPORARY EROSION AND SEDIMENT CONTROL IMPLEMENTATION

- A. Contractor is responsible for implementing and updating the SWPPP including TESC BMPs.
1. Contractor shall inspect the TESC measures daily and maintain these measures to ensure continued proper functioning for the duration of the task order.
  2. Contractor will be responsible for documenting TESC site inspections on a weekly basis in areas of active construction and on a monthly basis in areas that have undergone stabilization. Contractor shall keep records of the inspections on site.
  3. During the construction period the Contractor shall, at no additional cost to the Port, upgrade and/or maintain TESC measures as needed, based on Contractor means and methods, work sequencing, and changing site conditions (e.g., changes to impervious surface coverage, proximity of work to storm conveyance systems, storm events, etc.). Contractor shall modify these measures for changing site conditions and update the SWPPP to document all modifications made.
- B. Contractor shall clean all stormwater components affected by construction debris prior to the completion of each task order, per TESC BMPs for catch basin maintenance. The cleaning process shall not flush sediment-laden water into a downstream system.
- C. Contractor shall ensure that water, or a dust palliative and a dispensing subcontractor, if needed, is available for project use. It is the responsibility of the Contractor to develop and adhere to appropriate safety measures pertaining to the palliative use. This also includes ensuring the dispensing subcontractor develops and adheres to the appropriate safety measures, if a dispensing subcontractor is used. Water used for dust suppression shall not be applied at such a rate or in a location that it will generate runoff from the site.
- D. Areas of exposed soils, including embankments, which will not be disturbed for two days during the wet season (October 1 through April 30) or seven days during the dry season (May 1 through September 30), shall immediately be stabilized by the Contractor with an Ecology-approved TESC measure (e.g., seeding, mulching, plastic covering, etc.).
- E. TESC measures in an inactive area shall be inspected and maintained by the Contractor until the area is permanently stabilized.
- F. In the event that additional temporary erosion and pollution control measures are required due to the Contractor's negligence, carelessness, or failure to install permanent controls as a part of the Work as scheduled or as ordered by the Engineer, such work shall be performed by the Contractor at its own expense.
- G. Contractor shall remove all TESC facilities, install permanent site surfacing improvements and permanent BMPs with minimal disturbance, and shall clean stormwater facilities prior to Work completion.

- H. Contractor shall submit a Notice of Termination ("NOT") and terminate coverage under the CSGP upon final stabilization of the Site; in accordance with permit requirements.

**END OF SECTION**

This page intentionally left blank

## **PART 1 - GENERAL**

### 1.01 SUMMARY

- A. This section includes the requirements for preparing, submitting, and coordinating product data, shop drawings, and samples under the applicable specification section.

### 1.02 SUBMITTALS

- A. The Contractor shall submit the following in accordance with the Contract Documents:
  - 1. Product Data Submittals: Submit manufacturer's standard published data. Mark each copy to identify applicable products, models, options, and other data. Supplement manufacturers' standard data with information specific to the Project, including compatibility with adjacent Work where applicable.
  - 2. Shop Drawing Submittals: Prepared specifically for this Project; indicate dimensions, utility and electrical characteristics, utility connection requirements, and location of utility outlets for service for functional equipment and appliances.
  - 3. Sample Submittals: Illustrate functional and aesthetic characteristics of the product, with integral parts and attachment devices. Coordinate sample submittals for interfacing work.
    - a. For selection from standard finishes, submit samples of the full range of the manufacturer's standard colors, textures, and patterns; unless otherwise approved by the Engineer.

## **PART 2 - PRODUCTS**

### 2.01 NEW PRODUCTS

- A. Provide new, unused products unless specifically required or permitted by the Contract Documents.

### 2.02 PRODUCT OPTIONS

- A. Products Specified by Reference Standards or by Description Only: Use any product meeting those standards or description.
- B. Products Specified by Naming One or More Manufacturers: Use a product of one of the manufacturers named and meeting specifications, no options or substitutions allowed.
- C. Products Specified by Naming One or More Manufacturers with a Provision for Substitutions: Submit a request for substitution for any manufacturer not named.

## **PART 3 - EXECUTION**

### 3.01 TRANSPORTATION AND HANDLING

- A. Coordinate schedule of product delivery to designated prepared areas to minimize on-Site storage time, double handling, and potential damage to stored materials.
- B. Transport and handle products in accordance with manufacturer's instructions.
- C. Transport materials in covered trucks to prevent contamination of product and littering of surrounding areas.
- D. Promptly inspect shipments to ensure that products comply with requirements, quantities are correct, and products are undamaged.

- E. Provide equipment and personnel to handle products by methods to prevent soiling, disfigurement, or damage.
- F. Arrange for the return of packing materials, such as wood pallets, where economically feasible.

### 3.02 STORAGE AND PROTECTION

- A. Designate receiving/storage areas for incoming products so that they are delivered according to installation schedule and placed convenient to work area to minimize waste, excessive handling, and misapplication.
- B. Store and protect products in accordance with manufacturers' written instructions and the requirements of the contract documents.
- C. Store with seals and labels intact and legible.
- D. Store sensitive products in weather tight, climate controlled, enclosures in an environment favorable to product.
- E. For exterior storage of fabricated products, place on sloped supports above ground.
- F. Cover products subject to deterioration with impervious sheet covering. Provide ventilation to prevent condensation and degradation of products.
- G. Prevent contact with material that may cause corrosion, discoloration, or staining.
- H. Provide equipment and personnel to store products by methods to prevent soiling, disfigurement, or damage.
- I. Arrange storage of products to permit access for inspection. Periodically inspect stored products to verify products are undamaged and are maintained in acceptable condition.

**END OF SECTION**

## **PART 1 - GENERAL**

### 1.01 SUMMARY

- A. This section includes information on warranty, operation and maintenance manuals, and as built documentation.
- B. Prior to requesting final inspection, the Contractor shall assure itself that the project is complete in all aspects.

## **PART 2 - PRODUCTS**

### 2.01 WARRANTY

- A. The Contractor warrants the labor, materials and equipment delivered under the contract to be free from defects in design, material, or workmanship, and against damage caused prior to final inspection. Unless otherwise specified, this warranty extends for a period of one (1) year from the date of Substantial Completion.
- B. The Contractor shall promptly (within 48-hours) repair or replace all defective or damaged items delivered under the contract. The Contractor will haul away all defective or damaged items prior to Substantial Completion.
- C. In the event of equipment failure, during such time or in such a location that immediate repairs are mandatory, the Contractor shall respond promptly, irrespective of time. If the Contractor is not available, the Port will effect repairs. The Contractor shall then reimburse the Port for parts and labor necessary to correct deficiencies as defined within the warranty clause and time.

### 2.02 OPERATION AND MAINTENANCE MANUALS

- A. The following information (minimum of 3 copies) shall be furnished for all items of equipment on the Project requiring operational and/or maintenance procedures and for any additional items indicated by the Engineer:
  - 1. Lubrication Information: This shall consist of the manufacturer's recommendations regarding the lubricants to be used and the lubrication schedule to be followed.
  - 2. Control Diagrams: Diagrams shall show internal and connection wiring and as-built wiring diagrams (where applicable).
  - 3. Start-up Procedures: These instructions consist of equipment manufacturer's recommendations for installation, adjustment, calibration, and troubleshooting.
  - 4. Operating Procedures: These instructions consist of the equipment manufacturer's recommended step-by-step procedures for starting, operating, stopping the equipment under specified modes of operation, and for long-term shut-down (moth-balling).
  - 5. Preventative Maintenance Procedures: These instructions consist of the equipment manufacturer's recommended steps and schedules for maintaining the equipment.
  - 6. Overhaul Instructions: These instructions consist of the manufacturer's directions for the disassembly, repair and reassembly of the equipment and any safety precautions that must be observed while performing the work.
  - 7. Parts List: This list consists of the generic title and identification number of each component part of the equipment. This list shall include weights of individual components of each item of equipment weighing over 100 pounds.

8. Spare Parts List: This list consists of the manufacturer's recommendations of number of parts which should be stored by the Port and any special storage precautions which may be required.
9. Exploded View: Exploded or cut views of equipment shall be provided if available as a standard item of the manufacturer's information. When exploded or cut views are not available, plan and section views shall be provided with detailed callouts.
10. Specific Information: Where items of information not included in the above list are required, they will be provided as described in the specifications for the equipment.
11. Complete identification, including model and serial numbers.
12. Submittal information, as specified in Section 013300 Submittal Procedures.
13. Warranty Information: This information consists of the name, address, and telephone number of the manufacturer's representative to be contacted for warranty, parts, or service information.
14. Maintenance information summaries shall be prepared on 8-1/2" x 11" paper and digital version (PDF format) on CD-ROM and shall contain the following information compiled from manufacturer's recommendations in the order shown.
  - a. Description or name of item of equipment
  - b. Asset number (to be provided at a later date)
  - c. Manufacturer
  - d. Name, address, and telephone number of local manufacturer's representative
  - e. Serial number (where applicable)
  - f. Equipment nameplate data
  - g. Recommended maintenance procedures:
    - 1) Description of procedures.
    - 2) Lubricant(s) or other materials required (where applicable), including type of lubricant, lubricant manufacturer, and specific compound.
    - 3) Additional information as required for proper maintenance.
  - h. Maintenance schedule, broken down into:
    - 1) Daily
    - 2) Weekly
    - 3) Monthly
    - 4) Quarterly
    - 5) Semi-Annually
    - 6) Annually
  - i. Recommended spare parts (where applicable)
  - j. Asset Number Information:
    - 1) Provide the following information in Excel spreadsheet format:

- (a) Asset Number (to be provided at a later date)
- (b) Description
- (c) Plan Sheet Number
- (d) Parcel Number
- (e) Vendor
- (f) Manufacturer
- (g) Model Year
- (h) Serial Number
- (i) Warranty - Start Date; Finish Date
- (j) Required Preventative Maintenance
- (k) Purchase Price
- (l) Make
- (m) Model
- (n) Fuel Used
- (o) Capacity

2) Asset Number Information will be required for the following items:

- (a) (a)

- 15. Provide video tapes, DVDs, and audio-visual training materials utilized in the manufacturer's instruction program for the Port.
- 16. All such information shall be organized by the Contractor into 3-inch, 3-post, expandable metal binders. The binders shall be sized for material approximately 8-1/2 by 11 inches, and the material in the binders shall not protrude beyond the covers. The binder(s) shall be divided with coversheets for each major item of equipment. The cover sheets shall be typewritten to indicate the name, type of equipment, and location(s) within the Project where installed. A neatly typewritten index shall be provided. The number of copies of such binders to be submitted shall be equal to the total of the Contractor's requirements plus five (5) paper copies and an electronic copy in PDF format to be retained by the Port.
- 17. All operation and maintenance information shall be comprehensive and detailed and shall contain information adequately covering all normal operation and maintenance procedures.
- 18. All information shall be specific for the items of equipment installed on the project. Material not directly applicable shall be removed, omitted, or clearly marked as inapplicable.
- 19. Lubricants shall be described in detail, including type, recommended manufacturer, and manufacturer's specific compound to be used.
- 20. If manufacturer's standard brochures and manuals are used to describe operating and maintenance procedures, such brochures and manuals shall be modified to reflect only the model or series of equipment used on this project.

21. Extraneous material shall be crossed out neatly or otherwise annotated or eliminated. It shall be the responsibility of the Contractor to ensure that all operation and maintenance materials are obtained. Material submitted must meet the approval of the Engineer prior to project acceptance.

### **PART 3 - EXECUTION**

#### **3.01 FINAL DOCUMENTS**

##### **A. Project As-Built Drawings**

1. Project As-Built Drawings shall be compiled by the Contractor and submitted to the Engineer for translation to the Record Drawings on a monthly basis.
2. The Project As-Built Drawings will be submitted on paper full-sized (ANSI D) copy.
3. Drawings shall be kept current and shall be done at the time the material and equipment is installed. Annotations to the record documents shall be made with an erasable colored pencil conforming to the following color code:
  - a. Additions - Red
  - b. Deletions - Green
  - c. Comments - Blue
  - d. Dimensions - Graphite
4. Project As-Built Drawings must be complete and accepted by the Engineer before Final Completion is issued.
5. As-Built Drawings shall be in accordance with horizontal and vertical control as shown on the drawings.

##### **B. Final Survey**

1. See Section 01 71 23 Field Engineering for Final Survey requirements. The Final Survey shall be completed and submitted to the Engineer within 30 days of Substantial Completion. Final Survey must be complete and accepted by the Engineer before Final Completion is issued.

##### **C. The following Certificates shall be submitted by the Contractor prior to Final Completion:**

1. Certificates of Conformance
  - a. Notice of Termination (NOT) Construction Stormwater General Permit: (Confirmation of Termination request acceptance by DOE).

#### **3.02 CLEAN-UP**

- A. Definition: Except as otherwise specifically provided, "clean" (for the purpose of this Article) shall be interpreted as meaning the level of cleanliness generally provided by commercial building maintenance subcontractors using commercial quality building maintenance equipment and materials.
- B. General: Prior to completion of the work, remove from the job site all tools, surplus materials, equipment, scrap, debris, and waste. Conduct final progress cleaning as described above.
- C. Site: Unless otherwise specifically directed by the Engineer, hose down all paved areas on the site, all public sidewalks and catch basins on adjoining streets. Completely remove all resultant debris.

D. Structure:

1. Exterior: Visually inspect all exterior surfaces and remove all traces of soil, waste material, smudges, and other foreign matter. Remove all traces of splashed materials from adjacent surfaces. If necessary to achieve a uniform degree of exterior cleanliness, hose down the exterior or the structure. In the even of stubborn stains not removable with water, the Engineer may require light sandblasting or other cleaning at no additional cost to the Port.
  2. Interior: Visually inspect all interior surfaces and remove all traces of soil, waste material, smudges, and other foreign matter. Remove all traces of splashed materials from adjacent surfaces. Remove all paint droppings, spots, stains, and dirt from finished surfaces. Use only the specified cleaning materials and equipment.
  3. Clean all glass inside and outside.
  4. Polished Surfaces: To all surfaces requiring the routine application of buffed polish, apply the specified polish as recommended by the manufacturer of the material being polished.
- E. Timing: Schedule final cleaning as approved by the Engineer to enable the Port to occupy a completely clean project.

**END OF SECTION**

This page intentionally left blank

## **PART 1 - GENERAL**

### 1.01 SUMMARY

- A. This section includes requirements relating to the following:
  - 1. Examination, preparation, and general installation procedures
  - 2. Cutting and patching

### 1.02 SUBMITTALS

- A. Cutting and Patching: Submit written request in advance of cutting or alteration that affects:
  - 1. Structural integrity of any element of Project;
  - 2. Integrity of weather exposed or moisture resistant element;
  - 3. Efficiency, maintenance, or safety of any operational element;
  - 4. Visual qualities of sight exposed elements; and
  - 5. Work of the Port or separate Contractor.
- B. Project As-Built Documents: Accurately record actual locations of capped and active utilities.

## **PART 2 - PRODUCTS**

### 2.01 PATCHING MATERIALS

- A. New Materials: As specified in product sections; match existing products and work for patching and extending work.
- B. Type and Quality of Existing Products: Determine by inspecting and testing products where necessary, referring to existing work as a standard.

## **PART 3 - EXECUTION**

### 3.01 EXAMINATION

- A. Verify that existing site conditions and substrate surfaces are acceptable for subsequent work. Start of work means acceptance of existing conditions.
- B. Verify that existing substrate is capable of structural support or attachment of new work being applied or attached.
- C. Examine and verify specific conditions described in individual specification sections.
- D. Take field measurements before confirming product orders or beginning fabrication, to minimize waste due to over-ordering or misfabrication.
- E. Verify that utility services are available, of the correct characteristics, and in the correct locations.
- F. Prior to Cutting: Examine existing conditions prior to commencing work, including elements subject to damage or movement during cutting and patching. After uncovering existing work, assess conditions affecting performance of work. Beginning of cutting or patching means acceptance of existing conditions.

### 3.02 PREPARATION

- A. Clean substrate surfaces prior to applying next material or substance.
- B. Seal cracks or openings of substrate prior to applying next material or substance.

- C. Apply manufacturer required or recommended substrate primer, sealer, or conditioner prior to applying any new material or substance in contact or bond.

### 3.03 GENERAL INSTALLATION REQUIREMENTS

- A. Install products as specified in individual sections, in accordance with manufacturer's instructions and recommendations, and so as to avoid waste due to necessity for replacement.
- B. Make vertical elements plumb and horizontal elements level, unless otherwise indicated.
- C. Install equipment and fittings plumb and level, neatly aligned with adjacent vertical and horizontal lines, unless otherwise indicated.
- D. Make consistent texture on surfaces, with seamless transitions, unless otherwise indicated.
- E. Make neat transitions between different surfaces, maintaining texture and appearance.

### 3.04 CUTTING AND PATCHING

- A. Whenever possible, execute the work by methods that avoid cutting or patching.
- B. Perform whatever cutting and patching is necessary to:
  - 1. Complete the work;
  - 2. Fit products together to integrate with other work;
  - 3. Provide openings for penetration of mechanical, electrical, and other services;
  - 4. Match work that has been cut to adjacent work;
  - 5. Repair areas adjacent to cuts to required condition;
  - 6. Repair new work damaged by subsequent work;
  - 7. Remove samples of installed work for testing when requested; and
  - 8. Remove and replace defective and non-conforming work.
- C. Execute work by methods that avoid damage to other work and that will provide appropriate surfaces to receive patching and finishing. In existing work, minimize damage and restore to original condition.
- D. Employ original installer to perform cutting for weather exposed and moisture resistant elements, and sight exposed surfaces.
- E. Cut rigid materials using masonry saw or core drill. Pneumatic tools not allowed without prior approval.
- F. Restore work with new products in accordance with requirements of Contract Documents.
- G. Patching:
  - 1. Finish patched surfaces to match finish that existed prior to patching. On continuous surfaces, refinish to nearest intersection or natural break. For an assembly, refinish entire unit.
  - 2. Match color, texture, and appearance.
  - 3. Repair patched surfaces that are damaged, lifted, discolored, or showing other imperfections due to patching work. If defects are due to condition of substrate, repair substrate prior to repairing finish.

### 3.05 PROTECTION OF INSTALLED WORK

- A. Protect installed work from damage by construction operations.
- B. Provide special protection where specified in individual specification sections.
- C. Provide temporary and removable protection for installed products. Control activity in immediate work area to prevent damage.
- D. Provide protective coverings at walls, projections, jambs, sills, and soffits of openings.
- E. Protect finished floors, stairs, and other surfaces from traffic, dirt, wear, damage, or movement of heavy objects, by protecting with durable sheet materials.
- F. Prohibit traffic or storage upon waterproofed or roofed surfaces. If traffic or activity is necessary, obtain recommendations for protection from waterproofing or roofing material manufacturer.
- G. Remove protective coverings when no longer needed; reuse or recycle plastic coverings if possible.

### 3.06 ADJUSTING

- A. Adjust operating products and equipment to ensure smooth and unhindered operation.

**END OF SECTION**

This page intentionally left blank

## **PART 1 - GENERAL**

### 1.01 SUMMARY

- A. This section includes information for progress and final cleaning and restoration of damaged work prior to final inspection.

## **PART 2 - PRODUCTS**

### 2.01 MATERIALS

- A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

## **PART 3 - EXECUTION**

### 3.01 PROGRESS CLEAN-UP

- A. The Contractor shall clean the project site and work areas daily, including common areas. Enforce requirements strictly. Dispose of materials lawfully.
  - 1. Comply with all requirements for removal of combustible waste materials and debris.
  - 2. Do not hold waste materials more than seven days during normal weather or three days if the temperature is expected to rise above 80 deg F.
  - 3. Containerize unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.
    - a. Use containers intended for holding waste materials for the type of material to be stored.
  - 4. Coordinate progress cleaning for joint use areas where Contractor and other contractors are working concurrently.
- B. Site: Maintain Project site free from waste materials and debris.
- C. Work Areas: Clean areas where work is in progress to the level of cleanliness necessary for proper execution of the work.
  - 1. Remove liquid spills promptly.
  - 2. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire area, as appropriate.
- D. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.
- E. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.
- F. Exposed Surfaces in Finished Areas: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.
- G. Waste Disposal: Do not bury or burn waste materials on-site. Do not wash waste materials down sewers or into waterways. Comply with waste disposal requirements in Section \_\_\_\_\_.

- H. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration until Substantial Completion.
- I. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.
- J. Limiting Exposures: Supervise construction operations to assure that no part of the construction, completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

### 3.02 FINAL CLEANING

- A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.
- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
  - 1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a designated portion of Project:
    - a. Clean Project site, yard, and grounds in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.
    - b. Sweep paved areas broom clean. Remove spills, stains, and other foreign deposits.
    - c. Rake grounds that are neither planted nor paved to a smooth, even-textured surface.
    - d. Remove tools, construction equipment, machinery, and surplus material from Project site.
    - e. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances.
    - f. Remove debris and surface dust from limited access spaces, including roofs, attics, and similar spaces.
    - g. Sweep concrete floors broom clean in unoccupied spaces.
    - h. Remove labels that are not permanent.
    - i. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency.
    - j. Leave Project clean and ready for occupancy.

### 3.03 REPAIR OF WORK

- A. Complete repair and restoration operations before requesting inspection for determination of Substantial Completion.
- B. Repair or remove and replace defective construction. Repairing includes replacing defective parts, refinishing damaged surface, touching up with matching materials, and properly adjusting operating equipment. Where damaged or worn items cannot be repaired or restored, provide replacements. Remove and replace operating components that cannot be repaired. Restore damaged construction and permanent facilities used during construction to specified condition.

1. Touch up and otherwise repair and restore marred or exposed finishes and surfaces. Replace finishes and surfaces that already show evidence of repair or restoration.
  - a. Do not paint over "UL" and other required labels and identification, including mechanical and electrical nameplates. Remove paint applied to required labels and identification.
2. Replace parts subject to operating conditions during construction that may impede operation or reduce longevity.

**END OF SECTION**

This page intentionally left blank

## **PART 1 - GENERAL**

### 1.01 SUMMARY

- A. This section includes construction waste management requirements.

### 1.02 DESCRIPTION OF WORK

- A. The work includes demolition and removal within the project areas as shown on the drawings. The work also includes waste generated by construction activities, materials, packaging, scraps, and garbage.
- B. Soils excavated within the projects areas, as shown on the drawings, are anticipated to be free of contamination, however, should the Contractor, using visual and olfactory methods, identify potentially contaminated soil, the Contractor shall notify the Engineer to determine if the soil requires special handling. This material shall be segregated from other excavated material. It shall be stockpiled on plastic and covered with plastic until such time as appropriate testing and analysis can be completed by the Engineer. Upon completion of the testing and analysis the Engineer will direct the Contractor concerning the disposition of the material. Soil beyond construction excavation limits will not require excavation unless free draining product is observed or other special conditions exist in which case the Engineer will direct the Contractor in additional excavation. Soils determined to be contaminated will be hauled and disposed of at a locations designated in the following paragraphs.

### 1.03 DEFINITIONS

- A. Co-mingled or Off-site Separation: Collecting all material types into a single bin or mixed collection system and separating the waste materials into recyclable material types at an off-site facility.
- B. Construction, Demolition and Land-Clearing (CDL) Waste: Includes all nonhazardous solid wastes resulting from construction, remodeling, alterations, repair, demolition, and land clearing. Includes material that is recycled, reused, salvaged or disposed as garbage.
- C. Hazardous/Dangerous Waste: As defined by Chapter 70.105.010 Revised Code of Washington and 40 Code of Federal Register 261 and by Washington Administrative Code 173-303.
- D. Proper Disposal: As defined by the jurisdiction receiving the waste.
- E. Recyclable Materials: Products and materials that can be recovered and remanufactured into new products.
- F. Recycling: The process of sorting, cleaning, treating and reconstituting materials for the purpose of using the material in the manufacture of a new product. Can be conducted on-site (as in the grinding of concrete).
- G. Recycling Facility: An operation that is permitted to accept materials for the purpose of processing the materials into an altered form for the manufacture of a new product.
- H. Salvage for Reuse: Existing usable product or material that can be saved and reused in some manner on the project site or other projects off-site.
- I. Salvage for Resale: Existing usable product or material that can be saved and removed intact (as is) from the project site to another site for resale to others without remanufacturing.
- J. Source-Separated Materials: Materials that are sorted at the site into separate containers for the purpose of reuse or recycling.

- K. Sources Separation: Sorting the recovered materials into specific material types with no, or a minimum amount of, contamination on site.
- L. Time-Based Separation: Collecting waste during each phase of construction or deconstruction that results in primarily one major type of recovered material. The material is removed before it becomes mixed with the material from the next phase of construction.
- M. Garbage: Product or material typically considered to be trash or debris that is unable to be salvaged for resale, salvaged and reused, returned, or recycled.
- N. Olfactory Indications (methods): Of or relating to the sense of smell. Soils contaminated with petroleum and other volatile constituents typically exhibit characteristic odors that can be detected (and sometimes identified) by smell.
- O. PID: Photo Ionization Detector. A field instrument that is used to detect the presence of and give a relative indication of the concentration of vapors emitted from volatile constituents (contamination) in environmental media (soil and water).
- P. Soil (waste) Profile: A characterization of the chemical and physical properties of a waste material including the types of contaminants and their concentrations as measured by approved laboratory analytical methods. A profile is required by the receiving permitted disposal or recycling facility.
- Q. Special Handling: Refers to hauling and disposal of soils that, because they are contaminated, cannot be reused in place as backfill or as general fill at another location. Such soils must be hauled to and managed at a permitted disposal or recycling facility.
- R. Type A Contaminated Soil: Soil that must be removed from the Project site and has been determined by the Engineer to contain petroleum hydrocarbons in concentrations exceeding state or federal cleanup standards or special Port determined criteria. Type A soil requires disposal at an approved facility.
- S. Type B Contaminated Soil: Soil that must be removed from the Project site and has been determined by the Engineer to contain petroleum hydrocarbons or other contaminants in concentrations that will require disposal or recycling at one of the approved facility.
- T. Type C Contaminated Soil: Soil determined by Engineer to contain unknown constituent(s) and requires further testing and classification. Type C soil requires disposal at one of the approved facility.
- U. Type D Material: Material including soil, determined by the Engineer not to require special handling with regard to this Contract. Classification of material as Type D material by the Port is not a certification nor does it release the Contractor of liability or obligation to meet any disposal or storage facility acceptance or testing requirements.
- V. Unanticipated Contamination: Contamination unexpectedly found in an excavation or in other locations where there is no prior knowledge, information, or history to indicate possible spills or releases of contamination.
- W. Visual Indications (methods): A preliminary evaluation of the potential presence of contamination based on visual observation. For example, fuel contaminated soils are frequently discolored or stained relative to non-petroleum impacted native soils or clean fill.

#### 1.04 SUBMITTALS

- A. Waste Management Plan
  - B. Waste Management Final Report
-

- C. Soils Management Plan
- D. Soils Hauling Receipts

#### 1.05 PERFORMANCE GOALS

- A. General: Divert CDL waste to the maximum extent practicable from the landfill by one or a combination of the following activities:
  - 1. Salvage
  - 2. Reuse
  - 3. Source separated CDL recycling
  - 4. Co-mingled CDL recycling
- B. CDL waste materials that can be salvaged, resold, reused or recycled, include, but are not limited to the following:
  - 1. Clean dimensional wood, pallet wood, plywood, OSB, and particleboard
  - 2. Asphalt
  - 3. Concrete and concrete masonry units
  - 4. Ferrous and non-ferrous metals
  - 5. Field office waste paper, aluminum cans, glass, plastic, and cardboard
- C. Hazardous/Dangerous Wastes, contaminated soils and other hazardous materials such as paints, solvents, adhesives, batteries, and fluorescent light bulbs and ballasts shall be disposed of at applicable permitted facilities.

#### 1.06 WASTE MANAGEMENT PLAN

- A. Submit a Waste Management Plan within 10 days after the notice to proceed and not less than 5 days before any demolition activities in accordance with these specifications. Provide a Waste Management Plan in a format as approved by the Engineer.
- B. The Waste Management Plan shall include the following:
  - 1. Name of designated Waste Management Coordinator.
  - 2. A list of waste materials, including estimated types and quantities, of the waste that will be generated. Indicate salvaged for resale, salvaged for reuse, recycled, or disposed for each item.
  - 3. Identify waste handling methods to be used, including one or more of the following:
    - a. Method 1 - Contractor or subcontractor(s) hauls recyclable materials to an approved recycling facility.
    - b. Method 2 - Contracting with diversion/recycling hauler to haul recyclable material to an approved recycling or material recovery facility.
    - c. Method 3 - Recyclable material reuse on-site.
    - d. Method 4 - Recyclable material salvage for resale.
    - e. Method 5 - Contractor or subcontractor hauls waste to an approved disposal facility.

4. Identification of each recycling, disposal, or material recovery facility to be utilized, including name, address and types of materials being recycled at each facility.
  5. Description of the method to be employed in collecting, and handling, waste materials.
  6. Description of methods to communicate Waste Management Plan to personnel and subcontractors.
  7. Actions that will be taken to reduce solid waste generation.
- C. Revise and resubmit Waste Management plan as required by the Engineer. Approval of the Contractor's Plan does not relieve the Contractor of responsibility for compliance with all applicable laws and regulations. Distribute copies of the Waste Management Plan to each subcontractor.

#### 1.07 WASTE MANAGEMENT FINAL REPORT

- A. Provide a Waste Management Final Report, in a format approved by the Engineer. The Waste Management Final Report shall list the following for the project:
1. A record of each waste material type and quantity recycled, reused, salvaged, or disposed from the Project. Include total quantity of waste material removed from the site and hauled to a landfill.
  2. Percentage of total waste material generated that was recycled, reused, or salvaged.
- B. Quantities shall be reported by weight (tons) unless otherwise approved by the Engineer.
- C. Submit copies of manifests, weight tickets, recycling/disposal receipts or invoices, which validate the calculations or a signed certification of completeness and accuracy of the final quantities reported.

#### 1.08 SOILS MANAGEMENT PLAN

- A. A minimum of 10 days prior to excavation of any subsurface materials, submit a Soils Management Plan to the Engineer. The Soils Management Plan must be approved by the Engineer prior to any excavation of subsurface materials. Include the following in the Soils Management Plan:
1. Identification of all soil disposal/recycling facilities to be used on the project for Type A and B Contaminated Soil.
  2. Identification of all fill sites, disposal facilities and/or end uses of material determined to be Type D Material.
  3. Contingency for delivery and placement of Type C Contaminated Soil at an onsite Soil Stockpile area.
  4. Contingency for managing debris encountered during excavation that may disqualify soil for disposal or recycle at the approve facilities.
  5. General description of how equipment operators, safety personnel and other applicable Contractor shall coordinate with the Engineer to facilitate handling of contaminated soil in accordance with this specification.
  6. Description of all haul routes to be used on the project.
- B. Include in the Two Week Look Ahead Schedule specific time frames for excavation. Each excavation activity shall be given an individual line item description, time frame and duration.

- C. Notify the Engineer prior to hauling contaminated soil to the soil disposal facility. The notification shall include:
  - 1. An estimate of the number of truck-trips, the haul destination, and the period in which these trips will be made (e.g., 20 truck-trips to the Waste Management Facility over the two-week period beginning on March 1, 2012).

#### 1.09 QUALITY ASSURANCE

- A. Regulatory Requirements: The Contractor shall maintain compliance with all applicable Federal, State, or Local laws that apply to Construction Waste Management and material salvage, reuse, recycling and disposal.
- B. Disposal Sites, Recyclers and Waste Materials Processors: All facilities utilized for management of any materials covered under this specification must maintain all necessary permits as required by federal, state and local jurisdictions.

#### 1.10 HEALTH AND SAFETY

- A. The Contractor is required to implement all health and safety provisions as required by Specification 01 35 29 - Health, Safety and Emergency Response Procedures.

### **PART 2 - PRODUCTS - NOT USED**

### **PART 3 - EXECUTION**

#### 3.01 WASTE DISPOSAL

- A. Source-Separated CDL Recycling: Provide individual containers for separate types of CDL waste to be recycled, clearly labeled with a list of acceptable and unacceptable materials.
- B. Co-Mingled CDL Recycling: Provide containers for co-mingled CDL waste to be recycled, clearly labeled with a list of acceptable and unacceptable materials.
- C. Landfill: Provide containers for CDL waste that is to be disposed of in a landfill clearly labeled as such.
- D. Removal of CDL Waste from Project Site: Transport CDL waste off Port's property and provide legal disposal.

#### 3.02 SOIL DISPOSAL

- A. Excavation/Testing: The field-testing for contaminated soil will be performed by the Port and will result in the following classification of material as defined in paragraph DEFINITIONS of this section:
  - 1. Type A Contaminated Soil.
  - 2. Type B Contaminated Soil.
  - 3. Type C Contaminated Soil.
  - 4. Type D Material.
- B. Disposition of Material
  - 1. Type A and B Contaminated Soil: Material determined to be Type A or B Contaminated Soil shall be hauled by the Contractor to an approved facility for disposal.

2. Type C Material: Material determined to be Type C is of unknown origin or special circumstances. Material determined to be Type C contaminated soils shall be hauled to an onsite Soil Stockpile Site area. The Contractor shall protect the material once stockpiled. The Port will direct the Contractor on the disposition of the material following the analysis of the suspect material.
3. Type D Material: Material determined not to require special handling (Type D) shall be hauled by the Contractor to a site determined by the Contractor. If testing or certification of this material is required by the receiving site, the Contractor shall complete these requirements. The Port will not certify or declare the material suitable for unrestricted use.

C. Other Requirements

1. Cover all soil stockpiles and maintain stockpile areas in accordance with SECTION 01 57 13 - Temporary Erosion and Sediment Control and Construction Stormwater Pollution Prevention.
2. Material determined to be Type A, Type B or Type C contaminated material may be, upon approval of the Engineer, temporarily stockpiled within the construction area. Provide an impervious liner beneath this soil and securely cover with a waterproof covering. Remove the material prior to completion of work in the work area.
3. Submit all hauling receipts (or copies of receipts) from the receiving facility for all Type A, Type B or Type C Contaminated soil at least weekly.
4. The Engineer may require shut down of excavation should unforeseen condition warrant.

**END OF SECTION**

## **PART 1 - GENERAL**

### 1.01 SUMMARY

- A. Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
  - 1. Substantial Completion procedures
  - 2. Final completion procedures
  - 3. Warranties
  - 4. As-Built Drawings

### 1.02 ACTION SUBMITTALS

- A. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.

### 1.03 PROJECT SUBMITTALS

- A. Submittal of Project Warranties
- B. Record Drawings
  - 1. Miscellaneous Record Submittals: See other Specification Sections for miscellaneous recordkeeping requirements and submittals in connection with various construction activities.
- C. Schedule of Maintenance Material Items: For maintenance material submittal items specified in other Sections.

### 1.04 SUBSTANTIAL COMPLETION PROCEDURES

- A. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected.
- B. Submittals Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request:
  - 1. Certificates of Release: Obtain and submit releases from authorities having jurisdiction permitting Port unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
  - 2. Submit closeout submittals specified in individual Sections, including specific warranties, operation and maintenance manuals, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
  - 3. Submit maintenance material submittals specified in individual Sections, including tools, spare parts, extra materials, and similar items, and deliver to location designated by the Contract Document or Engineer. Label with manufacturer's name and model number where applicable.
  - 4. Submit test/adjust/balance records.
  - 5. Submit changeover information related to Port's occupancy, use, operation, and maintenance.

- C. Procedures Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request:
  - 1. Make final changeover of permanent locks and deliver keys to Port
  - 2. Complete startup and testing of systems and equipment
  - 3. Perform preventive maintenance on equipment used prior to Substantial Completion
  - 4. Instruct Port's personnel in operation, adjustment, and maintenance of products, equipment, and systems
  - 5. Advise Port of changeover in heat and other utilities
  - 6. Terminate and remove temporary facilities from Project site
  - 7. Complete final cleaning requirements
- D. Submit a written request for inspection to determine Substantial Completion a minimum of DD days prior to the date the work will be completed and ready for final inspection and tests. On receipt of request, Engineer will either proceed with inspection or notify Contractor of unfulfilled requirements. Engineer will prepare the Notice of Substantial Completion after inspection or will notify Contractor of items, either on the Contractor's list or additional items identified by the Engineer, that must be completed or corrected before notice will be issued.
  - 1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
  - 2. Results of completed inspection will form the basis of requirements for final completion.

#### 1.05 PUNCH LIST (LIST OF INCOMPLETE ITEMS)

- A. Organization of List: Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of Construction.
  - 1. Organize list of spaces in sequential order.
  - 2. Organize items applying to each space by major elements.

#### 1.06 FINAL COMPLETION PROCEDURES

- A. Submittals Prior to Final Completion: Before requesting final inspection for determining final completion, complete and submit the following:
  - 1. Submittal of all remaining items, including as-built documents, final completion construction photographic documentation, damage or settlement surveys, surveys, and similar final record information and all other submittals defined in the Contract Documents.
  - 2. List of Incomplete Items: Submit copy of Engineer's Substantial Completion inspection list of items to be completed or corrected (Punch List). Copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
- B. Inspection: Submit a written request for final inspection to determine acceptance a minimum of 14 days prior to date the work will be complete and ready for final inspection and tests. On receipt of request, the Engineer will either proceed with inspection or notify contractor of unfulfilled requirements.

1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

C. Execution of all Change Orders.

#### 1.07 FINAL ACCEPTANCE PROCEDURES

A. Submittals Prior to Final Acceptance:

1. Receipt and approval of application for final payment; due within seven (7) days of receipt of Final Completion by the Engineer;
2. Contractor's signed waiver and release of claims on the Engineer provided form;
3. Contractor's submittal of list of all suppliers and subcontractors and the total amounts paid to each on the Engineer provided form; and
4. Contractor's submittal of a list of all subcontractors and suppliers requiring Affidavits of Wages paid on the Contract and certify that each of companies will submit an approved Affidavit of Wages paid to the Port within 30 days.

B. The Engineer will issue the Final Acceptance Memo upon receipt of the required submittals.

### **PART 2 - PRODUCTS**

#### 2.01 CONTRACTOR'S WARRANTY

- A. The Contractor warrants the labor, materials and equipment delivered under the contract to be free from defects in design, material, or workmanship, and against damage caused prior to final inspection. Unless otherwise specified, this warranty extends for a period of one (1) year from the date of Substantial Completion.
1. Time of Submittal: Submit written warranties on request of Engineer for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated, or when delay in submittal of warranties might limit the Port's rights under warranty.
  2. Partial Occupancy: Submit properly executed warranties within 15 days of completion of designated portions of the Work that are completed and occupied or used by Port or Port tenants during construction.
  3. Submit Warranties to the Engineer as a submittal, as described in 01 33 00 – Submittal Procedures.
  4. Provide additional copies of each warranty in Operation and Maintenance Manuals as described in 01 78 23 – Operation and Maintenance Manuals.
- B. In the event of equipment failure, during such time or in such a location that immediate repairs are mandatory, the Contractor shall respond promptly (within 48 hours), irrespective of day of the week. If the Contractor is not available, the Port will affect repairs. The Contractor shall then reimburse the Port for parts and labor necessary to correct deficiencies as defined within the warranty clause and time.

#### 2.02 AS-BUILT DRAWINGS

- A. Project As-Built Drawings: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised drawings as modifications are issued.

- B. Project As-Built Drawings shall be compiled by the Contractor and submitted to the Engineer for translation to the Record Drawings on a monthly basis.
  - 1. The Project As-Built Drawings will be submitted on paper full-sized (ANSI D) copy.
  - 2. Drawings shall be kept current and shall be done at the time the material and equipment is installed. Annotations to the record documents shall be made with an erasable colored pencil conforming to the following color code:
    - a. Additions – Red
    - b. Deletions – Green
    - c. Comments – Blue
    - d. Dimensions – Graphite
  - 3. Project As-Built Drawings must be complete and accepted by the Engineer before Final Completion is issued.
  - 4. As-Built Drawings shall be in accordance with horizontal and vertical control as shown on the drawings.

### **PART 3 – EXECUTION**

#### **3.01 MAINTENANCE OF AS-BUILT DRAWINGS**

- A. The Contractor shall maintain at the Project site, in good order for ready reference by the Engineer, one complete copy of the Contract Documents, including Addenda, Change Orders, other documents issued by the Port, a current Progress Schedule, and approved Submittals. The Contractor shall also generate and keep on site all documents and reports required by applicable permits.
- B. The Contractor's As-Built Drawings shall be updated to record all changes made during construction. The location of all existing or new underground piping, valves and utilities, and obstructions located during the Work shall be appropriately marked until the Contractor incorporates the actual field dimensions and coordinates into the as-built drawings. The as-built drawings shall be updated at least weekly and before elements of the Work are covered or hidden from view. After the completion of the Work, the as-built drawings shall be provided to the Port.

**END OF SECTION**

## **PART 1 - GENERAL**

### 1.01 SECTION INCLUDES

- A. Sawcut and remove existing asphalt and concrete pavement and items.
- B. Cold mill asphalt concrete pavement.
- C. Remove miscellaneous items as specified.
- D. Salvage, disposal, storage and handling of removed items.
- E. Restoration of site after demolition.

### 1.02 DESCRIPTION OF WORK

- A. The extent and location of the Work is indicated on the Task Order and shall be in conformance with these specifications and to the dimensions indicated on the Task Order.

### 1.03 RELATED SECTIONS

- A. Section 03 30 00 – Cast-in-Place Concrete
- B. Section 31 00 00 – Earthwork

### 1.04 DEMOLITION

- A. The Contractor assumes full responsibility for the proper disposal of all demolition materials.

### 1.05 SALVAGE

- A. Remove, as a unit, items designated for salvage. Clean and tag for storage. Protect from damage and deliver to location designated by Engineer.

### 1.06 QUALITY ASSURANCE

- A. Maintain in satisfactory working condition equipment, tools and machines used in the performance of the work.

## **PART 2 - PRODUCTS**

### 2.01 GENERAL

- A. Products that are required to accomplish, or to be incorporated into, the work of this section are as selected by the Contractor.

## **PART 3 - EXECUTION**

### 3.01 GENERAL

- A. Notify the Engineer in writing a minimum of two (2) days prior to beginning work.
- B. Obtain approval from the Engineer and authorities having jurisdiction for work which affects means of ingress and egress from work area including Tacoma Public Works, Tacoma Fire Department and Tacoma Rail. Review with and obtain approval of authorities for temporary construction which affects work area.
- C. The construction area shall be discussed with the Engineer and tenant to determine the allowable footprint of each area of work and any barricading and safety light requirements.
- D. Damaged items that are to remain in place shall be replaced by the Contractor at no additional expense to the Port.

- E. In the event of discrepancy, immediately notify the Engineer. Do not proceed with the Work until all discrepancies have been fully resolved and approved by the Engineer.

### 3.02 SAWCUTTING

- A. Sawcut all pavements designated for removal.
- B. Perform full depth sawcutting of asphalt and concrete pavement as indicated on the Drawings or where directed by the Engineer.
- C. Neatly cut and remove materials and prepare openings to receive new work.
- D. Make neat vertical sawcuts at the boundaries of the area to be removed and use care in removing the pavement and concrete to protect pavement, concrete, and rail which is to remain in place adjacent to the work area.
- E. Provide vacuum equipment to control dust and debris generated by sawcutting operations. Control and prevent silt-laden runoff generated by sawcutting operations from entering the storm drainage system.
- F. Replace any adjacent damaged materials designated to remain at no additional cost to the Port.
- G. Provide bracing, or screening as needed to prevent damage to adjacent facilities that are to remain in place.
- H. Field verify any sensor loops or other objects embedded in the pavement at the vicinity of proposed sawcutting. Notify the Engineer of any conflicts a minimum of two (2) business days prior to the intended sawcutting work.

### 3.03 EXISTING PAVEMENT REMOVAL

- A. Existing asphalt and/or concrete pavement shall be removed to the extent shown on the Drawings, or as described in each Task Order, or where directed by the Engineer, with a method approved by the Engineer.
- B. Care must be taken not to disturb or damage any existing underground utilities during removal.

### 3.04 DISPOSAL

- A. Cleanup: Remove all debris, rubble or litter left at the site from any of the demolition operations and leave a clean site.
- B. The Contractor assumes full responsibility for the proper disposal of all demolition materials under this Contract in a manner that meets the requirements of federal, state and local regulations for protecting the health and safety of employees, the public, and for protecting the environment.

### 3.05 MILL ASPHALT PAVEMENT

- A. Clean the pavement surface of excessive dirt, clay and other foreign material immediately prior to milling the pavement.
- B. Provide a cold-milling machine which is self-propelled, capable of milling the pavement to a specified depth and smoothness and of establishing grade control; with means of controlling transverse slope and dust produced during the pavement milling operation. The machine shall have the ability to grind material to 1-1/2 inch minus in size and remove the millings or cuttings from the pavement and load them into a truck. The milling machine shall not cause damage to any part of the pavement structure that is to remain in place and material shall be loaded directly into a truck.

- C. Where indicated on the Drawings, mill asphalt concrete pavement by pavement grinder to the depth indicated on the drawings or as directed by the Engineer.
- D. Make sufficient passes so that the designated area is milled to the grades and cross sections indicated. The milling shall proceed with care and in depth increments that will not damage the pavement below the designated finished grade. Repair and replace, as directed, items damaged during milling such as manholes, valve boxes, utility lines, pavement that is torn, cracked, gouged, broken or undercut.
- E. Conform the finished milled surfaces to the lines, grades, and cross sections indicated. The finished milled-pavement surfaces shall vary not more than 1/4 inch from the established plan grade line and elevation. Finished surfaces at a juncture with other pavements shall coincide with the finished surfaces of the abutting pavements. The deviations from the plan grade line and elevation will not be permitted in areas of pavements where closer conformance with planned grade and elevation is required for the proper functioning of appurtenant structures involved.
- F. Milling shall not be performed when there is a measurable accumulation of snow or ice on the pavement surface.
- G. The Contractor shall be responsible for locating a stockpile site for milled material and hauling material to this site.

### 3.06 ADJUSTMENT OF EXISTING STRUCTURES

- A. Manholes, valve boxes, catch basins, and other appurtenances within the area to be paved shall be adjusted to grade as shown on the Drawings. Permanent curbs, gutters, and other supports shall be constructed and backfilled prior to placing asphalt or concrete. All asphalt contact surfaces shall be coated with tack coat.

**END OF SECTION**

This page intentionally left blank

## **PART 1 - GENERAL**

### 1.01 SECTION INCLUDES

- A. Concrete Formwork
- B. Concrete Reinforcement
- C. Cast-in-Place Concrete Elements

### 1.02 RELATED SECTIONS

- A. Section 02 41 10 – Site Preparation
- B. Section 31 00 00 – Earthwork

### 1.03 REFERENCES

- A. General: Comply with the most recent edition of the publications listed below to the extent indicated by references thereto.
- B. American Society for Testing and Materials (ASTM)
  - 1. ASTM A82 – Specification for Steel Wire, Plain, for Concrete Reinforcement
  - 2. ASTM A615 - Specification for Deformed and Plain Billet-Steel Bars for Concrete Reinforcement
  - 3. ASTM C33 - Specification for Concrete Aggregate
  - 4. ASTM C94 - Specification for Ready-Mixed Concrete
  - 5. ASTM C150 - Specification for Portland Cement
  - 6. ASTM C156 - Test Method for Water Retention by Concrete Curing Materials
  - 7. ASTM C171 - Specification for Sheet Material for Curing Concrete
  - 8. ASTM C260 – Specification for Air Entraining Admixtures for Concrete
  - 9. ASTM C309 - Specification for Liquid Membrane-Forming Compounds for Curing Concrete
  - 10. ASTM C494 - Specification for Chemical Admixtures for Concrete
  - 11. ASTM C920 - Specification for Elastomeric Joint Sealants
  - 12. ASTM D1751 - Specification for Preformed Expansion Joint Fillers for Concrete Paving and Structural Construction (Nonextruding and Resilient Bituminous Type)
  - 13. ASTM D6690 - Specification for Joint and Crack Sealants, Hot Applied, for Concrete and Asphalt Pavements
  - 14. ASTM E96 - Test Methods for Water Vapor Transmission of Materials
- C. American Concrete Institute (ACI)
  - 1. ACI 301 – Specifications for Structural Concrete
  - 2. ACI 305 – Hot Weather Concreting
  - 3. ACI 306 – Cold Weather Concreting
  - 4. ACI 308 - Standard Practice for Curing Concrete
  - 5. ACI 315 - Details and Detailing of Concrete Reinforcement

6. ACI 318 - Building Code Requirements for Reinforced Concrete

D. Washington State Department of Transportation (WSDOT)

1. Standard Specifications for Road, Bridge and Municipal Construction; Washington State Department of Transportation, M 41-10.

1.04 SUBMITTALS

A. Submit the following documents to, and obtain written approval from, the Engineer before placing any concrete on the job:

1. Certificates of Specification compliance for materials to be used.
2. Proposed concrete mix design, indicating constituent material contents per cubic yard of concrete.
3. Mix design test certificates for compressive strength, yield, air content, and slump of the proposed concrete mix. As a minimum, compressive strength test results at 7, 14, and 28-days shall be provided in accordance with ACI 318 5.3 unless otherwise specified.
4. Manufacturer's name and certificates of compliance with applicable standards shall be provided for all admixtures, concrete bonding agents, curing compounds, etc., proposed for use on the job.

1.05 VERIFICATION OF ELEVATIONS AND DIMENSIONS

- A. Field verify existing surface elevations.

1.06 QUALITY ASSURANCE

A. Inspection and Testing as follows:

1. Port will provide necessary inspection and testing as required.
2. Provide all necessary assistance and access in carrying out such inspections and tests, including sufficient mixed concrete and constituent materials required for testing and inspection, at no additional cost to the Port.

B. Qualification of Workmen as follows:

1. Provide at least one person who shall be present at all times during execution of this portion of the work. They shall be thoroughly trained and experienced in concrete work, and shall direct all work performed under this section.
2. Trained and experienced journeyman concrete finishers shall be responsible for finishing of exposed surfaces.

**PART 2 - PRODUCTS**

2.01 GENERAL

- A. All concrete shall be normal weight concrete and ready-mix. Batching, mixing, transportation, and delivery of ready-mix concrete shall conform to ASTM C94.
- B. Obtain cementitious materials from same source throughout.

2.02 MATERIALS

- A. Forms

1. Forms shall be required for all concrete placements, unless otherwise approved by the Engineer.
2. Forms shall be wood or metal. Metal forms shall have all bolt and rivet heads countersunk so that a plane, smooth surface of the desired contour is obtained. Wood forms shall be sheathed or lined with plywood or tempered masonite so as to form even and uniform surfaces. Plywood forms shall not be used with the second ply exposed. Plywood panels shall be as large as possible.
3. Form ties shall be of approved round design, free from devices that will leave holes or depressions larger than 1-1/4 inches in diameter and of a type that when forms are removed shall leave no metal within 1-inch of finished surfaces. Ties that remain in place, i.e., snapties, shall have a center waterstop washer. Tie wire shall be in accordance with ASTM A82; minimum 16-gage wire required.

B. Reinforcing

1. Bars shall be of the sizes and shapes shown and shall conform to ASTM A615, Grade 60. Bars shall be free of mill, scale, rust, or other coatings.
2. Tie Bars: Shall be deformed steel bars meeting the requirements of ASTM A615, Grade 60.
3. Dowel Bars: Shall be straight, smooth, solid round bars, free from burring or other deformation that would interfere with free movement in the concrete. Dowels shall meet the requirements of ASTM A615, Grade 60. Coat sliding portion of each bar with factory applied, paraffin based lubricant. Lubricant shall be Dayton Superior DSC BB-Coat or Valvoline Tectyl 506 or approved equal. Support dowels with steel baskets or dowel assemblies. Supports shall conform to manufacturers recommendations for rigid welded dowel assemblies, heavy duty type. Weld spacer wires parallel to dowels and weld alternate ends of dowels to sides of assembly. Sliding surfaces shall be parallel with longitudinal axis of pavement within a tolerance of 1/8 inch per foot. Sliding end of assembly crossing joint shall alternate on each side of joint for all dowels in each joint.
4. Tie Wire: ASTM A82 No. 16-gage minimum double annealed black wire
5. Detailing: ACI 315

C. Aggregate

1. Conform to ASTM C33.
2. All coarse and fine aggregate shall consist of hard, tough, durable, particles free from foreign materials, and shall be stored in such a manner as to prevent segregation, excessive breakage, and the introduction of foreign material.
3. Coarse aggregate shall be size 57.

D. Water-reducing admixtures: Conform to the requirements of ASTM C494. Dosage rates in accordance with the manufacturer's recommendations.

E. Air-entraining admixtures: Conform to ASTM C260. Dosage rates in accordance with the manufacturer's recommendations to meet the air content specified herein. The air-entraining admixture shall be added directly to the concrete materials either before or during mixing.

F. Curing Materials

1. Curing materials and methods (if allowed by the Engineer) shall conform to ACI 308.

2. Curing and Sealing Compound (if allowed by the Engineer) shall conform to ASTM C309. Compound must be compatible with all applied finishes designated for use. Materials shall provide water retention not exceeding loss of .055 kg per square meter of surface in 72 hours when used at a coverage of 200 square feet per gallon and tested in accordance with ASTM C156.
  3. Non-staining Waterproof Paper Covering: ASTM C171.
  4. Polyethylene Film: Permeance not to exceed 0.20 perms when tested according to ASTM E96, Procedure B.
- G. Expansion Joint Material
1. Pre-molded filler, bituminous fiber type, ASTM D1751.
- H. Joint Sealant
1. Joint Sealant shall conform to ASTM D6690 or ASTM C920, Type M, Class 25, Use T.
- I. Patching Material and Bonding Agent
1. Bonding Agent Placement: BASF Concrecive Liquid LPL Bonding Agent or approved equal. Dampen surface and remove any standing water to achieve a saturated surface dry condition immediately prior to applying bonding agent and topping concrete placement.
  2. High Performance Portland Cement Mortar: pre-packaged 9000 psi high strength mortar, BASF Emaco T430, available in 55lb bags, or approved equal.

## 2.03 CONCRETE MIX DESIGN

- A. The proportions of aggregate to cement for any concrete shall be such as to produce a mixture which will work readily into the corners and angles of the forms, around reinforcement and embedded items, with the least possible segregation of the material and preventing excess free water to collect on the surface.
- B. Mix design and testing shall be evaluated according to ACI 318 chapter 5. Mix design submittal shall include sufficient information to evaluate the mix per this standard.
- C. Concrete shall be ready mixed concrete conforming to ASTM C94 and the following:
  1. 4000 psi minimum
    - a. 6000 psi minimum
  2. Slump: (3) inches, plus or minus one (1) inch. Slump may be increased by the addition of a water reducing admixture if approved by the Engineer.
  3. Aggregate: Per ASTM C33. Specific gravity of 2.60 minimum required.
  4. Cement: Cement shall conform to ASTM C150, Type I/II.
  5. Admixtures
    - a. All admixtures shall be supplied by one manufacturer approved by the Engineer.
    - b. Chemical admixtures shall conform to ASTM C494.
    - c. Slag cement is not allowed.

- d. Air-Entraining Agents: Shall meet the requirements of ASTM C260 and shall be added to the mixer in the amount necessary to produce (5%) entrained air; plus or minus 1-1/2%.
- e. Water-Reducing Agents: Shall be Master Builders' Pozzolith," or approved equal, conforming to ASTM C494, Type A for water-reducing, Type D for water-reducing and retarding, and Type E for water-reducing accelerating.

### **PART 3 - EXECUTION**

#### **3.01 EXAMINATION**

- A. Verify compacted base course is acceptable and ready for concrete.
- B. Verify gradients and elevations of base are correct.

#### **3.02 PREPARATION**

- A. Inspection:
  - 1. Prior to all work of this section, carefully inspect the installed work of all other trades and verify that all such work is complete to the point where this installation may properly commence.
  - 2. Verify that all items to be embedded in concrete are in place, properly oriented, located, and secured.
  - 3. Verify that concrete may be placed to the lines and elevations indicated on the Drawings, with all required clearance for reinforcement.
- B. Cleaning:
  - 1. Thoroughly clean all areas in which concrete is to be placed to remove all wood debris, sawdust, tie wire cuttings, and all other deleterious materials.
  - 2. Clean and roughen existing concrete or concrete from a previous pour to provide a bondable surface.
  - 3. Thoroughly wet concrete forms which have not been treated with oils, waxes, or other bond breakers prior to placing concrete.
  - 4. Clean all transporting and handling equipment of all hardened concrete.
- C. Notification:
  - 1. Notify the Engineer at least 24-hours in advance of concrete placement.

#### **3.03 FORMWORK**

- A. Forms shall be used to confine the concrete to the shape, line and dimensions of the members, and shall be substantial and sufficiently tight to prevent leakage of mortar. Forms shall be adequate in strength, securely anchored and properly braced and/or tied together to maintain position, shape and alignment within the specified tolerances during all concrete placement and consolidation of operations.
- B. The inside of forms shall be clean, free of encrusted grout and coated with a form release compound appropriate for the form surface and concrete finish required. Forms shall be thoroughly wetted before placing concrete. Under no circumstances shall form release compound be allowed to contact reinforcing steel or construction joint surfaces.

### 3.04 REINFORCING

- A. Fabrication and placement of all reinforcing steel, including the dimensions and radii of cold bent bends, shall comply with ACI 318.
- B. Before any concrete is placed, all reinforcing steel in the section or area to be placed shall be securely tied in place (alternate bar intersections minimum).
- C. Placing and Fastening: Place all steel reinforcement accurately and hold firmly in the position indicated on the Drawing during the placing and setting of concrete. Tie bars at all intersections, except where spacing is less than one foot in each direction, then tie alternate intersections.
- D. Minimum Cover: Provide the following minimum concrete covering of reinforcement:
  - 1. Concrete below ground deposited against forms: Two (2) inches
  - 2. Concrete deposited against earth: Three (3) inches
  - 3. Cover at unformed top surfaces: Two (2) inches
- E. Splicing: Furnish reinforcement in the full lengths indicated on the Drawings or Task Order. When approved by the Engineer, stagger splices minimum 24 inches or one lap length whichever is greater. Unless shown otherwise, lap all reinforcing with a class A lap per ACI 318 (18 inches minimum).
- F. Steel reinforcement, at the time concrete is placed around it, shall be free from loose rust or mill scale, oil, paint, and all other coatings which will destroy or reduce the bond between steel and concrete.

### 3.05 CONCRETE

- A. Placement
  - 1. Concrete shall not be placed without adequate cover during expected rainy periods. Cover materials shall be at the job site, ready for installation before concreting is started and shall remain in place until the concrete has set sufficiently to resist any damage to the finish from rainfall.
  - 2. Water shall be removed from within forms and excavation before and during placement of concrete.
  - 3. Concrete shall be deposited in all cases as near as practicable directly in its final position and shall not be caused to flow in the mass in a manner to permit or cause segregation. Dropping concrete a distance of more than 5 feet vertically without proper confinement or depositing a large quantity at any point and running or working it along the forms will not be permitted.
  - 4. Concrete shall be consolidated with the aid of mechanical vibrating equipment supplemented by hand spading and tamping. Vibrating equipment shall be of the internal type and shall at all times be adequate to properly consolidate all concrete.
- B. Cold and Hot Weather Concreting
  - 1. Do not place concrete when the atmospheric temperature drops below 40°F or rises above 90°F, unless special procedures are followed. The temperature of the concrete at time of placement shall not be over 80°F.

2. Follow procedures for production, delivery, placing, curing, inspection and testing of concrete under hot or cold weather conditions in accordance with the recommendations of ACI 305, "Hot Weather Concreting" or ACI 306, "Cold Weather Concreting".
3. If concrete is placed during cold or hot weather conditions, submit documentation to the Port demonstrating how the procedures described in the above referenced ACI documents will be followed. The Contractor's documentation shall be received by the Port no later than 72 hours prior to concrete placement.
4. The Port's review of this documentation does not relieve the Contractor's responsibility to provide concrete per the Contract Documents.

C. Finishing

1. Spreading dry cement for finishing is not permitted.
2. Finishing operations of all formed surfaces shall begin immediately upon removal of the forms and shall be completed within 8 hours following form removal. Immediately after form removal, all fins, unsightly ridges and projections, and exposed lips and edges shall be removed with a sharp tool or stone to make smooth and flush with adjoining surfaces. All tie rod holes shall be mortar packed. Honeycomb areas shall be patched or cut-out and replaced as directed by the Engineer.
3. Float Finish: All concrete slabs shall be float finished and sloped to indicated grades. Floating may be performed by use of hand or power driven equipment. Floating shall be started as soon as the screeded surface has stiffened sufficiently to produce a uniform surface free from screed marks.
4. Broom Finish: Slabs shall be floated as specified above and then broomed immediately following. The broom shall be of an approved type that will produce regular corrugations not over 1/16-inch-deep. Strokes of the broom shall be to edge of the slab. The finished surface shall be free of porous spots, irregularities, depressions, and pockets.

D. Curing

1. Protect concrete from premature drying. Provide temporary housing, covering, heating, cooling, or other protection as needed. Follow finishing operations with curing measures within 2 hours.
2. Keep concrete continuously moist for 7 days. Prevent rapid drying at the end of the curing period. Accomplish cure by one of the following methods:
  - a. Ponding or continuous sprinkling.
  - b. Absorbent mats or fabrics kept continuously wet.
  - c. Use curing compounds as specified. Remove compound film from all exposed surfaces at the end of curing period. Obtain Engineer's approval for all curing compounds used on vertical surfaces.
  - d. Non-staining waterproof paper as specified. Keep all joints airtight and weighted in place.
  - e. Non-staining polyethylene film as specified. Keep all joints weighted to prevent wind penetration.

E. Tolerances

1. Maximum Variation of Surface Flatness: 1/4 inch in 10 ft.

2. Maximum Variation From True Position: 1/4 inch.

F. Protection

1. Immediately after placement, protect concrete from premature drying, excessive hot or cold temperatures, and mechanical injury.
2. Vehicular traffic shall not be permitted over concrete until strength of concrete has reached 4000 psi.

G. Testing

1. Testing of concrete material will be done by the Port. Methods of sampling, testing, evaluation, and acceptance will conform to ACI 301. All fresh concrete samples intended for testing will be taken at the point of deposit into the formwork.
2. Testing, as described above, will be at Engineer's discretion and in no way relieves the Contractor of any obligations.
3. Additional tests by the Port may include the following:
  - a. Additional testing and inspection required because of changes in materials, proportions, and procedures.
  - b. Additional testing of materials or concrete occasioned by their failure by test or inspection to meet Specification requirements.
4. Any delivered load of concrete that is rejected shall be disposed of completely off-site in conformance with all applicable environmental regulations.

H. Rejected Concrete

1. Concrete not conforming with any portion of the specifications or concrete damaged from any cause and any concrete which shall be found defective at any time before the completion and acceptance of the work shall be removed and replaced.

**END OF SECTION**

## **PART 1 – GENERAL**

### 1.01 SECTION INCLUDES

- A. Existing site conditions.
- B. Excavation, embankment, and base for proposed paving surfaces.

### 1.02 RELATED SECTIONS

- A. Section 02 41 10 – Site Preparation
- B. Section 32 12 16 – Asphalt Paving (Lots Greater Than 300 Tons)
- C. Section 32 12 16.01 – Asphalt Paving (Lots Less Than 300 Tons)

### 1.03 REFERENCES

- A. ASTM C29 - Standard Test Method for Bulk Density (“Unit Weight”) and Voids in Aggregate; American Society for Testing and Materials; Current edition.
- B. ASTM D422 - Standard Test Method for Particle-Size Analysis of Soils; American Society for Testing and Materials; Current edition.
- C. ASTM D1556 - Standard Test Method for Density and Unit Weight of Soil in Place by Sand-Cone Method; American Society for Testing and Materials; Current edition.
- D. ASTM D1557 - Standard Test Method Laboratory Compaction Characteristics of Soil Using Modified Effort (58,000 ft-lbf/ft<sup>3</sup>(2,700 kN-m/m<sup>3</sup>)); American Society for Testing and Materials; Current edition.
- E. ASTM D2167 - Standard Test Method for Density and Unit Weight of Soil in Place by the Rubber Balloon Method; American Society for Testing and Materials; Current edition.
- F. ASTM D6938 - Standard Test Method for In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth); American Society for Testing and Materials; Current edition.
- G. EPA SW 846 - Test Methods for Evaluating Solid Waste, Physical/Chemical Methods; United States Environmental Protection Agency, SW-846; Current edition.
- H. WSDOT - Standard Specifications for Road, Bridge and Municipal Construction; Washington State Department of Transportation, M 41-10; Current edition.
- I. Washington Administrative Code (WAC) Ch. 173-340 - Model Toxics Control Act
- J. Washington Administrative Code (WAC) Ch. 173-303 - Dangerous Waste Regulations

### 1.04 SUBMITTALS

- A. See Section 01 33 00 - Submittal Procedures for submittal procedures.
- B. Submit test reports for all imported materials as specified in Part 3.
- C. Submit test reports for all excavated materials to be used as fill or backfill as specified in Part 3 and not performed by the Port.
- D. Submit test reports for all field tests to determine in-place density as specified in Part 3.

### 1.05 QUALITY ASSURANCE

- A. The Port will provide testing and inspection services of excavated materials.

- B. Contractor shall perform and pay for all test reports on imported material.
- C. Sampling and testing for compliance with the Contract provisions will be in accordance with Section 01 45 00 and Part 3 of these specifications.
- D. Contractor may obtain copies of results of tests performed by the Port at no cost. Tests conducted for the sole benefit of the Contractor shall be at the Contractor's expense.

#### 1.06 EXISTING UTILITIES

- A. Existing Utilities: Verify the location of existing utilities at the sites as shown on the drawings. Contact One-Call at 1-800-424-5555 for utilities within public right of way and private locates for utilities on Port property. Protect those utilities which are to remain from damage. Repair damage to utilities which are to remain at no cost to the Port.

#### 1.07 BARRICADES

- A. Barriers shall be placed at each end of all excavations and at such places as may be necessary along excavations to warn all pedestrian and vehicular traffic of such excavations.
- B. Lighted barriers shall also be placed along excavations from one hour before sunset each day to one hour after sunrise of the next day until such excavation is entirely refilled, compacted and/or work completed. All excavations shall be barricaded in such a manner as to prevent person or persons from entering any excavation site public or private.

### **PART 2 – PRODUCTS**

#### 2.01 GRAVEL BASE

- A. Gravel base material: Clean, well graded granular material meeting the requirements of WSDOT Standard Specifications Section 9-03.9 (3) "CRUSHED SURFACING - BASE COURSE".
- B. Concrete rubble may be used as naturally occurring materials for aggregates on a case by case basis as directed by the Engineer. The product shall meet the specification requirements for specified type of aggregate. Recycled materials that are imported to the project site will require testing and certification for toxicity characteristics per WSDOT Standard Specifications Section 9-03.21(1).

#### 2.02 GRAVEL BACKFILL

- A. Gravel backfill: Clean, graded granular material meeting the requirements of WSDOT Standard Specifications Section 9-03.10 "AGGREGATE FOR GRAVEL BASE". Excavated gravel backfill material shall be characterized as specified in Part 3 herein.

#### 2.03 NATIVE BACKFILL

- A. Native Backfill is existing material which is removed and reinstalled as embankment or backfill in compliance with the material, handling, and installation requirements of the contract. For the purposes of bidding, Contractor shall assume native material will be available and will meet the requirements of the specified backfill and borrow material as follows:
  - 1. Native Backfill as Gravel Backfill above pipe zone for construction of Storm Drainage trunks and pipelines.
  - 2. Native Backfill as Gravel Backfill above Gravel Bedding Material for construction of Water Mains.

3. Native Backfill as Gravel Borrow for Embankment Construction: Where embankment is required between existing grade and bottom of pavement gravel base, material shall meet WSDOT Specification Section 9-03.14(1) for gravel borrow.
4. Native Backfill as Crushed Surfacing Base Course above Gravel Bedding zone for construction of Direct Buried Conduits.

#### 2.04 CRUSHED SURFACING TOP COURSE (CSTC)

- A. Crushed surfacing top course shall be manufactured from ledge rock, talus, or gravel meeting the requirements of WSDOT Standard Specifications Section 9.03.9(3) "CRUSHED SURFACING - Top Course".

#### 2.05 CRUSHED SURFACING BASE COURSE (CSBC)

- A. Crushed surfacing base course shall be manufactured from ledge rock, talus, or gravel meeting the requirements of WSDOT Standard Specifications Section 9.03.9(3) "CRUSHED SURFACING - Base Course".

#### 2.06 GRAVEL BORROW

- A. WSDOT Standard Specifications Section 9-03.14(1) "GRAVEL BORROW".

#### 2.07 SOIL STABILIZATION FABRIC

- A. Where directed by the Engineer, the Contractor shall place a geotextile fabric over the existing subgrade with a minimum of a twenty-four (24) inch overlap.
- B. The geotextile fabric shall be a non-woven polypropylene fabric. The fiber filaments shall be continuous filaments and shall be bonded by the needle punching bonding method.
- C. All rolls of material delivered to the site shall be properly packaged per the manufacturer's recommendation.

### **PART 3 – EXECUTION**

#### 3.01 GENERAL

- A. Excavation: Naturally occurring soil, sand, gravel, clays, or mixtures of the above, required to be moved or removed for the construction of roadways, parking areas, and associated work.
  1. Move excavation material with the use of mechanical equipment, such as shovels, loaders, bulldozers, graders, rippers, etc., that does not require drilling and blasting or drilling and line breaking.
  2. Do not excavate by sluicing method.
  3. In general, remove excavation in horizontal layers in such a way that the resulting material will be a reasonable blend of the naturally occurring materials.
  4. All excavated material may be stockpiled on plastic sheeting beside the trench as it is removed and may, if characterized as suitable and meets the requirements of Paragraph 2.03, be used as backfill from this position or wasted offsite.
- B. Filling: Place material used for the construction of fill or backfill in horizontal layers upon soil which has been stabilized or otherwise approved by the Engineer for fill or backfill construction.

### 3.02 EXPORT MATERIAL

- A. Material to be exported from the site must be stockpiled and characterized prior to offsite disposal. The Contractor will stockpile material at a location onsite as directed by the Engineer. Stockpiled material shall be placed onto plastic sheeting, covered and anchored to prevent rain water from contacting material. Refer to Paragraph 3.04 for characterization and disposal requirements. Contractor shall base their bid on the assumption that excavated material is not regulated.

### 3.03 CONTAMINATED/HAZARDOUS SOILS AND GROUNDWATER

- A. Contractor shall monitor soils and groundwater by instructing workers in observing and reporting questionable materials, odors, oily sheen or color on soils and water, and oily or chemical odors. If unexpected hazardous or contaminated materials are encountered, Contractor shall stop work in that area immediately and notify the Port.

### 3.04 EXCAVATED MATERIAL CHARACTERIZATION AND DISPOSAL

- A. Segregate and stockpile material for Port examination, identification, and testing.
  - 1. Notify the Port when materials are ready for testing.
  - 2. Contractor will allow 21 days for characterization of stockpiled materials
  - 3. Port of Tacoma will pay for and conduct testing of excavated materials.
  - 4. Port of Tacoma will be responsible for identifying whether material is regulated or non-regulated solid waste under this contract.
- B. Under this contract, material will be considered non-regulated solid waste if Port assessments indicate that concentrations of potential contaminants are equal to or below concentrations identified in WAC 173-340-900 Table 745-1 (Method A Soil Cleanup Levels for Industrial Properties) and if material is not designated as dangerous waste per WAC 173-303. The Port may base its identification of regulated or non-regulated material on one, several, or all of the parameters listed in WAC 173-340-900 Table 745-1 and WAC 173-303 (Dangerous Waste Regulations), at its own discretion, based on professional judgment with respect to indicators of suspicious material in the field and Port knowledge of the source of the suspicious material.
  - 1. Further management, handling, and disposal of material identified by the Port to be non-regulated shall be the responsibility of the Contractor. Contractor shall be responsible for the performance and cost of any additional characterization of clean material that may be required for Contractor's choice of disposal locations.
  - 2. Further management of regulated material through loading of the material into transport equipment/vehicles will be the responsibility of the Contractor at no additional cost to the Port. The Contractor will arrange for the appropriate transport and disposal of regulated material.
- C. Clean excess soils generated during site activities may be used for backfill and other fills associated with the work, as approved by the Engineer.

### 3.05 IMPORT MATERIAL CHARACTERIZATION TESTING, REPORTING, AND CERTIFICATION

- A. Provide characterization and testing as described below for all off-site borrow materials.
- B. The Contractor is responsible for all testing costs associated with characterization of off-site borrow materials.
- C. Provide the following information with each sample submitted:

1. Material Source
2. Proposed On-site Use
3. Sampling dates
4. Chain of custody
5. Sampling locations
6. Contractor's certification that the samples submitted are representative of the materials that shall be reused at the site.

D. Characterization Testing shall include:

1. Grain Size Distribution (ASTM D 422)
2. Maximum Dry Density (ASTM D1557)
3. Weight per unit volume of uncompacted material (ASTM C 29)
4. Priority Pollutant Metals (EPA SW 846 6010/6020/ 7041)
5. Volatile Organic Compounds (EPA SW 846 8260)
6. Semi-volatile Organic Compounds (EPA SW 846 8270)
7. PCBs and Pesticides (EPA SW 846 8080)
8. Petroleum Hydrocarbons (NWTPH-HCID)

### 3.06 COMPACTION

- A. Perform compaction with approved compaction equipment suited to the soil and the area being compacted.
- B. Moisten or aerate material as necessary to provide the moisture content that will readily facilitate obtaining the specified compaction with the equipment used.
- C. Uniformly compact each lift of material placed to the density indicated for the specific material and use set forth in these Specifications. The percent of density required is in relation to the maximum density obtainable at optimum moisture content (Compaction Control Density) as determined in paragraph 3.07 "Compaction Control Tests."

### 3.07 COMPACTION CONTROL TESTS

- A. Perform laboratory and field tests in accordance with the applicable provisions of these Specifications.
  1. Compaction control density shall be the maximum density at optimum moisture content as determined by ASTM D-1557, Standard Methods for Moisture-Density Relationships of Soil and Soil Aggregates, Methods B, C or D as applicable.
  2. Perform field tests to determine in-place compliance with required densities as specified and performed in accordance with ASTM D1556, D2167, or D6938.

### 3.08 GRADING AND LEVELING

- A. Grade the finished profiles of the construction areas within a tolerance of 0.05 foot plus or minus in 10 feet, ready for gravel base (wherever pavement is to be furnished).

### 3.09 PREPARATION FOR BASE COURSE OR GRAVEL SURFACING

- A. Preparation of Subgrade: Immediately prior to placement of surfacing materials, clean the entire width of the area of all debris and dispose of as directed by the Engineer. All depressions or ruts which contain storm water shall be drained.
1. Shape the entire subgrade to a smooth uniform surface, true to line, grade, and cross section as staked by the Engineer.
  2. Compact the material for a depth of six-inches below the subgrade to 95% of the maximum dry density as determined by compaction tests ASTM Designation D1557.
  3. If soft or spongy material underlying the upper six inches of the area being prepared precludes satisfactory compaction of the upper six inches, loosen, aerate, or excavate, replace and compact to the required density as directed by the Engineer.
  4. Remove and dispose of excess material which cannot be disposed of by normal drifting to low spots during blading and shaping operations or by placing in subgrade areas deficient in materials or by wasting, all as directed by the Engineer.
  5. Bring subgrade areas deficient in materials to grade by importing suitable materials from other subgrade areas or other sources as directed by the Engineer. Where embankment is required between existing grade and bottom of pavement gravel base, place material that meets the requirements described in WSDOT Specification Section 9-03.14(1) for gravel borrow. Place and compact earth embankment in conformance with WSDOT Specification 2-03.3(14) for embankment construction.
  6. Water materials added to subgrade areas deficient in materials and compact as necessary to yield a true finished subgrade as described above.
  7. Once it is prepared, maintain the subgrade for surfacing in the finished condition until the first course of surfacing has been placed.
- B. Finishing Subgrades: Before any paving material is placed, bring the subgrade to the proper line, grade and cross section and maintain until the base course and paving is placed, except that extra depth of subgrade for increased thickness of the pavement, for pavement anchors, for pavement headers, and for increased thickness at the edges of the pavement may be removed just before the pavement is placed.
1. Compact the subgrade for pavement to 95% of maximum dry density as defined for Compaction Control Density, Article "Compaction Control Tests" these Specifications, to a minimum depth of six inches and to a width that will accommodate the paving equipment.
- C. Subgrade Protection: Take all precautions necessary to protect the subgrade from damage; hauling over the finished subgrade shall be limited to that which is essential for construction purposes.
1. Equipment used for hauling over the prepared subgrade which, in the opinion of the Engineer, is causing undue damage to the prepared subgrade or to the underlying materials, shall be removed from the work at the request of the Engineer.
  2. Repair at the Contractor's expense all cuts, ruts and breaks in the surface of the subgrade prior to placing surfacing, treated base, or paving materials.

3. Protect the prepared subgrade from both the Contractor's traffic and public traffic and maintain the subgrade by blading and rolling as frequently as may be necessary to preserve the subgrade in a completely satisfactory condition.

**END OF SECTION**

This page intentionally left blank

## **PART 1 - GENERAL**

### 1.01 SCOPE

- A. The work covered by this Section includes the furnishing of all labor, materials, equipment and necessary services to construct asphalt pavements to the sections and at the locations as specified in this Section and as indicated on the Contract Drawings.
- B. This specification covers the requirements for general asphalt paving at the Port of Tacoma and includes mix design criteria for various aggregate gradations (  $\frac{1}{2}$  ",  $\frac{3}{4}$  " and 1").
  - 1. Specific Task Orders issued under this Contract may use one or more aggregate gradations. Each gradation shall meet the respective sieve criteria, gyration levels (N), target air voids ( $V_a$ ), voids filled with asphalt (VFA), and voids in mineral aggregate (VMA) as specified. The Contractor shall provide mix designs and quality control testing for EACH gradation specified herein

### 1.02 REFERENCES

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.
- B. Unless otherwise indicated, the most recent edition of the publication, including any revisions, shall be used.
- C. American Association of State Highway and Transportation Officials (AASHTO)
  - 1. AASHTO M 17 - Mineral Filler for Bituminous Paving Mixtures
  - 2. AASHTO M 323 - Superpave Volumetric Mix Design
  - 3. AASHTO M 332 - Performance-Graded Asphalt Binder Using Multiple Stress Creep Recovery (MSR) Test
  - 4. AASHTO T 11 - Materials Finer Than 75  $\mu$ m (No. 200) Sieve in Mineral Aggregates by Washing
  - 5. AASHTO T 27 - Sieve Analysis of Fine and Coarse Aggregates
  - 6. AASHTO T 89 - Determining the Liquid Limit of Soils
  - 7. AASHTO T 90 - Determining the Plastic Limit and Plasticity Index of Soils
  - 8. AASHTO T 96 - Resistance to Degradation of Small-Size Coarse Aggregate and Impact in the Los Angeles Machine
  - 9. AASHTO T 112 - Clay Lumps and Friable Particles in Aggregate
  - 10. AASHTO T164 - Quantitative Extraction of Asphalt Binder from Hot Mix Asphalt (HMA)
  - 11. AASHTO T168 - Sampling Hot Mix Asphalt Paving Mixtures
  - 12. AASHTO T 176 - Plastic Fines in Graded Aggregates and Soils by Use of the Sand Equivalent Test
  - 13. AASHTO T 304 - Uncompacted Void Content of Fine Aggregate
  - 14. AASHTO T308 - Determining the Asphalt Binder Content of Hot Mix Asphalt (HMA) by the Ignition Method
  - 15. AASHTO T 312 - Preparing and Determining the Density of Hot Mix Asphalt (HMA) Specimens by Means of the Superpave Gyrotory Compactor

16. AASHTO T 324 - Hamburg Wheel-Track Testing of Compacted Asphalt Mixtures
17. AASHTO T 329 - Moisture Content of Hot Mix Asphalt (HMA) by Oven Method
18. AASHTO T 335 - Determining the Percentage of Fracture in Coarse Aggregate

D. American Society for Testing and Materials (ASTM)

1. ASTM D75 - Sampling Aggregates
2. ASTM D2041 - Standard Test Method for Theoretical Maximum Specific Gravity and Density of Bituminous Paving Mixtures
3. ASTM D2726 - Standard Test Method for Bulk Specific Gravity and Density of Non-Absorptive Compacted Asphalt Mixtures
4. ASTM D4791 - Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate

E. Washington State Department of Transportation (WSDOT)

1. Construction Manual, M 41-01
2. Standard Specifications for Road, Bridge and Municipal Construction, M 41-10
3. Materials Manual, M 46-01

### 1.03 SUBMITTALS

- A. A separate job mix formula for each proposed mix design shall be submitted in writing by the Contractor upon execution of the task order. Submittals shall represent all submittal elements specified herein and shall include as a minimum:
1. Mix designation/identification number and certificate of manufacturer's rated production rate.
  2. Plant where mix will be produced.
  3. Performance Graded Binder Certified Test Reports
    - a. Source location and type of binder.
    - b. Certificate of Compliance, including date and signature of the supplier, regarding conformance with AASHTO M 332, Table 1.
    - c. Recovery requirements in accordance with WSDOT Section 9-02.1(4)
    - d. Temperature-viscosity relationship of the asphalt cement.
    - e. Minimum mixing temperature (degrees F).
    - f. Minimum compaction temperature (degrees F).
  4. Coarse Aggregate Certified Test Reports:
    - a. Source location and type of aggregate.
    - b. Angularity.
    - c. Bulk specific gravity.
    - d. Flat and elongated particles.
    - e. Soundness.

- f. LA Abrasion.
5. Fine Aggregate Certified Test Reports:
  - a. Source location and type of aggregate.
  - b. Bulk specific gravity.
  - c. Percent natural sand (if used).
  - d. Sand equivalent.
  - e. Uncompacted void content.
6. Recycled Asphalt Pavement Test Reports (if used)
7. Anti-strip agent:
  - a. Certification.
  - b. Amount used.
8. Optimum Asphalt Determination (in accordance with ASTM D5581 or ASTM D6927, as appropriate).
  - a. Compactive effort (75 or 112 blows applied to specimen, each face, as appropriate).
  - b. Actual specific gravity and unit weight of each specimen.
  - c. Percentage of asphalt in each specimen.
  - d. Theoretical specific gravity of each specimen calculated.
9. Percentage and grade of performance graded asphalt binder.
10. Proportions and percentage of each aggregate stockpile.
11. Temperature of mix when discharged from the mixer.
12. Compaction temperature
13. Plot of the blended aggregate gradation and gradation control points on the Federal Highway Administration (FHWA) 0.45 power gradation curve.
14. Maximum specific gravity at the target binder content.
15. Gyrotory compaction curve for  $N_{max}$ .
16. Bulk specific gravity at  $N_{design}$  gyrations.
17. Percent theoretical maximum density at  $N_{initial}$ ,  $N_{design}$ , and  $N_{max}$  gyrations.
18. Voids in mineral aggregate at  $N_{design}$  gyrations.
19. Voids filled with asphalt at  $N_{design}$  gyrations.
20. Dust to binder ratio
21. Flow value
22. Stability
23. Actual unit weight of laboratory compacted mixture.

- 24. Graphical plots of air voids, voids in the mineral aggregate, voids filled with asphalt, fines to effective binder content ratio, and unit weight verses asphalt content. Plots shall indicate values at -0.5 percent design asphalt content, design asphalt content, and +0.5 percent design asphalt content.
  - 25. Tensile strength ratio (TSR), strength of conditioned samples, and worksheets.
  - 26. A Hamburg Wheel-Track test, ASSHTO T 324. The mix design shall be evaluated and shall have a minimum of 15,000 passes before a rut depth of 10mm is achieved, with no stripping inflection point.
- B. The certification(s) shall show the appropriate AASHTO/ASTM test(s) for each material, test results, and a statement that the material meets the specification requirement.
  - C. If requested by the Engineer, submit samples for each type of aggregate to be used and from each source with proper identification as to source, type of aggregate and contract number. Take all samples in accordance with requirements of ASTM D75 and D242. Submit in clean, sturdy bags and in the following amounts for each sample when requested:

MATERIAL	SAMPLE SIZE
Coarse Aggregate	25 lbs.
Fine Aggregate	25 lbs.
Reclaimed Asphalt Pavement	25 lbs.
Mineral Filler	5 lbs.

- D. The job mix formula for each mixture shall be in effect until modified in writing by the Engineer. Should a change in mix or sources of materials be made, a new job mix formula must be tested and resubmitted for approved by the Engineer before the new mix is used.
- E. Working Drawings: For each paving area, provide working drawings to show the following information:
  - 1. Direction of paving.
  - 2. Lane widths.
  - 3. Thickness of each lift.
- F. Submit smoothness measurements and surface grade survey results to the Engineer prior to application for payment.
- G. Equipment List: The Contractor shall submit a list of equipment to be used for placing asphalt concrete to the Engineer prior to utilization on the job.
- H. Moisture content of asphalt

1.04 CONTRACTOR QUALITY CONTROL

- A. The Contractor shall be responsible for developing the asphalt mix designs specified herein. The mix designs shall be developed and/or certified by a laboratory accredited by AASHTO under the AASHTO resource program. Mixtures on WSDOT's QPL are considered to be certified.
- B. Quality Control Testing: The Contractor shall conduct any and all quality control (QC) testing that he deems necessary to properly control the quality, consistency, and uniformity of the asphalt concrete mix being produced. The minimum number of quality control tests is required for this Contract are defined in the following sections.

1. Asphalt Content. A minimum of one test shall be performed per lot in accordance with ASTM D6307 or ASTM D2172 for determination of asphalt content. If ASTM D6307 is used, mix specific calibration factors shall be determined at the beginning of plant production and furnished to the Engineer. If ASTM D2172 is used, the weight of ash portion of the test, as described in ASTM D2172, shall be determined as part of the first test performed at the beginning of plant production; and as part of every tenth test performed thereafter, for the duration of planned production. The last weight of ash value obtained shall be used in the calculation of the asphalt content for the mixture. The asphalt content for the lot will be determined by averaging the test results.
  2. Gradation. Aggregate gradations shall be determined at a minimum of twice per lot from mechanical analysis of extracted aggregate in accordance with ASTM D5444, ASTM C136, and ASTM C117.
  3. Aggregate Specific Gravities. The effective specific gravity of the aggregates in the mixture shall be determined in accordance with ASTM D6995 during construction of the test section and after every 2000 tons of mix production. If the effective specific gravity differs from the approved mix design by more than 1 percent, notify the Engineer. On the next lot after notification, in addition to the normal acceptance tests, the Contractor shall measure the bulk specific gravity of the aggregates in accordance with ASTM C127 and ASTM C128 and the asphalt content of each subplot in accordance with ASTM D6307 or ASTM D2171 and compute the VMA of the mixture for each subplot. If the VMA deviates by more than 1.0% from the mix design, then the contractor shall stop production and produce a revised mix design.
  4. A Hamburg Wheel-Track test, ASSHTO T 324. One sample shall be evaluated for each LOT and shall have a minimum of 15,000 passes before a rut depth of 10mm is achieved, with no stripping inflection point.
  5. Additional Testing. Any additional testing that the Contractor deems necessary to control the process may be performed at the Contractor's option.
- C. For all Quality Control testing performed by Contractor, information and data determined through that testing shall be made available for inspection by Engineer upon request. In no case, however, will Contractor's Quality Control test data be used by Engineer for acceptance or payment purposes.
- D. Surface Grades: Grades shall conform to the tolerance requirements specified herein, except where closer tolerance is required for the proper functioning of appurtenant structures and drainage as determined by the Engineer.

#### 1.05 QUALITY ASSURANCE

- A. The Engineer will provide inspection services. Sampling and testing for compliance shall be in accordance with the applicable reference standards using certified technicians and accredited independent testing laboratories.
- B. Sampling and testing for compliance with the Contract provisions shall be in accordance with Section 01 33 00 - Submittal Procedures and Section 01 45 00 - Quality Control.
- C. The Contractor may obtain copies of results of tests performed by the Engineer, at no cost. Tests conducted for the sole benefit of the Contractor, shall be at the Contractor's expense.
- D. Unless otherwise referenced or modified herein, quality control and quality standards for this section shall be as specified in the WSDOT Standard Specifications.

## 1.06 JOB CONDITIONS

- A. Environmental Requirements:
  - 1. Do not place asphalt beginning October 1st through March 31st of the following year, without written concurrence from the Engineer.
  - 2. In case of sudden rain, the Engineer may permit placing of mixture then in transport from the plant provided that the surface upon which the mix being placed is dry. In addition, the laydown temperatures must conform to the above requirements. Such permission, however, shall not be interpreted as a waiver of any of the quality requirements.
- B. New and existing manholes, catch basins, and utility vault covers shall be adjusted to conform to the new pavement grades. All lids, vaults, frames, grates, and other appurtenances shall be set to final grade and accepted by the Engineer paving. Paving shall be finished 1/4-inch to 1/2-inch higher than adjacent structures, unless otherwise shown or specified.
- C. Existing Underground Utilities: The Contractor shall locate existing underground utilities in the area of the work. Those utilities which are to remain shall be adequately protected from damage.
- D. All permanent utilities shall be installed prior to final paving. All utility trenches shall be patched with asphalt pavement as shown on the Contract Drawings.
- E. Dust Control: The Contractor shall be responsible for dust control at the site. As a minimum, a water truck and vacuum truck shall be used on site for dust control when required by the Engineer.

**PART 2 - PRODUCTS**

**2.01 PERFORMANCE GRADED ASPHALT BINDER (PGAB)**

- A. Asphalt shall conform to the requirements of AASHTO M 332, Table 1, and the recovery requirements of WSDOT Standard Specification Section 9-02.1(4) for the Performance Grade specified herein. The RTFO  $J_{nr diff}$  and PAV direct tension specifications of AASHTO M 332 are not required.

**2.02 AGGREGATE**

- A. Coarse Aggregate – Coarse aggregate shall conform to WSDOT Standard Specification Section 9-03.8 and AASHTO M 323, as modified below:

Test	Specification
Flat and Elongated Particles (ASTM D 4791, using a ratio of 5:1, maximum to minimum dimension)	8%, maximum
Coarse Aggregate Angularity (AASHTO T 335)	95% with 2 or more fractured faces 100% with 1 or more fractured faces
LA Abrasion Wear (AASHTO T 96, 500 revolutions)	40%, maximum

- B. Fine Aggregate - Fine aggregate shall consist of clean, sound, durable, angular shaped particles produced by crushing stone or gravel that meets the requirements for wear and soundness specified for coarse aggregate. Natural (non-manufactured) siliceous sand may be used to obtain the gradation of the aggregate blend or to improve the workability of the mix. The amount of sand to be added will be adjusted to produce mixtures conforming to requirements of this Specification. The aggregate particles shall be free from coatings of clay, silt, or other objectionable matter and shall contain no clay balls. Fine aggregate shall conform to WSDOT Standard Specification Section 9-03.8 and AASHTO M 323, as modified below:

Test	Specification
Sand Equivalent (AASHTO T 176)	45%, minimum
Uncompacted Void Content (AASHTO T 304, Method A)	45%, minimum
Deleterious Materials (AASHTO T 112)	2%, maximum

- C. Mineral filler, when used, shall conform to the requirements of AASHTO M 17.
- D. Crushed slag aggregates shall not be used.
- E. Recycled Asphalt Pavement (RAP)
  - 1. RAP, if used, shall conform to the requirements of WSDOT Standard Specification Section 9-03.8(3)B, 9-03.21(1), and 9-03.21(1)A, as modified herein.

2. The maximum proportion of RAP permitted within each mix shall not exceed 20 percent measured by total weight of HMA.
3. RAP shall have 100 percent passing the 2-inch sieve, 95 percent passing the 1 inch sieve, and shall be a mixture of only coarse aggregate, fine aggregate, and asphalt cement, free of solvents and other contaminating materials.
4. When RAP is used in a mixture, the RAP aggregate shall be extracted from the RAP using a solvent extraction (AASHTO T164) or ignition oven (AASHTO T308). The RAP aggregate shall be included in determinations of gradation, coarse aggregate angularity, fine aggregate angularity, and flat-and-elongated requirements. The sand equivalent requirements shall be waived for the RAP aggregates but shall apply to the remainder of the aggregate blend.
5. Documentation of RAP stockpile quality and traceability shall be submitted to the Engineer for approval prior to use.

F. Aggregate Gradation

1. Each gradation contains maximum and minimum control points. Job mix formula gradations must fall within control points for the specified nominal aggregate size. The combined aggregate shall conform to the gradation requirements shown below when tested in accordance with AASHTO T11 and T27. Design gradation requirements are as follows:

Sieve	1/2-inch NMAS	3/4-inch NMAS	1-inch NMAS
Size	(Percent Passing)	(Percent Passing)	(Percent Passing)
1-1/2"	-	-	100
1"	-	100	90-100
3/4"	100	90-100	67-86
1/2"	90-100	60-90	60-80
3/8"	75-90	50-82	51-69
No. 4	46-66	35-65	34-56
No. 8	33-45	23-49	27-43
No. 30	13-29	10-30	12-28
No. 200	3.0-7.0	3.0-7.0	3.0-7.0

2. Aggregates shall be provided in sufficient sizes to produce a uniform mixture. The Contractor shall indicate on the proposed job-mix formula the separate size designations of aggregate to be used.
3. It is recommended that the Bailey Method of gradation evaluation be used to evaluate the packing of aggregate particles and constructability of the blended aggregate mix. If segregation or non-uniformity is evident in the finished pavement, the Engineer reserves the right to require the Contractor to discontinue the use of crusher run or aggregate blends and to furnish separate sizes of open graded aggregate material.
4. Blended Aggregates:
  - a. Fine aggregates and coarse aggregates when blended shall not contain more than 2 percent by mass, clay and other friable particles as determined by AASHTO T 112.

- b. Each gradation contains maximum and minimum control points. Job mix formula gradations must fall within control points for the specified mix. The combined aggregate shall conform to the gradation requirements shown here when tested in accordance with AASHTO C117 and C136.

2.03 HOT MIX ASPHALT (HMA) MIX DESIGN

- A. Mix design shall be prepared by the Contractor in accordance with WSDOT SOP 732 as modified herein.
- B. Asphalt Binder: PG 58V-22.
- C. Aggregate Gradation: [1/2-inch; 3/4-inch; 1-inch]
- D. Gyration levels for mix preparation shall conform to the following:

Mix Designation	N <sub>initial</sub>	N <sub>design</sub>	N <sub>max</sub>
1/2 inch	8	100	160
3/4 inch	7	75	115
1 inch	7	75	115

- E. The target air voids (V<sub>a</sub>) of the mix design at the design number of gyrations shall be as follows:

Mix Designation	Air Voids (Percent)
1/2 inch	4.0
3/4 inch	4.0
1 inch	4.0

- F. The voids filled with asphalt (VFA) at the target air void level shall be as follows:

Mix Designation	Voids Filled with Asphalt (Percent)
1/2 inch	65 – 75
3/4 inch	65 – 75
1 inch	65 – 75

- G. The voids in mineral aggregate (VMA) of the HMA design shall be as follows:

Mix Designation	Voids in Mineral Aggregate (Percent) Minimum <sup>1</sup>
1/2 inch	14.0
3/4 inch	13.0
1 inch	12.0

<sup>1</sup>Note: VMA is not allowed to drop below minimum in production.

- H. The HMA design when compacted in accordance with AASHTO T 312, shall meet the density specified below at the initial, design, and maximum compaction levels.

Compaction Level (Number of Gyration)	Required Density (% of Theoretical Maximum Specific Gravity)
$N_{ini}$	$\%G_{mm} \leq 89$
$N_{des}$	$\%G_{mm} = 96$
$N_{max}$	$\%G_{mm} \leq 98$

- I. The dust to binder ratio (by weight ratio between the minus 200 sieve material and effective asphalt content) of the blended mix shall be between **[0.6 and 1.4 for 1/2-inch and 3/4-inch mixes, and 0.6 to 1.6 for 1-inch mix]**.
- J. Compacted mix design shall have a maximum rut depth after 15,000 passes of 10 mm and no stripping inflection point when tested accordance with WSDOT FOP for AASHTO T324. If a stripping inflection point is observed, the Contractor shall increase the approved anti-stripping agent dosage or take other corrective action to satisfy the specification.
- K. The mixture shall have a maximum indirect tensile strength of 175 psi per WSDOT Bituminous Materials FOP for ASTM D6931.

#### 2.04 HEAT-STABLE ANTI-STRIPPING ADDITIVE

- A. Mix designs shall include a minimum of 0.05 percent by weight of binder of an approved non-amine based anti-stripping additive, ZycoTherm SP2 or equivalent.

#### 2.05 TACK COAT

- A. Unless otherwise approved by the Engineer, the tack coat shall be CSS-1, CSS-1h, or STE-1 emulsified asphalt conforming to WSDOT Standard Specification Section 9-02.1(6). The CSS-1 and CSS-1h emulsified asphalt may be diluted with water at a rate not to exceed one part water to one part emulsified asphalt. The tack coat shall not exceed the maximum temperature recommended by the emulsified asphalt manufacturer.

#### 2.06 JOINT AND CRACK SEALANT

- A. Sealant material shall conform to the requirements of WSDOT Standard Specification Section 9-04.2(1)A2.

### PART 3 - EXECUTION

#### 3.01 CONSTRUCTION METHODS

- A. Asphalt Mixing Plant – Asphalt shall be produced at a plant approved by the WSDOT. Plants shall conform to WSDOT Standard Specifications Section 5-04.3(3)A.
- B. Hauling Equipment:
- Hauling equipment shall conform to WSDOT Standard Specifications Section 5-04.3(3)B, as modified herein.
  - Trucks shall be equipped with tarps, in good condition without holes, which can be tied down over the sides and ends of the truck beds during periods of inclement weather to prevent rain from entering the truck bed and coming in contact with the asphalt concrete mix.

3. Trucks shall be loaded using a multiple-drop method (front then back the middle) to minimize truck to truck segregation.
- C. Paving Equipment – Asphalt pavers shall conform to WSDOT Standard Specifications Section 5-04.3(3)C.

**NOTE: The requirement for using a material transfer vehicle may be removed as determined appropriate by the specifier.**

- D. Materials Transfer Vehicle – For lots greater than 300 tons, the Contractor shall use a Materials Transfer Vehicle (MTV) to deliver the HMA from the hauling equipment to the paving equipment for any lift in or partially in the top 0.3 feet of the pavement section. MTVs shall conform to WSDOT Standard Specifications Section 5-04.3(3)D. **[All 1 inch NMAS mix must be placed with an MTV, regardless of depth from surface.]**
- E. Compaction Equipment – Rollers shall conform to WSDOT Standard Specifications Section 5-04.3(3)E.
- F. Preparation of the Asphalt Binder Material (asphalt cement):
1. The binder shall be stored within the temperature range specified by the supplier of the binder for the grade of asphalt cement being used. Different grades of asphalt binder shall be stored separately and not mixed together at any time.
  2. The binder shall be heated in a manner that will avoid local overheating and provide a continuous supply of the bituminous material to the mixer at a uniform temperature.
  3. The temperature of the binder delivered to the mixer shall be sufficient to provide a suitable viscosity for adequate coating of the aggregate particles, but shall not exceed 350 degrees F unless otherwise required by the asphalt binder manufacturer.
- G. Preparation of the Aggregates:
1. The aggregate for the mixture shall be heated and dried prior to introduction into the mixer. Aggregate shall be dry with no moisture content prior to introduction into the mixer. The maximum temperature and rate of heating shall be such that no damage occurs to the aggregates.
  2. The aggregate temperature shall not be lower than is required to obtain complete coating and uniform distribution of the aggregate particles and to provide a mixture of satisfactory workability.
- H. Preparation of Bituminous Mixture:
1. Asphalt plant shall not exceed production rate certified by manufacturer.
  2. Mixing shall conform to WSDOT Standard Specifications Section 5-04.3(6), as modified herein.
  3. The aggregates and the bituminous material shall be properly proportioned and introduced into the mixer in the amount specified by the job mix formula.
  4. Job mix formula production tolerances shall conform to WSDOT Standard Specifications Section 9-03.8(7), except the tolerance limits for aggregate shall not exceed the limits of the control points specified herein.

5. The moisture content of all bituminous mix upon discharge shall not exceed one (1) percent. Asphalt sampling shall be performed in accordance with AASHTO T 168 and moisture content testing shall be performed in accordance with AASHTO T 329. Results of the moisture content testing shall be submitted to the Engineer.
- I. Preparation of the Underlying Surface:
    1. Preparation shall conform to WSDOT Standard Specifications Sections 5-04.3(4), and, 5-04.3(4)C as modified herein.
    2. Asphalt materials shall not be placed until the underlying course has been tested and accepted by the Engineer.
    3. The underlying surface shall be free of water, foreign material, and dust when the hot mix asphalt mixture is applied. Immediately before placing asphalt materials, clean all underlying surfaces and previous courses of all loose and foreign material by sweeping with hand brooms, power sweepers or blowers as directed by the Engineer.
    4. Tack Coat:
      - a. Tack coat shall be applied in accordance with WSDOT Standard Specifications Section 5-04.3(4), as modified herein. The Engineer shall verify that the tack coat has been properly placed prior to constructing subsequent pavement lifts. Refer to the applicable sections in Chapter 5 of the WSDOT Construction Manual for guidance on tack coat application and inspection.
      - b. Apply tack coat only when the underlying surface is free of water, foreign material, dust, and the ambient temperature meets the requirements for the pavement course being placed.
      - c. Residual asphalt coating shall be 0.03 to 0.05 gallons per square yard on newly placed asphalt surfaces
      - d. Residual asphalt coating shall be 0.06 to 0.08 gallons per square yard on existing or milled asphalt surfaces.
      - e. Residual asphalt coating shall be 0.06 to 0.08 gallons per square yard on compacted subgrade.
      - f. Tack coat shall be applied to all vertical surfaces of existing pavement, curbs, gutters, utility structures, concrete edge of the wharf, and construction joints in the asphalt against which additional material is to be placed.
      - g. Exposed surfaces of utility vault lids, frames, grates, valve boxes, inlets and other appurtenances within the area to be paved shall be protected from tack coating.
    5. Manholes, valve boxes, inlets, frames, grates, lids, and other appurtenances within the area to be paved shall be adjusted to final grade as shown on the Contract Drawings, shall be in place during paving operations, and shall not be paved over as part of the paving operation. Permanent curbs, gutters, and other supports shall be constructed and backfilled prior to placing asphalt. All contact surfaces shall be coated with tack coat.
  - J. Transporting, Placing, and Finishing:
    1. The asphalt concrete mixture shall be transported from the mixing plant to the site in vehicles conforming to the requirements specified herein.

2. Hauling over freshly placed material shall be not permitted until the material has been compacted, as specified, and allowed to cool to atmospheric temperature.
3. Placing and finishing of the asphalt mixture shall be in accordance with WSDOT Standard Specifications Section 5-04.3(7), as modified herein.
4. The nominal compacted depth of any layer of any course shall be within the depth range shown below.

HMA Class	Minimum Thickness, in.	Maximum Thickness, in.
1/2 inch	2.0	3.0
3/4 inch	3.0	4.0
1 inch	3.0	4.0

5. The hot mix asphalt mixture shall not be placed during unsuitable weather or when the surface temperature of the underlying course is less than that specified below. Asphalt shall not be placed unless the atmospheric temperature is at least 50 degrees F and rising. The temperature requirements may be waived by the Engineer, if requested; however, all other requirements including compaction shall be met.

Lift Thickness, T (inches)	Minimum Base Temperature (degrees F)
T > 3	40
2 < T < 3	45
T < 2	55

6. The initial placement of the asphalt concrete mixture shall occur at a temperature suitable for obtaining density, surface smoothness, and other specified requirements but not less than 250 degrees F, unless approved by the Engineer.
7. Upon arrival, the mixture shall be placed to the full width of the paving lane. It shall be struck off in a uniform layer of such depth that, when the mix is properly compacted, shall have the required thickness and conform to the grade and contour indicated. The speed of the paver shall be regulated to eliminate pulling and tearing of the bituminous mat. Unless otherwise permitted, placement of the mixtures shall begin along the centerline of a crowned section or on the high side or areas with a one-way slope. The mixture shall be placed in consecutive adjacent strips having a minimum width of 10-feet except where edge lanes require less width to complete the area.
8. On areas where irregularities or unavoidable obstacles make the use of mechanical spreading and finishing equipment impractical, the mixture may be spread and raked by hand tools.
9. Formation of all joints shall be made to ensure a continuous bond between courses and obtain required density. Joints shall have same texture as other sections of course and meet requirements for smoothness and grade.
10. Roller shall not pass over unprotected transverse end of freshly laid mixture except when necessary to form a temporary stop. After a temporary stop, and prior to continuation of paving, the tapered edge shall be cut back to its full depth and width on a straight line, to expose a vertical face, before placing the adjacent lane.

11. Longitudinal joints which are irregular, damaged, uncompacted, or otherwise defective shall be cut back to expose a clean, vertical, sound, surface for the full depth of the course. Apply tack coat on all newly exposed contact surfaces before placing any fresh mixture against the joint.

### 3.02 COMPACTION OF MIXTURE

- A. After placing, the mixture shall be thoroughly and uniformly compacted by rolling. Surface shall be compacted as soon as possible when the mixture has attained sufficient stability so that the rolling does not cause undue displacement, cracking or shoving. Sequence of rolling operations and the type of rollers shall be at the discretion of the Contractor.
  - B. Compaction shall be completed before the mixture cools below 175 degrees F, unless otherwise approved by the Engineer. Temperature shall be determined using an infrared thermometer by the Engineer.
  - C. The speed of the roller shall, at all times, be sufficiently slow to avoid displacement of the hot mixture and be effective in compaction. Any displacement occurring as a result of reversing the direction of the roller, or from any other cause, shall be corrected at once.
  - D. In areas not accessible to the roller, the mixture shall be thoroughly compacted with mechanical tampers.
  - E. Any mixture that becomes loose and broken, mixed with dirt, contains check-cracking, or in any way defective shall be removed and replaced with fresh hot mixture and immediately compacted to conform to the surrounding area. This work shall be done at Contractor's expense. Skin patching will not be allowed.
  - F. Compaction of the asphalt mixture shall be in accordance with WSDOT Standard Specifications Section 5-04.3(10), as modified herein.
    1. For density determination, each day's production will be treated as a lot. A minimum of ten sublots will be tested each day; 15 if production tonnage is expected to exceed 600 tons for that day. In no case shall the subplot size for density determination exceed 40 tons. Random test locations will be determined according to WSDOT Test Method T 716.
    2. In-place density shall be a minimum of 93% of the reference theoretical maximum density as determined by WSDOT FOP for AASHTO T209.
    3. If nuclear density testing is the basis for acceptance, then the nuclear density testing equipment shall be calibrated in accordance with WSDOT SOP 730. Calibration cores may be omitted at the Engineer's discretion.
    4. Determine reference theoretical maximum density as the moving average of the most recent five determinations for the lot of asphalt concrete being placed according to WSDOT Materials Manual Standard Operating Procedure 729.
    5. Engineer may evaluate cyclic density as described in WSDOT Standard Specifications Section 5-04.3(10)B to assess segregation.
  - G. Joints:
    1. The longitudinal joint in one course shall offset the longitudinal joint in the course immediately below by at least 6-inches; however, the joint in the surface course shall be at the centerline of the pavement if that pavement is to be used by normal car or truck traffic.
-

2. Longitudinal joint density shall be assessed once per subplot in accordance with WSDOT SOP 735. Low density is defined as less than 91 percent of reference maximum density. When placing a single paver width patch, consecutive density tests will be taken on alternating sides of the patch.
3. Transverse joints in one course shall be offset by at least 10-feet longitudinally from transverse joints in the previous course. Transverse joints in adjacent lanes shall be offset a minimum of 10-feet.

### 3.03 JOINT SEALANT

- A. Apply joint sealant to the edges of new paving joints, catch basins, manholes, at the meet lines to concrete structures and as directed by the Engineer.

### 3.04 SURFACE SMOOTHNESS

- A. The completed surface of the wearing course shall conform to the smoothness tolerance requirements of WSDOT Standard Specifications Section 5-04.3(13).

### 3.05 FIELD QUALITY CONTROL

- A. Contractor shall backfill core holes with compacted asphalt or quickset concrete with a minimum compressive strength of 3,000 psi at the Engineer's discretion.
- B. Surface Grades: Grades shall conform to tolerance requirements specified herein, except where a closer tolerance is required for the proper functioning of appurtenant structures and drainage as determined by Engineer.
- C. After the curing, Contractor shall perform a flood test to check if there are any local depressions on the pavement. All asphalt pavement work where water ponds and does not run off within a reasonable amount of time, as determined by the Engineer, shall be fixed to provide proper drainage. Test shall be performed in the Engineer's presence.
- D. Quality Assurance Testing By Engineer:
  1. Contractor shall arrange for Engineer to have access to the mixing plant for verification of weights or proportions, character of materials used and determination of temperatures used in the preparation of asphalt concrete mix.
  2. Contractor shall provide reasonably safe and convenient access, acceptable to Engineer, for inspection and sampling of the AC, and shall cooperate in the inspection and sampling process when requested to do so.

### 3.06 ADJUSTING AND CLEANING

- A. The Contractor shall adjust manholes, utility vaults and boxes, and valve boxes to final grades.
- B. At the conclusion of the work and before final payment is made, Contractor shall remove all debris of every kind from the premises and leave the area broom clean.

### 3.07 PROTECTION

- A. After final rolling, the Contractor shall not permit vehicular traffic on pavement for a minimum of 24 hours until it has cooled and hardened.
- B. The Contractor shall erect barricades to protect paving from traffic until mixture has cooled enough not to become marked.

**END OF SECTION**

This page intentionally left blank

## **PART 1 - GENERAL**

### 1.01 SECTION INCLUDES

- A. Miscellaneous pavement markings.

### 1.02 RELATED SECTIONS

- A. Section 02 41 10 – Site Preparation

### 1.03 REFERENCES

- A. WSDOT – Standard Specifications for Road, Bridge and Municipal Construction; Washington State Department of Transportation, M 41-10; Current edition.
- B. FS TT-P-1952 - Paint, Traffic Black, and Airfield Marking, Waterborne; U.S. General Services Administration, Rev. E, 2007.
- C. FHWA MUTCD - Manual on Uniform Traffic Control Devices for Streets and Highways; U.S. Department of Transportation, Federal Highway Administration; <http://mutcd.fhwa.dot.gov>; current edition.

### 1.04 SUBMITTALS

- A. See Section 01 33 00 for submittal procedures.
- B. Product Data: Manufacturer's data sheets on each product to be used, including:
  - 1. Preparation instructions and recommendations.
  - 2. Storage and handling requirements and recommendations.
  - 3. Installation methods.
- C. Certificates: Submit for each batch of paint and glass beads stating compliance with specified requirements.
- D. Submit manufacturer's certification of the actual volatile organic compound (VOC) content for all pavement paints proposed for use on this project. Submit certification of the actual VOC content for coatings manufactured after 1 September 1987. For coatings manufactured before 1 September 1987, submit VOC content and date of manufacture. VOC content shall be measured in grams per liter by weight of coating as applied excluding water and color added to the tint base.
- E. Submit verification to local air pollution authorities and the State Department of Ecology that paint products furnished meet applicable regulations as to allowable VOC content for the time and place of application and use intended.

### 1.05 DELIVERY, STORAGE, AND HANDLING

- A. Deliver paint in containers of at least 5 gallons accompanied by batch certificate.
- B. Deliver glass beads in containers suitable for handling and strong enough to prevent loss during shipment accompanied by batch certificate.
- C. Store products in manufacturer's unopened packaging until ready for installation.
- D. Store and dispose of solvent-based materials, and materials used with solvent-based materials, in accordance with requirements of local authorities having jurisdiction.

### 1.06 FIELD CONDITIONS

- A. Do not install products under environmental conditions outside manufacturer's absolute limits.

## **PART 2 - PRODUCTS**

### 2.01 MATERIALS

- A. Paint: Materials shall conform to WSDOT Standard Specification Section 9-34.2 for low VOC paint.
- B. Glass Beads: Material shall conform to WSDOT Standard Specification Section 9-34.4
- C. Paint for Obliterating Existing Markings: FS TT-P-1952; black for bituminous pavements, gray for portland cement pavements.
- D. Temporary Marking Tape: Preformed, reflective, pressure sensitive adhesive tape in color(s) required; Contractor is responsible for selection of material of sufficient durability as to perform satisfactorily during period for which its use is required.

## **PART 3 - EXECUTION**

### 3.01 EXAMINATION

- A. Do not begin installation until pavement surfaces have been properly prepared.

### 3.02 PREPARATION

- A. Allow new pavement surfaces to cure for a period of not less than 14 days before application of marking materials.
- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.
- C. Obliteration of existing markings using paint is acceptable in lieu of removal; apply the black paint in as many coats as necessary to completely obliterate the existing markings.
- D. Clean surfaces thoroughly prior to installation.
  - 1. Remove dust, dirt, and other granular surface deposits by sweeping, blowing with compressed air, rinsing with water, or a combination of these methods.
  - 2. Completely remove rubber deposits, existing paint markings, and other coatings adhering to the pavement, by scraping, wire brushing, sandblasting, mechanical abrasion, or approved chemicals.
  - 3. All surfaces shall be dry prior to striping.
- E. Where oil or grease are present, scrub affected areas with several applications of trisodium phosphate solution or other approved detergent or degreaser, and rinse thoroughly after each application; after cleaning, seal oil-soaked areas with cut shellac to prevent bleeding through the new paint.
- F. Establish survey control points to determine locations and dimensions of markings; provide templates to control paint application by type and color at necessary intervals.
- G. Temporary Pavement Markings: When required or directed by Engineer, apply temporary markings of the color(s), width(s) and length(s) as indicated or directed.

1. After temporary marking has served its purpose, remove temporary marking by carefully controlled sandblasting, approved grinding equipment, or other approved method so that surface to which the marking was applied will not be damaged.
2. At Contractor's option, temporary marking tape may be used in lieu of temporary painted marking; remove unsatisfactory tape and replace with painted markings at no additional cost to the Port.

### 3.03 INSTALLATION

- A. Begin pavement marking as soon as practicable after surface has been cleaned and dried.
- B. At the time of application all pavement surfaces shall be free of moisture, oil, dirt, dust, grease and similar foreign materials.
- C. Do not apply paint if temperature of surface to be painted or the atmosphere exceeds the temperature limits recommended by the manufacturer.
- D. Apply in accordance with manufacturer's instructions using an experienced technician that is thoroughly familiar with equipment, materials, and marking layouts.
- E. Comply with FHWA MUTCD manual (<http://mutcd.fhwa.dot.gov>) for details not shown.
- F. Apply markings in locations determined by measurement from survey control points; preserve control points until after markings have been accepted.
- G. Apply uniformly painted markings of color(s), lengths, and widths as indicated on the drawings; true, sharp edges and ends; and in conformance with WSDOT Standard Specification Section 8-22.3(3) for marking application for paint.
  1. Length Tolerance: Plus or minus 3 inches.
  2. Width Tolerance: Plus or minus 1/4 inch.
  3. Letter/Number Height Tolerance: Plus or minus 1 inch.
- H. Use suitable mechanical equipment that provides constant agitation of paint and travels at controlled speeds.
  1. Conduct operations in such a manner that necessary traffic can move without hindrance.
  2. Place warning signs as necessary for alerting traffic.
  3. If paint does not dry within expected time, discontinue paint operations until cause of slow drying is determined and corrected.
  4. Use hand application by pneumatic spray for application of paint in areas where a mobile paint applicator cannot be used.
  5. Distribute glass beads uniformly on the paint lines within ten seconds without any waste, applied at rate of 6 pounds per gallon of paint; if the marking equipment does not have a glass bead dispenser, use a separate piece of equipment adjusted and synchronized with the paint applicator; remove and replace markings having faulty distribution of beads.
- I. Symbols: Use a suitable template that will provide a pavement marking with true, sharp edges and ends, of the design and size indicated.

### 3.04 DRYING, PROTECTION, AND REPLACEMENT

- A. Protect newly painted markings so that paint is not picked up by tires, smeared, or tracked.

- B. Provide barricades, warning signs, and flags as necessary to prevent traffic crossing newly painted markings.
- C. Allow paint to dry at least the minimum time specified by the applicable paint standard and not less than that recommended by the manufacturer.
- D. Remove and replace markings that are applied at less than minimum material rates; deviate from true alignment; exceed length and width tolerances; or show light spots, smears, or other deficiencies or irregularities.
- E. Remove markings in manner to avoid damage to the surface to which the marking was applied, using carefully controlled sand blasting, approved grinding equipment, or other approved method.
- F. Replace removed markings at no additional cost to the Port.

**END OF SECTION**

## **PART 1 - GENERAL**

### **1.01 DESCRIPTION OF WORK**

- A. The work includes the requirements for furnishing and installing all items and components of a completed fence system in conformance with these specifications or as established by the Engineer.

### **1.02 REFERENCES**

- A. ASTM A 53 - Standard Specification for Pipe Steel, Black and Hot-Dipped, Zinc Coated, Welded and Seamless; American Society for Testing and Materials; current edition.
- B. ASTM A 653 – Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy Coated (Galvannealed) by the Hot-Dip Process; American Society for Testing and Materials; current edition.
- C. ASTM F 626 - Standard Specification for Fence Fittings; American Society for Testing and Materials; current edition.
- D. ASTM F 668 - Standard Specification for Polyvinyl Chloride (PVC) and Other Organic Polymer-coated Steel Chain Link Fence Fabric; American Society for Testing and Materials; current edition.
- E. ASTM F 900 - Standard Specification for Industrial and Commercial Swing Gates; American Society for Testing and Materials; current edition.
- F. ASTM F 1043 – Specification for Strength and Protective Coatings on Steel Industrial Chain Link Fence Framework; American Society for Testing and Materials; current edition.
- G. ASTM F 1664 – Standard Specification for Poly(Vinyl Chloride) (PVC) and Other Conforming Organic Polymer-Coated Steel Tension Wire Used With Chain-Link Fence; American Society for Testing and Materials; current edition.
- H. ASTM F 1665 – Standard Specification for Poly(Vinyl Chloride) (PVC) and Other Conforming Organic Polymer-Coated Steel Barbed Wire Used With Chain-Link Fence; American Society for Testing and Materials; current edition.

### **1.03 SUBMITTALS FOR REVIEW**

- A. Product Data: Provide data on fabric, posts, accessories, fittings and hardware.
- B. Shop Drawings: Indicate plan layout, spacing of components, post foundation dimensions, hardware anchorage and schedule of components.
- C. Samples: Submit as specified in Section 01 33 00.

### **1.04 SUBMITTALS FOR INFORMATION**

- A. Manufacturer's Installation Instructions: Indicate installation requirements.

### **1.05 SUBMITTALS FOR CLOSEOUT**

- A. Project Record Documents: Accurately record actual locations of property perimeter posts relative to property lines and easements.

### **1.06 QUALITY ASSURANCE**

- A. Perform Work in accordance with specifications, drawings, and manufacturer's instructions.

### 1.07 QUALIFICATIONS

- A. Manufacturer: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.
- B. The Port reserves the right to have labor personnel it considers inadequate, unskilled or uncooperative, removed from Port work.

### 1.08 JOB CONDITIONS

- A. Clearing of the fence line will be required. Clearing shall consist of the removal and disposal of all vegetation measuring more than one (1) inch in diameter or higher than 15 inches above the ground. Clearing shall also include removal of other forms of non-vegetative debris or materials as required to construct the fence.
  - 1. The clearing width shall be approximately five (5) feet on each side of the chain-link fences.
- B. Grading of the fence line shall be accomplished to eliminate abrupt changes in ground contours. Grubbing incidental to grading shall be accomplished as required. Vegetation resulting from grubbing activities shall be disposed of as cleared material. Boulders, rocks, or excess excavation shall be graded along the fence line or placed adjacent to the clearing on Port of Tacoma property as directed by the Engineer.

## PART 2 - PRODUCTS

### 2.01 CHAIN LINK FENCE

- A. The fence shall be chain link fabric supported on a steel frame, the posts of which may be embedded in concrete foundations.
  - 1. All materials shall be new.
  - 2. All fence and gate fabric, framework, fittings, ties, and barbed wire shall be PVC coated, color black.
  - 3. Fabric: Shall have thermally fused and bonded vinyl clad coating over a galvanized or aluminized steel 9 gage core wire manufactured in accordance with ASTM F 668 for Class 2b. Fabric shall be twisted and barbed on both selvages.
  - 4. Framework:
    - a. Steel material for fence framework shall be hot-dipped galvanized per ASTM A 653/A 653M with a minimum zinc coating weight of 0.90 oz/ft<sup>2</sup>
    - b. Posts, rails and braces shall be in accordance with ASTM A 53 and ASTM F 1043.
      - 1) Line posts shall be 2.375-inch O.D., Schedule 40 pipe @ 3.65 pounds per foot, or "C" section @ 2.78 pounds per foot.
      - 2) End, corner, braced or pull posts shall be 2.875-inch O.D., Schedule 40 pipe @ 5.79 pounds per foot.
      - 3) Swing gate posts shall be sized according to the following tabulation. Pipe sizes are nominal O.D. for Schedule 40 pipe.

Swing Gate Opening (2 in. Frames)	Gate Post Dimensions	Weight, Pounds per Linear Foot
--------------------------------------	-------------------------	-----------------------------------

Single 6 ft. or Double to 12 ft. inclusive	2 7/8 in. O.D.	5.79
Single over 6 ft. to 13 ft. or Double over 12 ft. to 20 ft. inclusive	4 in. O.D.	9.11
Single over 13 ft. to 18 ft. or Double over 20 ft. to 36 ft.	6 5/8 in. O.D.	18.97
36 ft. and over	8 5/8 in. O.D.	24.70

- 4) Top rails and post braces shall be 1.66 inch O.D., schedule 40 pipe @ 2.27 pounds per foot, or Type II "C" section as detailed on the drawings @ 1.35 pounds per foot.
- c. Tension wire shall be zinc and PVC coated in accordance with ASTM F 1664 matching cladding of the fence fabric and shall be No. 7 gage, coil spring, high tensile strength wire, and Marcellled.
5. Fittings: Fittings shall be hot-dipped galvanized pressed steel in accordance with ASTM F 626. All fittings shall be industrial quality. All fittings except nuts and bolts shall be vinyl or powder coated after galvanizing, with 10-15 mils of thermally bonded PVC. After installation, spray all nuts and bolts with two coats of flat alkyd enamel paint (color to match fence) suitable for metal.
6. Gates:
  - a. Chain link gates shall be constructed with chain link fabric fastened to the end bars of the gate frame by tension bars and fabric bands, and to the top and bottom bars of the gate frames by tie wires in the same manner as specified for the chain link fence fabric.
  - b. Gate frames shall be constructed in accordance with ASTM F 900. The corners of the gate frame shall be welded and coated with two (2) coats of GALVACON or approved equal, or shall be manufacturer's standard galvanized cast corner connections.
    - 1) Cross-trussing shall be 3/8-inch galvanized steel adjustable rods.
    - 2) Each gate shall be provided complete with necessary hinges, latch and drop bar locking device designed for the type of gate, posts and lock used.
    - 3) Gates shall have positive-type latching devices with provisions for padlocking. Padlocks will be furnished by the Port of Tacoma.
7. Other Materials:
  - a. Each barbed wire shall conform to the requirements of ASTM F 1665 and shall consist of three strands of 9-gage galvanized and PVC coated wire, twisted with 4-point, 14-gage barbs with the barbs spaced an average of five inches apart.
  - b. Concrete used in anchorage of posts shall be standard ready-mixed concrete from an approved plant and shall develop a minimum compressive strength of 3,000 psi in 28-days.
  - c. Wire ties shall be 9-gauge galvanized and PVC coated steel.

## 2.02 FABRICATION

- A. Pales, rails and posts shall be pre-cut to specified lengths. Impasse rails shall be pre-punched to accept the tamperproof security fasteners. Post shall be pre-punched to accept bracket, rail, and post attachment.
- B. The manufactured galvanized framework shall be subjected to the PermaCoat® thermal stratification coating process (high-temperature, in-line, multi-stage, multi-layer) including, as a minimum, a six-stage pretreatment/wash (with zinc phosphate), an electrostatic spray application of an epoxy base, and a separate electrostatic spray application of a polyester finish. The base coat shall be a thermosetting epoxy powder coating (gray in color) with a minimum thickness of 2 mils. The topcoat shall be a "no-mar" TGIC polyester powder coat finish with a minimum thickness of 2 mils. The color shall be black.

## PART 3 - EXECUTION

### 3.01 GENERAL

- A. The location and alignment of the fence corners and gates shall be as shown on the task order drawings. The Contractor shall locate all intermediate line posts.
- B. The Contractor shall submit shop drawings of fencing, gates and appurtenances. Shop drawings must be approved by the Engineer prior to fabrication or installation.

### 3.02 INSTALLATION

- A. Fencing, gates and appurtenances shall be erected and installed by an organization regularly engaged in this business, employing labor skilled in this type of work to provide a complete security fencing system.
- B. Swing gates shall be fabricated to withstand wind and swing loads. They shall have locking bars to seat into keepers that are set in concrete in ground locations which will hold the gate rigidly in position when closed. Stops which will hold the gate open shall be provided and set in concrete at the location designated by the Engineer. Hinges shall be provided which will allow the gate to swing the entire arc indicated on the drawings. Install gates on gate posts only, do not install on buildings.
- C. Fabric shall be fastened to posts, the top rail and the bottom wire. Wire ties shall be spaced equally at four locations each post and shall be spaced at 24-inches on the top rail and bottom wire.
- D. Top rails shall be continuous. The Contractor shall provide for expansion or contraction of the continuous rail. Expansion and contraction spring couplings shall be installed at intervals of 100 feet maximum.
- E. Posts shall be installed vertically in the concrete with a minimum depth of embedment of 30 inches and at the spacing specified for the type of posts approved for the Project. In unpaved areas, the concrete shall be struck off two inches above the surrounding grade. In paved areas it shall be struck off flush with the paving. The top of the concrete shall be trowelled smooth, with a slight slope away from the posts.
- F. Minor damage to galvanizing of fabric and fence appurtenances shall be repaired by thorough cleaning of the damaged surfaces and the application of "GALVACON," or approved equal, in strict accordance with the manufacturer's recommendations.
- G. If PVC coating is damaged during installation, the Contractor shall replace or repair the material at the Contractor's expense.

- H. Upon completion of the work, the Contractor shall clean the fence of all soiled places and repair marred or abraded areas.
- I. Extension arms for barbed wire shall be sloped toward the outside of the property. The barbed wire shall be attached secure and under tension.

**END OF SECTION**

# APPENDIX A

## **CONSTRUCTION SWPPP SHORT FORM**

The threshold for using the Port of Tacoma’s (Port) short form is a project that proposes to clear or disturb less than one acre of land. Projects falling within this threshold may use this short form instead of preparing a professionally designed Construction Stormwater Pollution Prevention Plan (SWPPP). If project disturbance quantities exceed this threshold, you must prepare of formal Construction SWPPP as part of your submittal package. If your project is within the threshold and includes—or may affect—a critical area, please contact the Port to determine if the SWPPP short form may be used.

# CONSTRUCTION STORMWATER POLLUTION PREVENTION PLAN SHORT FORM

Project Name:

Address:

Contact/Owner:

Phone:

Erosion Control Supervisor:

Phone:

Cell:

Pager:

Emergency (After hours) Contact:

Phone:

Permit No.:

Parcel No.:

## **Required Submittals**

A Construction SWPPP consists of both a project narrative and a site plan. The project narrative describes existing conditions on the site, the proposed conditions, and how construction site runoff will be managed until final site stabilization is achieved. Any additional relevant information should be included in the project narrative. All Best Management Practices (BMPs) that will be utilized onsite must be included as part of the project narrative and provided (electronically or hard copy) as part of the submittal package. If additional BMPs beyond those included in the Washington Department of Ecology's (Ecology) Western Washington Stormwater Management Manual (Ecology SWMM) or the City of Tacoma's (City) Stormwater Management Manual (City SWMM) are proposed to be used, a narrative and appropriate details describing the BMP (its function, installation method, and maintenance activities) will be required.

The site plan is a drawing which shows the location of the proposed BMPs to control erosion and sedimentation during and after construction activities.

**PROJECT NARRATIVE**

The Construction SWPPP Short Form narrative must be completed at part of the submittal package. Any information described, as part of the narrative, should also be shown on the site plan.

**Note:** From October 1 through April 30, clearing, grading, and other soil disturbing activities shall only be permitted by special authorization from the Port.

**A. Project Description (Check all that apply)**

- |  |  |   |
|--|--|---|
| <input type="checkbox"/> New Structure | <input type="checkbox"/> Building Addition | <input type="checkbox"/> Grading/Excavation |
| <input type="checkbox"/> Paving        | <input type="checkbox"/> Utilities         | <input type="checkbox"/> Other:             |

1. Total project area (square feet)
2. Total proposed impervious area (square feet)
3. Total existing impervious area (square feet)
4. Total proposed area to be disturbed (square feet)
5. Total volume of cut/fill (cubic yards)

Additional Project Information:

**B. Existing Site Conditions (Check all that apply)**

1. Describe the existing vegetation on the site. (Check all that apply)
 

<input type="checkbox"/> Forest	<input type="checkbox"/> Pasture/field grass	<input type="checkbox"/> Pavement	<input type="checkbox"/> Landscaping	<input type="checkbox"/> Brush
<input type="checkbox"/> Trees	<input type="checkbox"/> Other:			
2. Describe how surface water (stormwater) drainage flows across/from the site. (Check all that apply)
 

<input type="checkbox"/> Sheet Flow	<input type="checkbox"/> Gutter	<input type="checkbox"/> Catch Basin	<input type="checkbox"/> Ditch/Swale	<input type="checkbox"/> Storm Sewer
<input type="checkbox"/> Stream	<input type="checkbox"/> Other:			
3. Describe any unusual site condition(s) or other features of note.
 

<input type="checkbox"/> Steep Grades	<input type="checkbox"/> Large depression	<input type="checkbox"/> Underground tanks	<input type="checkbox"/> Springs
<input type="checkbox"/> Easements	<input type="checkbox"/> Existing structures	<input type="checkbox"/> Existing utilities	<input type="checkbox"/> Other:

**C. Adjacent Areas (Check all that apply)**

1. Check any/all adjacent areas that may be affected by site disturbance and fully describe below in item 2:

- Streams\*       Lakes\*       Wetlands\*       Steep slopes\*  
 Residential Areas       Roads       Ditches, pipes, culverts       Other:

*\* If the site is on or adjacent to a critical area (e.g., waterbody), the Port may require additional information, engineering, and other permits to be submitted with this short form.*

2. Describe how and where surface water enters the site from properties located upstream:

---

---

---

---

---

3. Describe the downstream drainage path from the site to the receiving body of water (minimum distance of 0.25 mile [1320 feet]). (E.g., water flows from the site into a curb-line, then to a catch basin at the intersection of X and Y streets. A 10-inch pipe system conveys water another 1000 feet to a wetland.) Include information on the condition of the drainage structures.

---

---

---

---

---

**D. Soils (Check all that apply)**

The intent of this section is to identify when additional soils information may be required for applicants using this short form. There are other site-specific issues that may necessitate a soils investigation or more extensive erosion control practices. The Port will determine these situations on a case-by-case basis as part of their review.

1. Does the project propose infiltration? Infiltration systems require prior Port approval.

- Yes       No

2. Does the project propose construction on or near steep slopes (15% or greater)?

- Yes       No

If infiltration is proposed for the site or steep slopes (15% or greater) have been identified, the Port will require soils information as part of project design. The applicant must contact a soil professional or civil engineer that specializes in soil analysis and perform an in-depth soils investigation. If the Yes box is checked for either question, the Port may not permit the use of this short form.

**E. Construction Sequencing/Phasing**

1. Construction sequence: the standard construction sequence is as follows:
  - Mark clearing/grading limits.
  - Install initial erosion control Best Management Practices (BMPs) (e.g., construction entrance, silt fence, catch basin inserts, etc.).
  - Clear, grade, and fill project site as outlined in the site plan while implementing and maintaining proper temporary erosion and sediment control BMPs simultaneously.
  - Install permanent erosion protection as described in the specifications (e.g., impervious surfaces, landscaping, etc.).
  - Remove temporary erosion control methods as permitted. Do not remove temporary erosion control until permanent erosion protection is fully established.

List any changes from the standard construction sequence outlined above:

---

---

---

---

2. Construction phasing: if construction is going to occur in separate phases, please describe:

---

---

---

---

---

**F. Construction Schedule**

1. Provide a proposed construction schedule (dates construction starts and ends, and dates for any construction phasing.)

**Start Date:**

**End Date:**

Interim Phasing Dates:

Wet Season Construction Activities: Wet season occurs from October 1 to April 30. Please describe construction activities that will occur during this time period.

---

---

**Note:** Additional erosion control methods may be required during periods of increased surface water runoff.

**2. Site plan** (see Figure 1, page 6)

A site plan, to scale, must be included with this checklist that shows the following items:

- a. Address, Parcel Number, Permit Number, and Street Names
- b. North Arrow
- c. Indicate boundaries of existing vegetation (e.g., tree lines, grassy areas, pasture areas, fields, etc.)
- d. Identify any onsite or adjacent critical areas and associated buffers (e.g., wetlands, steep slopes, streams, etc.).
- e. Identify any FEMA base flood boundaries and Shoreline Management boundaries.
- f. Show existing and proposed contours.
- g. Delineate areas that are to be cleared and/or graded.
- h. Show all cut and fill slopes, indicating top and bottom of slope catch lines.
- i. Show locations where upstream run-on enters the site and locations where runoff leaves the site.
- j. Indicate existing surface water flow direction(s).
- k. Label final grade contour and indicate proposed surface water flow direction and surface water conveyance systems (e.g., pipes, catch basins, ditches, etc.).
- l. Show grades, dimensions, and direction of flow in all (existing and proposed) ditches, swales, culverts, and pipes.
- m. Indicate locations and outlets of any dewatering systems (usually to sediment trap).
- n. Identify and locate all erosion control methods to be used during and after construction.

**ONSITE FIELD VERIFICATION OF ACTUAL CONDITIONS IS REQUIRED.**

**Figure 1.** (to be worked out with Engineering Dept.)

---

## GUIDELINES FOR EROSION CONTROL ELEMENTS

This SWPPP must contain the 12 required elements, as required by Ecology. Check off each element as it is addressed in the SWPPP short form and/or on your site plan.

- 1. Mark Clearing Limits
- 2. Establish Construction Access
- 3. Control Flow Rates
- 4. Install Sediment Controls
- 5. Stabilize Soils
- 6. Protect Slopes
- 7. Protect Drain Inlets
- 8. Stabilize Channels and Outlets
- 9. Control Pollutants
- 10. Control Dewatering
- 11. Maintain BMPs
- 12. Manage the Project

The following is a brief description of each of the 12 required elements of a SWPPP. If an element does not apply to the proposed project site, please describe why the element does not apply. Applicable BMPs are listed with each element and in Table 1. Please note that this list is not a comprehensive list of BMPs available for small construction projects, but erosion and sediment control techniques most pertinent to small construction sites are included here. More detailed information on construction BMPs can be found in Ecology's SWMM Volume II and the City's SWMM Volume II (Ecology 2005; City of Tacoma 2012). Please provide hard copies of the BMPs that will be used for the project and include as part of this Construction SWPPP. BMPs that may be used if needed can be noted as being contingent in the event additional erosion control is needed. Describe any additional BMPs that will be utilized onsite and add them to the SWPPP short form.

For phased construction projects, clearly indicate erosion control methods to be used for each phase of construction.

*Element #1 – Mark Clearing Limits*

All construction projects must clearly mark any clearing limits, sensitive areas and their buffers prior to beginning any land disturbing activities, including clearing and grading. Clearly mark the limits both in the field and on the site plans. Limits shall be marked in such a way that any trees or vegetation that is to remain will not be harmed.

Applicable BMPs include:

- BMP C101: Preserving Natural Vegetation
- BMP C102: Buffer Zones
- BMP C103: High Visibility Plastic or Metal Fence
- BMP C104: Stake and Wire Fence

The BMP(s) being proposed to meet this element are:

---

---

**OR**

This element is not required for this project because:

---

---

---

---

*Element #2 – Establish Construction Access*

All construction projects subject to vehicular traffic shall provide a means of preventing vehicle “tracking” soil from the site onto streets or neighboring properties. Limit vehicle traffic on- and off-site to one route if possible. All access points shall be stabilized with a rock pad construction entrance or other Port-approved BMP. The applicant should consider placing the entrance in the area for future driveway(s), as it may be possible to use the rock as a driveway base material. The entrance(s) must be inspected weekly, at a minimum, to ensure no excess sediment buildup or missing rock.

Applicable BMPs include:

- BMP C105: Stabilized Construction Entrance
- BMP C106: Wheel Wash
- BMP C107: Construction Road/Parking Area Stabilization

The BMP(s) being proposed to meet this element are:

---

---

**OR**

This element is not required for this project because:

---

---

---

---

*Element #3 – Control Flow Rates*

Protect properties and waterways downstream of the project site from erosion due to increases in volume, velocity, and peak flow of stormwater runoff from the project site.

Permanent infiltration facilities shall not be used for flow control during construction unless specifically approved by the Environmental Department. Sediment traps can provide flow control for small sites by allowing water to pool and allowing sediment to settle out of the water.

Applicable BMPs include:

- BMP C207: Check Dams
- BMP C240: Sediment Trap

The BMP(s) being proposed to meet this element are:

---

---

**OR**

This element is not required for this project because:

---

---

---

---

*Element 4 – Install Sediment Controls*

Surface water runoff from disturbed areas must pass through an appropriate sediment removal device prior to leaving a construction site or discharging into a waterbody. Sediment barriers are typically used to slow stormwater sheet flow and allow the sediment to settle out behind the barrier.

Sediment controls must be installed/constructed prior to site grading.

Applicable BMPs include:

- BMP C208: Triangular Silt Dike
- BMP C232: Gravel Filter Berm
- BMP C233: Silt Fence
- BMP C235: Straw Wattles

The BMP(s) being proposed to meet this element are:

---

---

**OR**

This element is not required for this project because:

---

---

---

---

*Element #5 – Stabilize Soils*

Stabilize exposed and unworked soils by applying BMPs that protect the soils from raindrop impact, flowing water, and wind.

From October 1 through April 30, no soils shall remain exposed or unworked for more than 2 days. From May 1 to September 30, no soils shall remain exposed or unworked for more than 7 days. This applies to all soils whether at final grade or not.

Applicable BMPs include:

- BMP C120: Temporary and Permanent Seeding
- BMP C121: Mulching
- BMP C122: Nets and Blankets
- BMP C123: Plastic Covering
- BMP C140: Dust Control

The BMP(s) being proposed to meet this element are:

---

---

**OR**

This element is not required for this project because:

---

---

---

---

*Element #6 – Protect Slopes*

Protect slopes by diverting water at the top of the slope. Reduce slope velocities by minimizing the continuous length of the slope.

Applicable BMPs include:

- BMP C200: Interceptor Dike and Swale
- BMP C204: Pipe Slope Drains
- BMP C207: Check Dams

The BMP(s) being proposed to meet this element are:

---

---

**OR**

This element is not required for this project because:

---

---

---

---

*Element #7 – Protect Drain Inlets*

All operable storm drain inlets must be protected during construction so that stormwater runoff does not enter the conveyance system without first being filtered or treated to remove sediment. Install catch basin protection on all catch basins within 500 feet downstream of the project.

Applicable BMPs include:

- BMP C220: Storm Drain Inlet Protection

The BMP(s) being proposed to meet this element are:

---

---

**OR**

This element is not required for this project because:

---

---

---

---

*Element #8 – Stabilize Channels and Outlets*

Stabilize all temporary onsite conveyance channels. Provide stabilization to prevent erosion of outlets, adjacent stream banks, slopes, and downstream reaches at the conveyance system outlets.

Applicable BMPs include:

- BMP C202: Channel Lining
- BMP C209: Outlet Protection

The BMP(s) being proposed to meet this element are:

---

---

**OR**

This element is not required for this project because:

---

---

---

---

*Element #9 – Control Pollutants*

Handle and dispose of all pollutants, including demolition debris and other solid wastes in a manner that does not cause stormwater contamination. Provide cover and containment for all chemicals, liquid products (including paint), petroleum products, and other materials. Handle all concrete and concrete waste appropriately.

Applicable BMPs include:

- BMP C150: Materials on Hand
- BMP C151: Concrete Handling
- BMP C152: Sawcutting and Surface Pollution Prevention
- BMP C153: Material Delivery, Storage and Containment

The BMP(s) being proposed to meet this element are:

---

---

**OR**

This element is not required for this project because:

---

---

---

---

*Element #10 – Control Dewatering*

Clean, non-turbid dewatering water, such as groundwater, can be discharged to the stormwater system provided the dewatering flow does not cause erosion or flooding of receiving waters.

Applicable BMPs include:

- BMP C150: Materials on Hand

The BMP(s) being proposed to meet this element are:

---

---

**OR**

This element is not required for this project because:

*Element #11 – Maintain BMPs*

Maintain and repair temporary erosion and sediment control BMPs as needed. Inspect all BMPs at least weekly and after every storm event.

Remove all temporary erosion and sediment control BMPs within 30 days after final site stabilization or if the BMP is no longer needed. Any sediment trapped during construction activities should be removed or stabilized onsite. No sediment shall be discharged into the stormwater drainage system or any natural conveyance system (e.g., streams).

Applicable BMPs include:

- BMP C160: Certified Erosion and Sediment Control Lead

The BMP(s) being proposed to meet this element are:

---

---

**OR**

This element is not required for this project because:

---

---

---

---

*Element #12 – Manage the Project*

Phase development projects to prevent soil erosion and the transport of sediment from the project site during construction. Coordinate all work prior initial construction with subcontractors and other utilities to ensure no areas are worked prematurely.\

A designated erosion and sediment control person is required for all construction projects. This person is responsible for ensuring that the project’s erosion and sediment control BMPs are appropriate for the site and are functioning properly. They are also responsible for updating the SWPPP as necessary as site conditions warrant. They must be available 24 hours a day to ensure compliance.

Applicable BMPs include:

- BMP C160: Certified Erosion and Sediment Control Lead
- BMP C162: Scheduling
- BMP C180: Small Project Construction Stormwater Pollution Prevention

The BMP(s) being proposed to meet this element are:

---

---

**OR**

This element is not required for this project because:

---

---

---

---

**Table 1. Applicable BMPs for the 12 Elements of a SWPPP**

Element #1 – Mark Clearing Limits		
BMP C101	Preserving Natural Vegetation	
BMP C102	Buffer Zones	
BMP C103	High Visibility Plastic and Wire Fence	
BMP C104	Stake and Wire Fence	
Element #2 – Establish Construction Entrance		
BMP C105	Stabilized Construction Entrance	
BMP C106	Wheel Wash	
BMP C107	Construction Road/Parking Area Stabilization	
Element #3 – Control Flow Rates		
BMP C207	Check Dams	
BMP C240	Sediment Trap	
Element #4 – Install Sediment Controls		
BMP C208	Triangular Silt Trap	
BMP C232	Gravel Filter Berm	
BMP C233	Silt Fence	
BMP C235	Straw Wattles	
Element #5 – Stabilize Soils		
BMP C120	Temporary and Permanent Seeding	
BMP C121	Mulching	
BMP C122	Nets and Blankets	
BMP C123	Plastic Covering	
BMP C140	Dust Control	
Element #6 – Protect Slopes		
BMP C200	Interceptor Dike and Swale	
BMP C204	Pipe Slope Drains	
BMP C207	Check Dams	
Element #7 – Protect Drain Inlets		
BMP C220	Storm Drain Inlet Protection	
Element #8 – Stabilize Channels and Outlets		
BMP C202	Channel Lining	
BMP C209	Outlet Protection	
Element #9 – Control Pollutants		
BMP C150	Materials on Hand	

Element #9 – Control Pollutants, cont.		
BMP C151	Concrete Handling	
BMP C152	Sawcutting and Surfacing Pollution Prevention	
BMP C153	Materials, Delivery, Storage and Containment	
Element #10 – Control Dewatering		
BMP C150	Materials on Hand	
Element #11 – Maintain BMPs		
BMP C160	Certified Erosion and Sediment Control Lead	
Element #12 – Manage the Project		
BMP C160	Certified Erosion and Sediment Control Lead	
BMP C162	Scheduling	
BMP C180	Small Project Construction Stormwater Pollution Prevention	

## REFERENCES

City of Tacoma. 2012. Stormwater Management Manual 2012 Edition. Public Works/ Environmental Services, Maintenance Division, Tacoma, Washington.

Washington State Department of Ecology (Ecology). 2005. Stormwater Management Manual for Western Washington. Water Quality Program, Lacey, Washington.