**QUESTIONS & RESPONSES #02**
**PROCUREMENT NUMBER: 092026-1059**
**RFP/RFQ TITLE: TOTE Terminal Pavement Maintenance and Repair**
**CONTACT: Maddie Pattin, Contracts & Procurement Analyst**
**EMAIL: procurement@portoftacoma.com**
**PHONE NUMBER: 253-888-4744**
**QUESTIONS DUE DATE: Tuesday, November 10, 2026 @ 2:00 PM (PDT)**
**Q&A ISSUE DATE: 11/06/2026**

| # | Question | Answer | Question # |
|---|---|---|---|
| 1 | You're also requesting estimates for the construction materials testing and special inspections scope of work with procurement? | Materials testing services will be provided for and paid by the Port, per Section 01 45 00, 1.04B | email |
| 2 | Looking through this document, we would like to pursue the joint sealants. Does that include performing all asphalt work? The procurement summary describes joint sealants, but in the specs, it sounds like all asphalt work is involved. Can you please clarify. | Joint sealant (s) are included in Bid Item #3 - 2.5" HMA Paving, per Section 01 20 00, 1.07C. | email |
| 3 | Do you already have a subcontractor in place to provide pavement quality testing/assurance through density testing of the newly compacted asphalt concrete pavement? | Materials testing services will be provided for and paid by the Port, per Section 01 45 00, 1.04B | email |
| 4 | section 32 12 16-7 E "Recycled Asphalt Pavement is prohibited"<br>On past projects at the port, this has never been a requirement. Is it the Port's intention to proceed with this requirement? There would be a savings to the Port if RAP was incorporated in the HMA. | An addendum will be issued, replacing the entire paving section (32 12 16) with an updated specification, which allows the use of RAP. | Q-004294 |
| 5 | When do you hope this paving will happen? With the weather window shrinking, I am curious when you plan to perform the scope of work. | The contractor shall complete the entire scope of work no later than 180 days from execution of the contract, per Section 00 52 00, 3.0. | Q-004304 |
| 6 | If we were to grind on a friday night, with paving happening on Saturday, what time on a friday night could we begin work? | An addendum will be issued to clarify the Facility operating hours. Additionally, the Contractor shall coordinate its activities through the Engineer, per Section 01 30 00, Paragraph 1.03.A | Q-004304 |