PORT OF TACOMA

WAPATO CREEK BRIDGE AND CULVERT REMOVAL

PROJECT NO. 201070.01 CONTRACT NO. 071198

PORT COMMISSIONERS:

DON MEYER
KRISTIN ANG
RICHARD P. MARZANO
DEANNA KELLER
JOHN McCARTHY


PORT STAFF:

JOHN WOLFE
Chief Executive Officer

DAKOTA CHAMBERLAIN, PE Chief Facilities Development Officer

TREVOR THORNSLEY, PE Director of Engineering

STAN RYTER, PE Senior Project Manager



		DRAWING INDEX	
SHEET NO.	DWG NO.	DRAWING TITLE	
		GENERAL	
1	G1.1	COVER SHEET	
2	G1.2	ABBREVIATIONS AND GENERAL NOTES	
3	G1.3	CONSTRAINTS AND SEQUENCING PLAN	
		SURVEY	
4	SV1.1	SURVEY - PHASE 1	
5	SV1.2	SURVEY - PHASE 2	
	· · · · · · · · · · · · · · · · · · ·	DEMOLITION	
6	D1.1	EROSION CONTROL AND DEMOLITION PLAN - PHASE 1	
7	D1.2	EROSION CONTROL AND DEMOLITION PLAN - PHASE 2	
8	D1.3	EROSION CONTROL AND DEMOLITION NOTES & DETAILS	
9	D1.4	EROSION CONTROL AND DEMOLITION NOTES & DETAILS	
		CIVIL	
10	C1.1	CIVIL/SITE PLAN - PHASE 1	
11	C1.2	CIVIL/SITE PLAN - PHASE 2	
12	C1.3	CIVIL/SITE DETAILS	
13	C2.1	GRADING AND DRAINAGE PLAN - PHASE 1	
14	C2.2	GRADING AND DRAINAGE PLAN - PHASE 2	
15	C2.3	GRADING AND DRAINAGE SECTIONS	
16	C2.4	GRADING AND DRAINAGE DETAILS OUTFALL REPAIR	
17	C2.5	GRADING AND DRAINAGE DETAILS CREEK RESTORATION	
18	C2.6	GRADING AND DRAINAGE DETAILS STORMFILTER	
		STRUCTURAL	
19	S1.1	BRIDGE GENERAL NOTES	
20	S1.2	BRIDGE LAYOUT	
21	S2.1	FOUNDATION PLAN	
22	S2.2	TYPICAL DRILLED SHAFT DETAILS	
23	S2.3	ABUTMENT DETAILS	
24	S2.4	WING WALL DETAILS	
25	S3.1	TYPICAL SECTION	
26	S3.2	FRAMING PLAN AND CAMBER DIAGRAM	
27	S3.3	GIRDER DETAILS	
28	S3.4	GIRDER AND BEARING DETAILS	
29	S4.1	TRAFFIC BARRIER 1	
30	S4.2	TRAFFIC BARRIER 2	
31	S4.3	APPROACH SLAB DETAILS 1 OF 2	
32	S4.4	APPROACH SLAB DETAILS 2 OF 2	
33	S5.1	BAR BENDING DIAGRAMS	


OVED:	AWB 06/01/20	Ser E Colo					N
00	CHECKED BY DATE	A COSC AND	1	2407 North 31st Street, Suite 100	e 100	Dort of	
Mr 6/19/20	SEK 06/01/20	The state of the s	ゴ	Tacoma, Washington 98407 (253) 396-0150 Fax (253) 396-0162	96-0162	Tacom	eu
ENG. DATE	TOR ENG. DATE PROJ. ENGR DATE	The state of the s				P.O. BOX 1837 TACOMA, WA 98401 (253)383-5841	01 (253)383-5841
Y: rlambe	rlambert Jun 17, 2020	The special special state of the special speci	MARK:	REVISION: B	BY:	APPR: DATE:	
RESS: ONE SI	TCUM PLAZA	STORY TOWN					
TACOM	TACOMA, WA 98401-1837						

 COVER SHEET
 COVER SHEET
 OB/01/20

 HIP: 20N
 RANGE: 03E
 SECTION: 01
 PRINTED BY: rlambert Jun 17, 2020


 IRZ: WA83-SF
 VERT: MLLW 19.18' @ TIDE 22 1933
 PORT ADDRESS: ONE SITCUM PLAZA

 L: 15
 DRAWING SCALE: AS SHOWN
 TACOMA, WA 98401-1837



GENERAL NOTES

- 1. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH PERMIT CONDITIONS, CITY OF TACOMA STANDARDS, AND WASHINGTON STATE DEPARTMENT OF TRANSPORTATION (WSDOT) STANDARD SPECIFICATIONS 2018.
- 2. BEFORE ANY CONSTRUCTION MAY BEGIN, THE CONTRACTOR SHALL HOLD A PRE-CONSTRUCTION MEETING WITH THE PORT AND CITY OF TACOMA PERMIT DEPARTMENT AND INSPECTION STAFF.
- 3. A COPY OF THESE APPROVED PLANS AND ALL AMENDMENTS SHALL BE ON THE CONSTRUCTION SITE AT ALL TIMES.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ADEQUATE SAFEGUARDS, SAFETY DEVICES, PROTECTIVE EQUIPMENT, FLAGGERS, SPOTTERS, AND ANY OTHER NEEDED ACTIONS TO PROTECT THE LIFE, HEALTH, AND SAFETY OF THE PUBLIC, AND OF THE CONTRACTOR. ANY WORK WITHIN THE TRAVELED RIGHT OF WAY THAT MAY INTERRUPT NORMAL TRAFFIC FLOW SHALL REQUIRE AT LEAST ONE FLAGGER FOR EACH LANE OF TRAFFIC AFFECTED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DEVELOPING TEMPORARY TRAFFIC CONTROL PLANS, PERMITTING, AND COORDINATION TO PROVIDE ADEQUATE TEMPORARY TRAFFIC CONTROL ACCORDING TO THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES, WSDOT STANDARD PLANS, AND CITY PERMITS.
- 5. PRIOR TO THE START OF EXCAVATION, THE CONTRACTOR SHALL CALL 1-800-424-5555 FOR PUBLIC UTILITY LOCATES, A PRIVATE UTILITY LOCATE COMPANY FOR PRIVATE UTILITY LOCATES, AND COORDINATE UTILITY WORK WITH THE UTILITY SERVICE PROVIDER.
- THE EXISTENCE, LOCATION AND CHARACTERISTICS OF UNDERGROUND UTILITIES SHOWN ON THESE PLANS HAS BEEN OBTAINED FROM A REVIEW OF AVAILABLE RECORD DATA. NO REPRESENTATION IS MADE AS TO THE ACCURACY OR COMPLETENESS OF SAID UTILITY INFORMATION. THE CONTRACTOR SHALL POTHOLE OR OTHERWISE CONFIRM CONDITIONS. IF CONDITIONS DIFFER FROM THOSE SHOWN ON THE PLANS, THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND SHALL NOT BEGIN CONSTRUCTION UNTIL THE CHANGED CONDITIONS HAVE BEEN EVALUATED. THE CONTRACTOR SHALL TAKE PRECAUTIONARY MEASURES TO PROTECT THE UTILITY LINES SHOWN AND ANY OTHER LINES NOT OF RECORD OR NOT SHOWN ON THESE PLANS.
- 7. TACOMA POWER HAS OVERHEAD 230kV TRANSMISSION LINE IN THE PROJECT AREA AND 13.8kV AND 115kV OVERHEAD DISTRIBUTION ALONG ALEXANDER AVENUE. BEWARE AND UNDERSTAND WAC 296-155-53408 WHEN WORKING NEAR ENERGIZED ELECTRICAL CONDUCTORS AND EQUIPMENT. THE SYSTEM HAS POLES, DOWN GUYS, ANCHORS, OVERHEAD AND UNDERGROUND ELECTRICAL CONDUCTORS AND MISCELLANEOUS FIXTURES AND DEVICES ON AND OFF SITE.
- TACOMA WATER FACILITIES MUST REMAIN ACCESSIBLE AT ALL TIMES. ANY DAMAGES TO TACOMA WATER FACILITIES WILL BE REPAIRED BY TACOMA WATER CREWS AT THE EXPENSE OF THE CONTRACTOR.





ALL STATES




06/ 06/ 08/


DATE


ATO CREEK
CULVERT RE BRIDGE

()



Kpff





NOTES:

1.) VERTICAL DATUM: PORT OF TACOMA
BENCHMARK: BRASS DISK ON THE NORTH SIDE OF THE 11TH STREET BRIDGE EAST OF
THE INTERSECTION WITH MILWAUKEE WAY.
BENCHMARK NO. 846

ELEVATION = 19.18'

2.) BASIS OF BEARINGS FOR THIS SURVEY IS THE WASHINGTON STATE COORDINATE SYSTEM, SOUTH ZONE (4602) BASED ON THE PORT OF TACOMA SITTS & HILL ENGINEERS, INC. MONUMENT NETWORK MAP.


3.) UTILITY LOCATIONS SHOWN ARE PER FIELD LOCATED UTILITY PAINT MARKS & REFERENCE MAPS MADE AVAILABLE BY THE VARIOUS UTILITY PROVIDERS. UNLESS INDICATED, DEPTHS OF UTILITY LINES ARE NOT AVAILABLE. UTILITY LOCATES ON ALL PUBLIC AND PRIVATE UTILITIES ARE REQUIRED AND SHALL BE FIELD VERIFIED PRIOR TO CONSTRUCTION.


4.) THIS MAP DOES NOT REPRESENT A BOUNDARY SURVEY.

5.) FIELDWORK WAS COMPLETED ON APRIL 25, 2018.

LEGEND:

LEGEND:	
	CURB LINE
· · · · · · · · · · · · · · · · · · ·	EDGE OF PAVEMENT
SD	STORM LINE
	SANITARY SEWER LINE
w	
NGAS	
BPBP-	
	CYCLONE FENCE LINE
———AP———AP——	OVERHEAD UTILITY LINES EDGE OF WATER
	ORDINARY HIGH WATER
MHHV	MEAN HIGH OR HIGH WATER
<u>n</u> .	SIGN
<u> </u>	BOLLARD
P	ELECTRICAL VAULT
	GUY ANCHOR
- 0 _è	POWER POLE W/DROP
	POWER POLE
<u></u>	SANITARY MANHOLE WITH STRUCTURE
ு © ©	STORM MANHOLE WITH STRUCTURE
Ⅲ/∅	CATCH BASIN/AREA DRAIN
⊞/∜	WATER METER
Q	FIRE HYDRANT
	WATER VAULT
X	WATER VALVE
- ©	MONITORING WELL
	TEST BORE HOLE
₽ •	
8	FIRE DEPARTMENT CONNECT TELECOMMUNICATION MARKER
∘ TM	
0	DECIDUOUS TREE -PERIMETER REPRESENTS DRIPLINE






2407 North 31st S
Tacoma, Washing (253) 396-0150 F
(253) 396-0150 F
(253) 396-0150 F
(253) 396-0150 F



3	3 608	>	WAPATO CREEK	CRE	EX]
	2	BRIDGE	ND CNI	VERT	BRIDGE AND CULVERT REMOVAL		. ,	1
> 0	1		SUR	SURVEY			1 m	37
S	OF 33		PHA	PHASE 2			DIRECTOR	出
/CONS:	071198	TDWNSHIP: 20N	RANGE: 03E	03E	SECTION: 01		PRINTED B	D B
	201070,01	DAT-HRZ: WA83-SF VERT: MLLW 19,18' @ TIDE 22 1933 PURT ADDR	VERT	MLLW 1	9,18' @ TIDE	22 1933	PURT A	UR
لت ا	BID SET	PARCEL: 15		DRAWIN	DRAWING SCALE: AS SHOWN	SHDWN		
		TON LINE ON ANOTATION THE BOOT OF TACOMINATED AND SHALL NOT	במטממ בוי	DIVOE	TUE DODT OF TA	CIMA AMO	NIVHU	TO



DEMOLITION NOTES


- CONTRACTOR SHALL CALL FOR UTILITY LOCATES AND LOCATE EXISTING UTILITIES IN THE ROADWAY AND ON-SITE PRIOR TO BEGINNING ANY DEMOLITION OR EXCAVATION.
- 2. REFERENCE DOCUMENTS AND RECORD DRAWINGS HAVE BEEN MADE AVAILABLE AS PART OF THE CONTRACT SPECIFICATIONS. SEE REFERENCE DOCUMENTS FOR EXISTING CONDITIONS AND DETAIL FOR DEMOLITION OF THE EXISTING BRIDGE STRUCTURE ON TOP OF EXISTING CULVERT.
- 3. EXISTING CREEK SHALL NOT BE DISTURBED BEYOND THE LIMITS
- IDENTIFIED, OR AS DIRECTED BY THE PORT.

 4. ALL EXISTING UTILITIES SHALL BE PROTECTED UNLESS
- OTHERWISE NOTED.
- COORDINATE WITH PORT FOR ECOLOGY BLOCK REMOVAL (NIC). EXISTING FENCE POSTS TO BE REMOVED SHALL BE CUT AND GROUND TO EXISTING GRADE (NIC).
- DEWATERING SEQUENCE SHOWN REPRESENTS A POSSIBLE CONSTRUCTION SEQUENCE. THE SEQUENCE IS FOR INFORMATION ONLY AND NOT INTENDED TO DICTATE METHODS OF CREEK DIVERSION. A DEWATERING PLAN SHALL BE DEVELOPED AND MAINTAINED BY CONTRACTOR WITHIN THE CONSTRAINTS IDENTIFIED ON G1.3, AND CURRENT TIDE INFORMATION. NO IN-WATER WORK SHALL BE PERFORMED WITHIN 2 DAYS OF A SIGNIFICANT RAIN EVENT TO LIMIT DEWATERING. WAPATO CREEK FLOWS: 10-YEAR FLOOD (10% ANNUAL CHANCE): 176 CFS

				REVISI		
		4		MARK:		
A VIDE A		100		The Server of th	SOLONAL ENGLA	
20	DATE		DATE			

	APPROVE
PHASE 1	WAPATO CREEK BRIDGE AND CULVERT REMOVAL
PHASE 1	BRID

KEY PLAN



DEMOLITION NOTES

- 1. CONTRACTOR SHALL CALL FOR UTILITY LOCATES AND LOCATE EXISTING UTILITIES IN THE ROADWAY AND ON-SITE PRIOR TO BEGINNING ANY DEMOLITION OR EXCAVATION.
- 2. REFERENCE DOCUMENTS AND RECORD DRAWINGS HAVE BEEN MADE AVAILABLE AS PART OF THE CONTRACT SPECIFICATIONS. SEE REFERENCE DOCUMENTS FOR EXISTING CONDITIONS AND DETAIL FOR DEMOLITION OF THE EXISTING BRIDGE STRUCTURE ON TOP OF EXISTING CULVERT.
- 3. EXISTING CREEK SHALL NOT BE DISTURBED BEYOND THE LIMITS IDENTIFIED, OR AS DIRECTED BY THE PORT.
- 4. ALL EXISTING UTILITIES SHALL BE PROTECTED UNLESS
- OTHERWISE NOTED. 5. COORDINATE WITH PORT FOR ECOLOGY BLOCK REMOVAL (NIC).
- 6. EXISTING FENCE POSTS TO BE REMOVED SHALL BE CUT AND GROUND TO EXISTING GRADE (NIC).
- 7. DEWATERING SEQUENCE SHOWN RÉPRESENTS A POSSIBLE CONSTRUCTION SEQUENCE. THE SEQUENCE IS FOR INFORMATION ONLY AND NOT INTENDED TO DICTATE METHODS OF CREEK DIVERSION. A DEWATERING PLAN SHALL BE DEVELOPED AND MAINTAINED BY CONTRACTOR WITHIN THE CONSTRAINTS IDENTIFIED ON G1.3, AND CURRENT TIDE INFORMATION. NO IN-WATER WORK SHALL BE PERFORMED WITHIN 2 DAYS OF A SIGNIFICANT RAIN EVENT TO LIMIT DEWATERING. WAPATO CREEK FLOWS: 10-YEAR FLOOD (10% ANNUAL CHANCE): 176 CFS







Construction of the Constr	
>>>>	FENCE DEMO (NIC
	UTILITY DEMO
	PAVEMENT SAWCU
	SILT CURTAIN
	COFFERDAM

LIMITS OF R.O.W. WORK

PROJECT LIMITS

- 4 INSTALL SCREENED PUMP WITH SEDIMENT TRAP
- 5 DEWATERING LINE WITH ENERGY DISSIPATION AT DISCHARGE POINT
- 6 REMOVE EXISTING FENCE (NIC)
- 7 REMOVE EXISTING GATE (NIC)
- 8 SAWCUT PAVEMENT


- 12 DEMOLISH AND DISPOSE OF EXISTING 96" CMP CULVERT
- (13) REMOVE 18 LF EXISTING 12" CONC PIPE
- 14) REMOVE TRAFFIC SIGN AND SALVAGE (NIC)
- 15 RELOCATE VAULT AND UNDERGROUND POWER, SEE C1.2
- 16) REMOVE EXISTING BRIDGE

KEY PLAN


PHASE 1

TEMPORARY EROSION AND SEDIMENT CONTROL (TESC) GENERAL NOTES:


- THE IMPLEMENTATION OF THESE PLANS AND THE CONSTRUCTION, REGULAR REVIEW, MAINTENANCE, REPLACEMENT, AND CONSTRUCTION STORMWATER POLLUTION PREVENTION PLAN (SWPPP), AND UPGRADING THESE FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR IN ACCORDANCE WITH PROJECT SPECIFICATIONS AND PLANS UNTIL ALL CONSTRUCTION IS APPROVED AND ACCEPTED BY THE ENGINEER. AT THE DISCRETION OF PORT ENVIRONMENTAL STAFF SWPP MEASURES OBSERVED AS INADEQUATE WILL BE BROUGHT TO THE CONTRACTORS ATTENTION FOR REVISION/MODIFICATION. PORT ENVIRONMENTAL STAFF; ANITA FICHTHORN (253) 495-2834, AFICHTHORN@NWSEAPORTALLIANCE.COM
- THE TESC FACILITIES SHOWN ON THIS PLAN SHALL BE CONSTRUCTED PRIOR TO ALL CLEARING AND DEMOLITION SO AS TO ENSURE THAT TRANSPORT OF SEDIMENT TO SURFACE WATERS, DRAINAGE SYSTEMS, AND ADJACENT PROPERTIES IS MINIMIZED. THE TYPICAL WET SEASON RUNS FROM OCTOBER THROUGH APRIL 30, AND THE DRY SEASON FROM MAY 1 THROUGH SEPTEMBER 30.
- THE TESC FACILITIES SHALL BE INSPECTED DAILY BY THE TESC SUPERVISOR AND MAINTAINED TO ENSURE CONTINUED PROPER FUNCTIONING IN ACCORDANCE WITH THE SPECIFICATIONS. WRITTEN RECORDS SHALL BE KEPT OF TESC INSPECTIONS WEEKLY.
- CONTRACTOR SHALL MAINTAIN EROSION CONTROL MEASURES AT ALL TIMES TO THE REQUIREMENTS OF THE PERMITS, SPECIFICATIONS AND MINIMUM REQUIREMENTS SHOWN IN PLANS.
- THE TESC MEASURES SHOWN ON THESE PLANS ARE MINIMUM REQUIREMENTS. SHOULD TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES, AS SHOWN ON THE PLANS, BECOME INADEQUATE, THE CONTRACTOR SHALL INSTALL BMPS AND/OR FACILITIES AS NECESSARY TO PROTECT ADJACENT PROPERTIES, WATERBODIES, CITY OF TACOMA DRAINAGE SYSTEM, AND EXISTING PORT DRAINAGE SYSTEMS MEETING THE APPROVAL OF THE ENGINEER.
- AS A GENERAL RULE, ANY AREAS OF EXPOSED SOILS, INCLUDING EMBANKMENTS, THAT WILL NOT BE DISTURBED FOR TWO DAYS DURING THE WET SEASON OR SEVEN DAYS DURING THE DRY SEASON SHALL BE IMMEDIATELY STABILIZED WITH THE APPROVED TESC BMP METHODS.
- INLET PROTECTION SHALL BE INSPECTED AFTER EACH STORM EVENT AND CLEANED OR REPLACED WHEN 13 FULL.
- 8. THE CONTRACTOR SHALL PROTECT STOCKPILE AND EXCAVATION AREAS FROM THE RELEASE OF SEDIMENT. STOCKPILES SHALL BE COVERED AT ALL TIMES WHILE NOT IN USE TO KEEP THE STORED MATERIAL DRY, AS SHOWN IN DETAIL.
- 9. ALL NON-SALVAGED MATERIAL REMOVED FROM THE SITE SHALL BE PLACED OR DISPOSED OF AT A PERMITTED SITE. CONTRACTOR SHALL OBTAIN CHARACTERIZATION DOCUMENTATION FROM THE ENGINEER FOR ALL MATERIAL PRIOR TO HAUL AND DISPOSAL.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR FULL COMPLIANCE WITH THE WASHINGTON STATE DROPPING LOAD OR OTHER MATERIALS COVERING LAWS (RCW 46.51.655.3/4).
- 11. PAVED AREAS SHALL BE SWEPT AS NECESSARY TO PREVENT SEDIMENT AND DUST TRACKING ONTO THE
- 12. PREVENTATIVE MEASURES TO MINIMIZE THE WIND TRANSPORT OF SOIL SHALL BE TAKEN WHEN SEDIMENT TRANSPORTED BY THE WIND IS LIKELY TO BE DEPOSITED IN DRAINAGE WAYS, WATER RESOURCES, OR NON-PORT PROPERTY.
- 13. ALL TESC MEASURES SHALL BE REMOVED AND DISPOSED OF AT AN APPROVED SITE UPON PROJECT COMPLETION.









2 STOCKPILE PROTECTION DETAIL




DELETERIOUS MATERIAL FROM LEACHING INTO WAPATO CREEK AND TO PREVENT WAPATO CREEK OR TIDAL WATERS FROM ENTERING THE PROJECT AREA. UPON COMPLETION OF THE PROJECT, ALL COFFERDAM MATERIALS SHALL BE REMOVED. HEIGHT TO WIDTH RATIO SHALL BE NO GREATER THAN 2:1.






STRAW WATTLE DETAIL



00

|Apple

D1.1



NOTES:

- 1. INSERT SHALL BE
 INSTALLED IN ALL
 OPERATIONAL CATCH
 BASINS WITHIN 500 FEET
 OF WORK LIMITS PRIOR
 TO CLEARING AND
 GRADING ACTIVITY, OR
 UPON PLACEMENT OF A
 NEW CATCH BASIN.
- 2. FILTERS SHALL BE INSPECTED AFTER EACH STORM EVENT AND CLEANED OR REPLACED WHEN IT IS 1/3 FULL.

INLET PROTECTION DETAIL

NTS